



SBI INFRA MANAGEMENT SOLUTIONS PVT.LTD.

(A wholly owned subsidiary of SBI)

**TENDERS ARE INVITED FOR PROPOSED AIR CONDITIONING WORK AT
SBI GANESH CHOKDI BRANCH, ANAND.**

FROM

**AUTHORISED DEALER OF RECOMMENDED MAKECARRIER, HITACHI, DAIKIN,
VOLTAS) IN GUJARAT**

PART – B :PRICE BID

TENDER SUBMITTED BY:

NAME : _____

ADDRESS : _____

DATE : _____

ARCHITECT:

Ar MAYUR SHAH

803, TOP FLOOR,

CENTER POINT,

ALKAPURI,

VADODARA – 390007.

(M) : 9377213854, 0265-2331172

Email : msa.baroda@gmail.com



INDEX

Tender documents are in two parts (Volumes) i.e. Part – A and Part – B

PART – B (PRICE BID)

Sr. No.	Description	Page No.
1	<i>Cover page</i>	1
2	<i>Index</i>	2
3	<i>Bill of Quantities</i>	3 - 5



BOQ : Interior Decoration and Furnishing work : AC WORK of GANESH CHOKDI BRANCH & ATM, ANAND for State Bank of India.					
SR. NO.	DESCRIPTION	QTY.	UNIT	RATE	AMOUNT
	All A.C should be of either carrier, hitachi, daikin, voltas make.				
	All A.C should be same brand irrespective of individual capacity. Mention the model no. and brand of A.C and R22 gas.				
	Have copper condensing coil and scroll compressor for cassette A.C.				
	Star rating should conform to guideline by BEE. latest guideline (JAN 2018).				
	Contractor shall mark location of indoor and outdoor unit and coordinate with other agencies for electric supply.				
	Contractor shall provide authorized dealership certificate from concerned company				
1	Providing approved quality make hi wall split A.C of 1.0 ton capacity (copper condenser & minimum 3 star rating) with remote, 4mt of copper pipe (FOR 2 ATM & 1 SERVER ROOM)	3	Nos.		
2	Installing pressure testing, gas charging, vacuuming commissioning 1.0 ton hi wall split A.C (indoor & outdoor unit). (installation should be done as per company specification.)	3	Nos.		
3	Providing approved quality make hi wall split A.C of 2.0 ton capacity (copper condenser & minimum 3 star rating) with remote, 4mt of copper pipe (FOR BANK HALL)	2	Nos.		



4	Installing pressure testing, gas charging, vacuuming commissioning 2.0 ton hi wall split A.C (indoor & outdoor unit). (installation should be done as per company specification.)	2	Nos.		
5	Providing approved quality make Cassette A.C of 2.0 ton capacity (copper condenser & minimum 3 star rating) with remote, 4mt of copper pipe (FOR BANK HALL)	3	Nos.		
6	Installing pressure testing, gas charging, vacuuming commissioning 2.0 ton Cassette A.C (indoor & outdoor unit). (installation should be done as per company specification.)	3	Nos.		
7	Providing & fixing 16 gauge MS powder coated wall hung/floor mounted (table top) A.C outdoor unit stand of minimum 24" length.	8	Nos.		
8	Providing & laying concealed refrigerant copper piping with proper 6/9 mm nitrile rubber insulation (k-flex, armcell make) & FRLS (RR cable, Finolex or equivalent make) 1.5/2.5 sq mm 3/4 core power control cable (depending on AC make & capacity & as per company specification) from indoor unit to outdoor unit. the laying shall be done using clamps & hangers to fix pipes to wall/slab piping shall not be fixed to false ceiling channel. quantity may differ considering site conditions.	45	MTR		
9	Providing & concealed water drainage piping from indoor to specified outdoor location using upvc (Astral, Supreme, Dutron make) pipe quantity may differ considering site conditions.	60	MTR		



	Note :- All zharis or chases in wall/columns/slabs, cone cutting etc. of conduits the filling of the same will be done by the contractor including all necessary material &labour.				
	TOTAL				