

PROPOSED INTERIORS FOR STATE BANK OF INDIA,

P&SB MEHDIPATNAM BRANCH

SCHEDULE OF QUANTITIES AND DETAILED SPECIFICATIONS.

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Unit</u>	<u>Qty.</u>	<u>Rate</u>	<u>Amount.</u>
A					
I.	INTERIOR WORKS:				
1.0	FIXED FURNITURE:				
1.1	FULL HEIGHT PARTITIONS:	Sq.M.	90		
	Providing and fixing metal stud dry wall partition with following specifications: The Partition will be fully opaque OR partly opaque and partly glazed as per specific site conditions and drawings.				
	(a) Supporting system comprising of 51mm / 50mm x 35mm / 34mm x 0.5mm metal studs at 600mm c/c and 51mm / 50mm x 32mm x 0.5mm metal tracks at floor, middle, door and ceiling level with joints staggered to avoid through joints. The vertical members should touch the ceiling with horizontal ceiling channel at slab / beam bottom. The rate should also include necessary strengthening with studs / tracks or channels at doors and other openings.				
	(b) 12mm MDF Exterior Grade Board fixed on both sides with 25mm dry wall screws for the entire height of the partition.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	Unit	<u>Qty.</u>	Rate	<u>Amount.</u>
	<p>(c) Partition from floor level upto 2350mm level to have 100mm skirting with 1 mm thick laminate silver colour at bottom + from 100mm to 300mm level to have 1mm Glossy Laminate (blue color) + from 300mm level to 950mm level to have 1mm Glossy Laminate (white color) + from 950mm level to 1100mm level 1mm Glossy Laminate (blue color) + from 1100mm level to 2250mm level to have 1mm Textured Glossy Laminate (white color) OR 8mm clear float glass as detailed in (d) below + from 2250mm level to 2350mm level 1mm Glossy Laminate (blue color) on both sides as shown in drawing.</p> <p>(d) Partition to have 8mm clear float glass instead of 1mm Textured Glossy Laminate fixed with 85mm x 18mm around MDF Exterior Grade jamb and 12mm x 12mm MDF Exterior Grade button beading on both sides of the glass, to a neat finish as per drawings and directions etc., complete.</p> <p>(e) Partition above 2350mm level to have 1 MM LAMINATE on both sides as shown in drawing.</p> <p>(f) All exposed surfaces of MDF Exterior Grade members to have 1.0 MM THICK LAMINATE FINISH.</p> <p>(g) All sections used should adhere to the manufacturers guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified sections.</p>				
1.2	HALF HEIGHT PARTITIONS:	Sq.M.	20		
	<p>Same as item 1.1 above, but for height of 1200mm from finished floor level, to a neat finish as per drawings and directions etc., complete and the following:</p> <p>(a) 6mm thick acrylic solid surface capping of 75mm on top, 25mm bands of 6mm acrylic solid surface on both sides of the partitions horizontally and vertically upto skirting as per drawings and directions etc., complete.</p>				

SIGNATURE OF THE BIDDER

<u>S.No.</u>	<u>Item. / Particulars.</u>	Unit	<u>Qty.</u>	Rate	<u>Amount.</u>
	(b) Partition from floor level upto 1200mm level on both sides to have 100mm Skirting of 1mm thick laminate , (silver) at bottom + from 100mm to 300mm level to have 1mm Glossy Laminate (blue color) + from 300mm level to 950mm level to have 1mm Glossy Laminate (white color) + from 950mm level to 1050mm level 1mm Glossy Laminate (blue color) + from 1050mm level to 1200mm level to have 6mm thick acrylic solid surface on both sides as shown in drawing.				
	(c) The cost to include all materials and hardware required etc., as per site conditions. The rate is for a finished item of work etc., complete as directed.				
1.3	DOORS:				
1.3.1	DOORS IN PARTITIONS:				
1.3.1	35MM DOORS IN PARTITIONS:	Sq.M.	18		
	Providing and fixing 35mm thick solid core flush shutter with 85mm x 18mm MDF Exterior Grade jamb around and 12mm x 12mm MDF Exterior Grade button beading fixed 1mm Laminate as specified on both sides and 8mm clear float glass with 3M privacy film fixed as per drawing with 50mm x 18mm MDF Exterior Grade jamb around the glass opening and 12mm x 12mm MDF Exterior Grade beading for fixing of glass on both sides.				
	The rate to include necessary hardware viz., door stopper, door buffer, pair of " H " type handles, Mortise Dead Lock and Euro Profile Cylinder - Key and Knob 70mm SS, 4 Nos. SS 2 ball-bearing hinges - (127mm x 76mm x 2.5mm), door closer (all of approved make and quality), 1.0 MM LAMIMATE finish for all exposed surfaces of MDF Exterior Grade members, etc., complete as directed.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	Unit	<u>Qty.</u>	Rate	<u>Amount.</u>
1.4	FIXED GLASS WORKS: (12MM TOUGHENED GLASS WORK WITH MAIN ENTRANCE DOOR AND GLASS PARTITION DOORS)	Sq.M.	13		
	Providing, making and fixing in position Fixed 12mm toughened glass as fixed glass from Floor to available Ceiling level along with Main Entrance Door and for Partitions. The glass is to be fixed with patch fittings and all the edges of the glass have to be polished for a smooth finish. The work includes cost of all materials, approved hardware, making necessary template before toughening of glass and fixing the same as per site conditions to a neat finished work as per drawings and directions etc., complete.				
1.5	12MM TOUGHENED GLASS MAIN ENTRANCE DOOR AND PARTITION DOORS:	Sq.M.	8		
	Providing, making and fixing in position Fixed 12mm toughened glass openable shutters work as per specifications given below and for the openings mentioned. Main Entrance Glass Work comprising of Door opening of approximate size 1800mm x 2250mm - 2400mm in two pieces, and Partition Doors of approximate size 900 - 1000mm x 2250mm - 2400mm. The entire work to be done as per site conditions with following specifications etc., complete as directed.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	Unit	<u>Qty.</u>	Rate	<u>Amount.</u>
	<p>(a) Entrance door - Providing, fixing in position glazed entrance Double door and Single door with patch fitting or approved make (Double Door approx. Size: 1800mm - 1500mm x 2400mm - 2250mm and Single Door approx. Size: 900mm - 1200mm x 2400mm - 2250mm) using 12mm / 10mm toughened glass edge polished. The Door to consist of Heavy Duty Floor spring, Upper Patch, Bottom Patch, Lock Keeper Plate, Euro Profile Cylinder (EPC), "H" Type Handle 32 x 600mm, Corner Lock and the side fixed glass to have 2 Nos. Bottom Patch and 2 Nos. Upper Patch for each door to a neat finish etc., complete as per drawing.</p> <p>(b) The work includes cost of all materials, approved hardware, making necessary template before toughening of glass and fixing the same as per site conditions to a neat finished work as per drawings and directions etc., complete.</p>				
1.6	WALL PANELLING:				
1.6.1	WALL PANELLING IN BANKING HALL:	Sq.M.	40		
	<p>Same as item 1.1 above, but for Wall Panelling. The basic frame work to comprise all cladding specified only from one side to a neat job as per drawings and directions etc., complete.</p> <p>(a) Providing 18mm thick MDF Exterior Grade jamb for door and window openings of suitable depth as per site conditions.</p> <p>(b) All exposed surfaces of MDF Exterior Grade members to have 1 MM LAMINATE finish.</p>				
1.6.2	WALL PANELLING WITH SPECIAL HIGH GLOSS LAMINATE FOR E-LOBBY:	Sq.M.	26		

<u>S.No.</u>	<u>Item. / Particulars.</u>	Unit	<u>Qty.</u>	Rate	<u>Amount.</u>
	Same as item 1.4 above to be clad with 1mm High Gloss Laminate (Laminate Base Rate Rs - 600/- Sq.M.) from one side to a neat finish as per drawings and directions etc., complete.				
1.7	COLUMN PANELLING:	Sq.M.	17		
	<p>Providing and fixing metal stud column panelling with following specifications:</p> <p>(a) Supporting system comprising of 51mm / 50mm x 35mm / 34mm x 0.5mm metal studs at 600mm c/c and 51mm / 50mm x 32mm x 0.5mm metal tracks at floor, middle, lintel level and ceiling level with joints staggered to avoid through joints. The vertical members should touch the ceiling with horizontal ceiling channel at slab / beam bottom. The rate should also include necessary strengthening with studs / tracks or channels at doors and other openings.</p> <p>(b) 12mm MDF Exterior Grade Board fixed on all four sides with 25mm dry wall screws for the entire height of the partition.</p> <p>(c) Column Panelling from floor level upto 2350mm level to have 100mm Skirting of 1mm thick silver colour at bottom + from 100mm to 2350mm level to have 1mm Glossy Laminate (Beech Wood color) on two longer sides of the column as shown in drawing.</p> <p>(d) Column Panelling to have 8mm toughened glass with 1mm glossy Laminate in blue color fixed with 12mm x 12mm MDF Exterior Grade button beading on two shorter sides of the column, to a neat finish as per drawings and directions etc., complete.</p> <p>(e) Column Panelling above 2350mm level to have 1MM LAMINATE on all four sides as shown in drawing.</p> <p>(f) All exposed surfaces of MDF Exterior Grade members to have 1 MM LAMINATE finish.</p>				

SINGNATURE OF THE BIDDER

<u>S.No.</u>	<u>Item. / Particulars.</u>	Unit	<u>Qty.</u>	Rate	<u>Amount.</u>
	(g) All sections used should adhere to the manufacturers guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified sections.				
	Providing and fixing in position 8mm toughened lacquered glass (colour - Black or blue) for glass partition. The work to include making necessary template for all the glasses and then cutting the glass to correct size, making all the necessary holes, cuts etc., and then toughening the same. The cost to include all hardware required viz., single corner patch, bracket etc., The approximate size of each glass will be 1950mm x 450mm to 1200mm as per site conditions. The rate is for a finished item of work etc., complete as directed.				
1.9	FALSE CEILING:				
	Providing, making and fixing in position the following types of different false ceilings with different materials as specified below for a finished item of work as per drawings and directions etc., complete.				
1.9.1	GRID FALSE CEILING:	Sq.M.	160		
	Providing & Fixing of Mineral Fibre Acoustical Suspended Ceiling System with 15mm Tiles and Exposed GRID. The tiles should have Humidity Resistance (RH) of 90% - 99%, NRC 0.5, Light Reflectance $\geq 87\%$, Thermal Conductivity $k = 0.052 - 0.057$ w/m K, Colour White, Fire Performance UK Class 0 / Class 1 (BS 476 pt - 6 & 7) in module size of 600 x 600 x 16mm, suitable for Green Building application, with Recycled content of 30% - 45%.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	Unit	<u>Qty.</u>	Rate	<u>Amount.</u>
	<p>The tile shall be laid on Microline / Silhouette profile grid system with 15mm - 16mm white flanges incorporating a 6mm central reveal in white/black colour and with a web height of 38mm and a load carrying capacity of minimum 8 Kgs/M2 & minimum pull out strength of 100 Kgs. Microline / Silhouette, Main Runners & Cross Tees to have mitred ends & "birdsmouth" notches to provide mitred cruciform junctions. The T Sections have a Galvanizing of 90 grams per M2 and need to be installed with Suspension system as per manufacturers details.</p> <p>The Instalation to comprise main runner spaced at 1200mm centres securely fixed to the structural soffit using US Boral / Gyproc / Armstrong suspension system (specifications below) at 1200mm maximum centre. The First/Last suspension system at the end of each main runner should not be greater than 450mm from the adjacent wall.</p> <p>Flush fitting 1200mm long cross tees to be</p>				
1.9.2	PLAIN FALSE CEILING:	Sq.M.	70		
	<p>Providing and fixing Concealed Grid suspended ceiling system of 12.5mm Gypsum Boards / Standard Plaster Boards fixed to ceiling Frame Work as per manufacturers instructions and details for a concealed grid key lock suspended ceiling system consisting of following:</p>				

<u>S.No.</u>	<u>Item. / Particulars.</u>	Unit	<u>Qty.</u>	Rate	<u>Amount.</u>
	<p>(a) 27 x 37 x 1.6mm Soffit Clip, 5mm suspension rod / 25 x 10 x 0.5mm Ceiling Angle, adjustable spring loaded suspension clip / 2.64mm dia Connecting Clip, 20 x 28 x 30 x 0.5mm Perimeter Channel, Top Cross Rail of 3000mm long of 0.55BMT Furring Channel / 15 x 45 x 15 x 0.9mm Intermediate Channel and 4000mm long made of 0.5mm BMT the Top Cross Rail / 80 x 26 x 0.5mm Ceiling Section to be suspended from ceiling at every 1200mm and Furring / Intermediate Channel to be fixed to Top Cross Rail / Ceiling Section at every 600mm to make a grid of 1200 x 600mm.</p> <p>(b) All sections used should adhere to the manufacturers guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified sections.</p> <p>(c) Further the rates to include cutouts for lighting fixtures / AC grilles / Fire Alarm Detectors etc., along with necessary strengthening and supports for fixing of these. The board joints are to be flush finished with jointing compound and paper tape, and painting the surface with required putty ,primer & painting , etc., complete as directed.</p>				
1.9.3	VERTICAL FACES IN FALSE CEILING:	Sq.M.	25		
	Same as item 1.9.2 above but for vertical faces in false ceiling as per drawing including cut outs for AC grilles etc., complete as directed.				
1.10	WORK TABLE:				
1.10.1	WORK TABLE: (WITH 6MM ACRYLIC SOLD	Sq.M.	3		

<u>S.No.</u>	<u>Item. / Particulars.</u>	Unit	<u>Qty.</u>	Rate	<u>Amount.</u>
	<p>Providing, making and placing in position worktables made in 18mm MDF Exterior Grade Board for all members except table top and 25mm block board for table top and Ready Made Foot Rest, Key Board Tray and vertical supports at approximately every 1350mm length. The Table top of 25mm Block Board to have extra thickening with 18mm x 50mm MDF Exterior Grade Board and front vertical facia to have 12mm x 43mm MDF Exterior Grade Board lipping cladded with 6mm thick acrylic solid surface for the entire table top and the front facia and remaining all exposed faces to have 1mm Glossy Laminate as specified. The unexposed surfaces of MDF Exterior Grade members to have 0.8 mm thick laminate etc., complete as directed.</p> <p>The table to have a three drawer unit for every 1350mm length as per drawing. All faces of MDF Exterior Grade Board to have 12mm MDF Exterior Grade lipping. The cost to include all materials, labour, necessary hardware viz., drawer channels, SS handles, set locks etc., to a neat job as per directions and directions etc., complete.</p>				
1.11	STORAGE UNITS:	Sq.M.	27		

<u>S.No.</u>	<u>Item. / Particulars.</u>	Unit	<u>Qty.</u>	Rate	<u>Amount.</u>
	<p>Providing, making and placing in position Storage Units with horizontal partitions of 1200mm high abutting wall and 750mm high as back credenza or abutting partition made in 18mm MDF Exterior Grade Board to all members except table top and 25mm block board for table top. The Table top of 25mm Block Board to have extra thickening with 18mm x 50mm MDF Exterior Grade Board and front vertical facia to have 12mm x 43mm MDF Exterior Grade Board lipping cladded with 6mm thick acrylic solid surface for the entire table top and the front facia and remaining all exposed faces to have 1mm Glossy Laminate as specified.</p> <p>All other exposed faces of the unit to have 1mm Glossy Laminate as specified and all unexposed faces to have 0.8mm Laminate finish for all other exposed surfaces of MDF Exterior Grade members and all necessary hardware viz., 'W' or wing hinges, locks, handles, tower bolts etc., and MDF Exterior Grade beading 36mm x 36mm at top and MDF Exterior Grade edge lipping 18mm x 12mm etc., as per drawings and directions etc., complete.</p>				
2.0	LOOSE FURNITURE:				
2.1	EXECUTIVE OFFICE TABLES:				
2.1	BRANCH HEAD TABLE:	Each.	1		
	Providing, making and placing in position Executive Table and Side Table of approximate size 2100mm x 900mm x 750mm + 1050mm x 450mm x 750mm with following specifications.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	Unit	<u>Qty.</u>	Rate	<u>Amount.</u>
	(a) Main Table and side Table top and to be made in 25mm block board with 6mm thick acrylic solid surface. The front side of the table to have a " C " made with 2 x 18mm thick MDF Exterior Grade Board cladded with 6mm acrylic solid surface on the front and the verticals towards the modesty panel. The modesty panel to have 18mm MDF Exterior Grade Board cladded with 1mm glossy Laminate (blue color) + 8mm clear toughened glass as specified.				
	(b) The " L " shaped table top of 25mm Block Board to have extra thickening with 18mm x 50mm MDF Exterior Grade Board and front vertical facia to have 12mm x 43mm MDF Exterior Grade Board lipping cladded with 6mm thick acrylic solid surface for the entire table top and the front facia and remaining all exposed faces to have 1mm Glossy Laminate as specified.				
	(c) All other members to be with 18mm MDF Exterior Grade Board and all exposed faces of the table to have 6mm acrylic solid surface OR 1mm Glossy Laminate as specified above to be used.				
	(d) All the edges of 18mm MDF Exterior Grade Board to have 18mm x 12mm MDF Exterior Grade edge lipping.				
	(e) One readymade CPU mobile pedestal.				
	(f) One Molded Key Board Tray with channels etc.,				

<u>S.No.</u>	<u>Item. / Particulars.</u>	Unit	<u>Qty.</u>	Rate	<u>Amount.</u>
	<p>(g) One Three Drawer Unit made with 18mm MDF Exterior Grade Board and 12mm MDF Exterior Grade Board. The unit to have one vertical filing drawer at bottom and two equal drawers on top. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and 18mm x 12mm MDF Exterior Grade edge lipping etc.,</p> <p>(h) One Side Table with shutter unit of 400mm made with 18mm MDF Exterior Grade Board and 19mm plywood with necessary hardware viz., ' W ' hinges, handles, locks, tower bolts, etc., and 18mm x 12mm MDF Exterior Grade edge lipping etc.,</p> <p>(i) All the unexposed faces to have 1.00mm Laminate finish.</p> <p>(j) Ready Made Modular Foot Rest - 400mm x 350mm x 65mm.</p> <p>The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.</p>				
2.2	OTHER OFFICER's EXECUTIVE TABLES:				
2.2.1	OFFICER's AND SIDE EXECUTIVE TABLES:	Each.	4		
	<p>Providing, making and placing in position Executive Table and Side Table of approximate size 1650mm - 1550mm x 750mm x 750mm + 1050mm x 450mm x 750mm with following specifications.</p> <p>(a) Main Table and side Table top and to be made in 25mm block board with 6mm thick acrylic solid surface. The front side of the table to have a inverted " U " made with 2 x 18mm thick MDF Exterior Grade Board cladded with 6mm acrylic solid surface on the front and the verticals towards the modesty panel. The modesty panel to have 18mm MDF Exterior Grade Board cladded with 1mm Glossy Laminate and 1mm Laminate as specified.</p>				

SINGNATURE OF THE BIDDER

<u>S.No.</u>	<u>Item. / Particulars.</u>	Unit	<u>Qty.</u>	Rate	<u>Amount.</u>
	(b) The " L " shaped table top of 25mm Block Board to have extra thickening with 18mm x 50mm MDF Exterior Grade Board and front vertical fascia to have 12mm x 43mm MDF Exterior Grade Board lipping clad with 6mm thick acrylic solid surface for the entire table top and the front fascia and remaining all exposed faces to have 1mm Glossy Laminate as specified.				
	(c) All other members to be with 18mm MDF Exterior Grade Board and all exposed faces of the table to have 6mm acrylic solid surface OR 1mm Glossy Laminate as specified above to be used.				
	(d) All the edges of 18mm MDF Exterior Grade Board to have 18mm x 12mm MDF Exterior Grade edge lipping.				
	(e) One readymade CPU mobile pedestal.				
	(f) One Molded Key Board Tray with channels etc.,				
	(g) One Three Drawer Unit made with 18mm MDF Exterior Grade Board and 12mm MDF Exterior Grade Board. The unit to have one vertical filing drawer at bottom and two equal drawers on top. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and 18mm x 12mm MDF Exterior Grade edge lipping etc.,				
	(h) One Side Table with shutter unit of 400mm made with 18mm MDF Exterior Grade Board with necessary hardware viz., ' W ' hinges, handles, locks, tower bolts, etc., and 18mm x 12mm MDF Exterior Grade edge lipping etc.,				
	(i) All the unexposed faces to have 1.0mm Laminate finish.				

SINGNATURE OF THE BIDDER

<u>S.No.</u>	<u>Item. / Particulars.</u>	Unit	<u>Qty.</u>	Rate	<u>Amount.</u>
	(j) Ready Made Modular Foot Rest - 400mm x 350mm x 65mm. The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.				
2.3	GRAHAK mitra TABLE:	Each.	1		
	Providing, making and placing in position Grahak (a) Main Table Top of 25mm Block Board to have (b) The front of the table to have a 600mm x (c) All other members to be with 18mm MDF (d) All the edges of 18mm MDF Exterior Grade (e) 2 Nos. readymade CPU mobile pedestals. (f) 2 Nos. Molded Key Board Trays with channels (g) 2 Nos. Three Drawer Unit made with 18mm (i) All the unexposed faces to have 0.8mm (j) 2 Nos. Ready Made Modular Foot Rests - The cost to include all materials, labour etc., for a				
2.4	SINGLE WINDOW COUNTERS:	Each.	3		
	Providing, making and placing in position Single (a) The overall size of each Single Window (b) Tabletop of main table and side table to have (c) All other members to be with 18mm MDF (d) All the edges of 18mm MDF Exterior Grade (e) One readymade CPU mobile pedestal. (f) One Molded Key Board Tray with channels etc., (g) One Three Drawer Unit made with 18mm MDF (h) One Side Table with shutters made with 25mm (i) All the unexposed faces to have 0.8mm (j) Ready Made Modular Foot Rest - 400mm x (k) All wooden members to have minimum two The cost to include the " L " shaped Single Window				
2.5	12MM TOUGHENED GLASS DIVIDERS FOR	Each.	2		
	Providing, making and fixing in position 12mm				
2.6	12MM TOUGHENED GLASS ON	Each.	3		
	Providing, making and fixing in position 12mm				

<u>S.No.</u>	<u>Item. / Particulars.</u>	Unit	<u>Qty.</u>	Rate	<u>Amount.</u>
2.7	FLOOR MOUNTED WRITTING DESK	Each.	3		
	Providing, making and placing in position Wall				
	(a) A Octogonal support boxing is to be made				
	(b) The Writing Desk Circular Top to have 12mm				
	(c) All members to be with 12mm / 18mm MDF				
	(d) All the edges of 12mm / 18mm MDF Exterior				
	(e) All the unexposed faces to have 0.8mm				
	The cost to include all materials, labour etc., for a				
3.0	OTHER WORKS:				
3.1	PLASTIC EMULSION PAINTING:	Sq.M.	200		
	Cleaning the surface of the wall & then applying				
3.2	ROLLER BLINDS:	Sq.M.	15		
	Providing and fixing in position of Roller Blinds of				
3.3	DESIGNER FILM WORK:	Sq.M.	20		
	Providing and fixing in position Designer Film				
3.8	ENTRANCE - VINYL SCRAPER MATTING:	Sq.M.	12		
	Providng, fixing in position 3M™ Nomad™				
3.9	ACP CLADDING:	Sq.M.	30		
	Supplying and fixing aluminium composite				
	TOTAL FOR INTERIOR WORKS:			RS.	
	DISCOUNT IF ANY:			RS.	
	NETT TOTAL:			RS.	
	Rupees _____			RS.	

Signature and Seal of the Contractor.