

Price Bid : Outside Repair & Renovation & Painting work (SBI HOUSE)

SI No	Item Description	Unit	Qty	Rate	Amount
1	Mechanical scraping with Buffing & Vacuum Machine and cleaning of wall surface. The rate is inclusive of machineries, labours, tools & tackles, scaffolding. All the existing furnitures are to be covered with proper plastic sheet	Sqft	28000		
2	To apply water base primer after repair of cracks, repairing of broken plaster, application of Dulux 2 K chemical compound. Moisture meter to be used for checking of moisture content and should not be more than 16 %.	Sqft	5000		
3	Application of Dulux Flexi base coat over the treated surface	Sqft	5000		
4	Plaster of cracks, repairing of broken plaster (1: 4) cement sand ratio, application of Dulux 2 K , after removal of damaged plaster and disposal of debris 1km away from the compound(Rate with scaffolding)	Sqft	3000		
5	Application of one coat of ALKALI BLOCK Primer (ICI / Nerolac) and 2 coats or more Exterior grade of DULUX Weather Shief Max / Nerolac XL Total / Berger Long Life Weather Shield / Asian Apex Ultimium Paint . The rate should be inclusive of all (labour, tools & tackles, scaffolding, covering of furniture with plastic sheet, OHP, etc. DFT (Dry Film Test and Mirco Thickness of paint is to be shown to the Engineer In-Charge before and application of paint)	Sqft	28000		
6	Same as above (Boundary Wall) & Servant Quarter	Sqft	8500		
7	Same as above Security Room	Sqft	4000		
8	Application of 2 coat of synthetic enamel paint on wooden surface, MS grill, etc over application of 1 coat of wooden / steel primer and preparation of surface	Sqft	6000		
9	Mirror Polishing of marble flooring with using machineries, chemical, etc and necessary cleaning	Sqft	1000		
10	Painting of Paver Tiles with INDICO Paint over primer for poarch area and garden area and fountain	sqft	4750		
	Sub Total				

(Rupees in word :

Date :

Signature of Bidder with Seal