



SBI INFRA MANAGEMENT SOLUTIONS PVT.LTD.

CIRCLE OFFICE, THIRD FLOOR, STATE BANK OF INDIA, SYNERGY BUILDING, C-6, G-BLOCK, BANDRA KURLA COMPLEX, BANDRA EAST, MUMBAI-400051

PART – B: FINANCIAL BID

TENDER FOR:

INTERIOR WORK FOR RENOVATION OF UNION OFFICE AT ZONAL OFFICE NAGPUR

TENDER SUBMITTED BY:

NAME : _____

ADDRESS : _____

DATE : _____

TENDER INVITED BY:

Vice President & Circle Head,

SBI Infra Management Solutions Pvt. Ltd; 3rd floor, Circle Office, State Bank of India, Synergy building, C-6, G-Block, Bandra -Kurla complex, Bandra East, Mumbai-400051.

S.NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
1	False Ceiling: Providing & fixing in position 12.5 mm thick gypsum board false ceiling fixed with 16 gauge galvanized frame supported from and fixed to RCC slab with Anchor bolts. The ceiling should contain approx. 40 % of the ceiling area of 12mm thick Armstrong ceiling (600*600 mm) - beauty sky or other approved pattern and stepping. All the joints to be properly sealed with jointing tape and finished with approved jointing material. The item includes making cut-outs and providing necessary frame work for light fitting, grill diffusers and ducts etc. which have to be made with frame of perimeter channels of size 20mm x 30mm x 0.55mm thick supported suitably and angle bead is to be used at steps to get straight line finish etc. complete. The item rate shall also include preparation of surface with sanding, and 3 coats of Acrylic Emulsion paint in approved shade over a coat of primer / putty including necessary work etc. complete as per Bank Engineer's instruction.	40	Sq M		
2	Providing and fixing factory made solid core flush door in single leaf 30 mm thick, finished with approved 1mm th. Laminate on both faces with / without glazing and venetians in the positions shown on the drawings or as directed, all necessary beads, molding and lipping, Stainless Steel fixtures and fastenings with CP / brass mortise lock, Stainless Steel handles on both sides, stoppers and exposed woodwork finished with French-polish complete. (without door frame).	5	Sq M		
3	Low / medium height partition: Providing and fixing in position low / medium height partition made of 50 x 50 x 1.2mm medium duty aluminum hollow square pipes framed at 0.6 m to 0.45 m c/c both ways covered with 6 mm MR grade ply and 1mm thick laminate of approved shade & make, both sides including necessary opening / outing for receiving cheques & other papers, and to receive 8mm th. Float glass including all necessary opening for electric / telephonic conduits etc. as per requirement. (Glass area in the partitions will be deducted in the measurements of partition).	1	Sq M		
4	Glass partition: Providing and fixing 8 mm thick glass with etching as per design for low height partitions held with SS clits (D brackets). All exposed glass edges with rounded moulding and crystal polish. All exposed woodwork to be finished in 3 coats of French polish/ melamine polish.	1	Sqm		
5	Providing & fixing in position floor spring for receiving glass door of approved make. (DORMA / HETTICH or equivalent)	1	No.		
6	Providing and fixing in position door closer of approved make (Hyper / Godrej or equivalent).	3	No		

S.NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
7	Tables : Providing & fixing in position tables made of 19mm MR grade Ply at top, side and front, support along with drawer unit & Key board tray with telescopic arrangement & CPU base resting on foot rest of teak wood member of 75 x 40 mm. 19mm th MR grade ply modesty panel. All external surfaces to be finished with 1 mm thick laminate and internal surface finished with 0.8 mm of approved shade and make including powder coated fittings like sliding channels, for key board & drawers, medium duty hinges for shutter, cable manager. S.S. handles in approved design and size and locks wherever directed in approved make. All exposed plywood edges to be finished with 6mm thick Teak wood beading with French polish in approved shade and necessary locks to shutters etc. complete in all respects.				
A	Officer's Tables - 1.50 x0.70 x 0.75 Mtr	1	No.		
B	Staff Table -1.20*.70*.75 Mtr	2	No.		
8	Low height & Full height storage: Providing & fixing in position 400mm deep low/full height storage made of 19mm MR grade ply at top, front and side with 12 mm MR grade ply at back, all external faces including back to be finished with 1 mm thick multi-color laminate at outside and inside finished with 0.8 mm laminate with locking and SS handle arrangement of approved make complete with openable type shutter, beading patti etc. All exposed plywood edges to be finished with 6mm th. Teak wood beading with French polish in approved shade complete in all respect.	10	Sq Mt		
9	Providing and fixing side table made of 18 mm thick ply for all top, support and side with 6 mm thick ply at back externally finished with 1.0 mm thick laminate and internal surface painted with three coats of synthetic enamel paint over a single coat of primer , both of approved make including brush finish S S handles, shutters , hinges with necessary teak wood beading including three coats of French polish to teak wood member and necessary locks to shutters etc. all required surface				
A	Size 1.05*0.4*0.75 Mtr	1	No		

S.NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
B	Size 0.9*0.4*0.75 Mtr	2	No		
10	Notice board: Providing & fixing notice board with approved upholstery. Size 3'-0" x 1'-6"	1	No		
11	Pin Board : Providing & fixing Pin board with approved upholstery. Size 3'-0" x 1'-6"	1	No		
12	Providing & fixing Paneling out of 12 mm thick ply and 1.0 mm thick laminate of approved shade and make to column with accessories etc. complete	2	sq m		
13	Providing and applying acrylic emulsion paint of approved quality, shade and colour in 2 or more coats to achieve desired result including applying one coat of primer of cement paint, preparing the surface by cleaning the dust/dirt by watering/brushing the surfaces, filling in cracks/crevices ,scaffolding at all levels, necessary lead, lifts etc. complete	100	sq m		
14	Providing and Laying vitrified tiles of approved make and quality of required size for flooring and skirting in required position laid on bed of C.M.1:4 including cement float, filling joint with white / colour cement slurry, cleaning, curing, complete. 600 mm x 600 mm. size (Basic rate = Rs. 70/- per Sqft) The item rate shall be inclusive of removing the existing flooring & skirting.(for repair purpose)	45	sq m		
15	Constructing 9"thk. Brick masonry wall Providing & Constructing 6" thick brick wall masonry in cement Mortar (1:4) including (1:2:4) R.C.C.Patti of size 11cm X 15cm at bottom & 2 Nos. M.S. bars at to properly bend & bound at ends along with form work, scaffolding, racking out joint, both side neeru plaster finish, clean / level the surface, curing carting away debris out of compound, cleaning the site etc. complete as per instructions of Architect. RCC lintels of 100 mm thickness to be provided at each interval of 2.1 m during brickwork.	0.5	Cu Mtr		

SEAL AND SIGNATURE OF THE TENDERER

S.NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
16	Providing general cement plaster 12 mm in cement mortar (1:4) in all positions including curing, scaffolding, cleaning, carting away debris out of the compound, cleaning etc. complete as per the instructions of the architect.	5	Sq Mt		
S U M M A R Y :					
	Total of Interior Work	Rs.			
	Less discount (if any)	Rs.			
	Total cost of work Tendered	Rs.			
	Add SGST @ 9%	Rs.			
	Add CGST @ 9%	Rs.			
	FINAL AMOUNT INCLUDING GST	Rs.			