



SBI INFRA MANAGEMENT SOLUTIONS PVT.LTD.

CIRCLE OFFICE, THIRD FLOOR, STATE BANK OF INDIA, SYNERGY BUILDING, C-6, G-BLOCK, BANDRA KURLA COMPLEX, BANDRA EAST, MUMBAI-400051

PART – B : FINANCIAL BID

TENDER FOR:

UPS AND SERVER ROOM PARTITIONS AT CHANDRAPUR MAIN, SHASTRINAGAR, JATPURA GATE, IND ESTATE CHANDRAPUR, CAC CHANDRAPUR LAKHAMAPUR, FOREST CAMP CHANDRAPUR, RBO OFFICE CHANDRAPUR, IN TOUCH CHANDRAPUR, CEMENT NAGAR CHANDRAPUR, SAORI BIDKAR (11) BRANCHES

TENDER SUBMITTED BY:

NAME : _____

ADDRESS : _____

DATE : _____

TENDER INVITED BY:

Vice President & Circle Head,

SBI Infra Management Solutions Pvt. Ltd; 3rd floor, Circle Office, State Bank of India, Synergy building, C-6, G-Block, Bandra -Kurla complex, Bandra East, Mumbai-400051.

S.NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
1	Removing existing partition and disposing the scrapped material as per prescribed norms as per instructions.	30	Sq m		
2	Full height /Low height Aluminium Composite Panelled partition for server room: Providing and fixing in position fully panelled/partly glazed & partly panelled partition made of 50 mm x 50mm x 1.2mm medium duty aluminium hollow square pipes framed at 0.60 m. to 0.45 m c/c both ways covered with 6 mm MR grade ply and 3 mm aluminium composite panel of approved shade with necessary fittings, silicon sealant and pasting material etc. as per requirement and instructions of Bank's Engineer.	60	Sq m		
3	Providing and fixing in position 3mm aluminium composite panel of approved shade on existing plywood partition covered with 6 mm MR grade ply with necessary fittings and pasting material of approved shade with necessary fittings, silicon sealant and pasting material etc. as per requirement and instructions of Bank's Engineer.	130	Sq m		
4	Providing and fixing in position 3mm aluminium composite panel of approved shade removing existing glass and providing 50 mm x 50mm x 1.2mm medium duty aluminium hollow square pipes framed at 0.60 m. to 0.45 m c/c both ways covered with 12 mm MR grade ply and 3 mm aluminium composite panel both ways of with necessary fittings, silicon sealant and pasting material etc. as per requirement and instructions of Bank's Engineer.	75	Sq m		

S.NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
5	Providing and fixing in position 3mm aluminium composite panel of approved shade on existing plywood partition with necessary fittings and pasting material of approved shade with necessary fittings, silicon sealant and pasting material etc. as per requirement and instructions of Bank's Engineer.	20	Sq m		

	S U M M A R Y :				
	Total of Interior Work	Rs.			
	Less discount (if any)	Rs.			
	Total cost of work Tendered	Rs.			
	Add SGST @ 9%	Rs.			
	Add CGST @ 9%	Rs.			
	FINAL AMOUNT INCLUDING GST	Rs.			

Total Amount

Rupees in words: _____

Signature & Seal of Contractor

Date: _____