



**SBI INFRA MANAGEMENT SOLUTIONS PVT. LTD.**

**(A wholly owned subsidiary of SBI )**

**TENDERS ARE INVITED FOR PROPOSED AIR CONDITIONING WORK AT  
SBI SANT ROAD BRANCH, DIST. GODHRA**

**FROM**

**AUTHORISED DEALER OF RECOMMENDED MAKE (CARRIER SUPERIA PRO.  
HITACHI, DAIKIN, VOLTAS) IN GUJARAT**

**PART – B : PRICE BID**

**TENDER SUBMITTED BY:**

**NAME :** \_\_\_\_\_

**ADDRESS :** \_\_\_\_\_

\_\_\_\_\_

**DATE :** \_\_\_\_\_

ARCHITECT:

**Ar MAYUR SHAH**  
803, TOP FLOOR,  
CENTER POINT,  
ALKAPURI,  
VADODARA – 390007.  
(M) : 9377213854, 0265-2331172  
Email : msa.baroda@gmail.com



## **INDEX**

**Tender documents are in two parts (Volumes) i.e. Part - A and Part - B**

### **PART - B (PRICE BID)**

<b>Sr. No.</b>	<b>Description</b>	<b>Page No.</b>
1	<i>Cover page</i>	1
2	<i>Index</i>	2
3	<i>Bill of Quantities ( 3 nos )</i>	3 - 5



<b>BOQ : Interior Decoration and Furnishing work : AC WORK of SANT ROAD BRANCH for State Bank of India.</b>					
<b>SR. NO.</b>	<b>DESCRIPTION</b>	<b>QTY.</b>	<b>UNIT</b>	<b>RATE</b>	<b>AMOUNT</b>
	All A.C should be of either carrier (superia pro), hitachi, daikin, voltas make.				
	All A.C should be same brand irrespective of individual capacity. Mention the model no. and brand of A.C and R32 gas.				
	Have copper condensing coil and scroll compressor for cassette A.C.				
	Star rating should conform to guideline by BEE. (latest guideline (JAN 2018).				
	Contractor shall mark location of indoor and outdoor unit and coordinate with other agencies for electric supply.				
	Contractor shall provide authorized dealership certificate from concerned company				
1	Providing approved quality make hi wall split A.C of 1.0 ton capacity (copper condenser & minimum 3 star rating) with remote, 4mt of copper pipe (FOR 1 SERVER ROOM, 1 UPS ROOM)	2	Nos.		
2	Installing pressure testing, gas charging, vacuuming commissioning 1.0 ton hi wall split A.C (indoor & outdoor unit). (installation should be done as per company specification.)	2	Nos.		



3	Providing approved quality make hi wall split A.C of 2.0 ton capacity (copper condenser & minimum 3 star rating) with remote, 4mt of copper pipe (FOR BANK HALL)	3	Nos.		
4	Installing pressure testing, gas charging, vacuuming commissioning 2.0 ton hi wall split A.C (indoor & outdoor unit). (installation should be done as per company specification.)	3	Nos.		
5	Providing approved quality make Cassate A.C of 3.0 ton capacity (copper condenser & minimum 3 star rating) with remote, 4mt of copper pipe (FOR BANK HALL)	1	Nos.		
6	Installing pressure testing, gas charging, vacuuming commissioning 3.0 ton Cassate A.C (indoor & outdoor unit). (installation should be done as per company specification.)	1	Nos.		
7	Providing & fixing 16 guage MS powder coated wall hung/floor mounted (table top) A.C outdoor unit stand of minimum 24" length.	5	Nos.		
8	Providing & laying concealed refrigerant copper piping with proper 6/9 mm nitrile rubber insulation (k-flex, armcell make) & FRLS (RR cable, Finolex or equivalent make) 1.5/2.5 sq mm 3/4 core power control cable (depending on AC make & capacity & as per company specification) from indoor unit to outdoor unit. the laying shall be done using clamps & hangers to fix pipes to wall/slab piping shall not be fixed to false ceiling channel. quantity may differ considering site conditions.	30	MTR		



9	Providing & concealed water drainage piping from indoor to specified outdoor location using upvc (Astral, Supreme, Dutron make) pipe quantity may differ considering site conditions.	30	MTR		
10	Providing & fixing MS powder coated wall hung/floor mounted (table top) A.C outdoor unit stand of minimum 36" length. (FOR 3 TON CASSATE AC)	1	Nos.		
	Note :- All zharis or chases in wall/columns/slabs, cone cutting etc. of conduits the filling of the same will be done by the contractor including all necessary material & labor.				
	<b>TOTAL</b>				