

NIT NO	SBIIMS/262/2018
DATE	4/12/2018



SBI INFRA MANAGEMENT SOLUTIONS PVT. LTD., (SBIIMS)

(WHOLLY OWNED SUBSIDIARY OF SBI)

INVITES TENDERS ON BEHALF OF SBI, HYDERABAD.

IN A SINGLE BID PROCESS.

FOR

ATM ROOM INTERIOR WORKS AT KODAGANDLA BRANCH
Region 6, RBO RC PURAM, AO NIZAMABAD

Interior Contractors who are on the panel of SBI, Hyderabad Circle, (LHO) in the appropriate category are only eligible. (Contractors should submit proof of the same)

Last date for submission of Tender: 3.00 P.M. (IST) on 10/12/2018

Opening of Tenders: 3.10P.M. (IST) on 10/12/2018

**The Sr. Vice president,
SBI Infra Management Solutions Pvt. Ltd.
Ground Floor , SBI LHO Campus,
Bank Street, Koti,
Hyderabad – 500 095
Telangana**

NOTICE INVITING TENDER

<u>SBIIMS invites sealed tenders for the Civil works for “ATM ROOM INTERIOR WORKS AT KODAGANDLA BRANCH”</u>		
1.	Name of Work	<u>ATM ROOM INTERIOR WORKS AT KODAGANDLA BRANCH.</u>
2.	Estimated cost	Rs. 1,67,804 + GST
3.	Time allowed for completion	15 Days from issue of Letter of Acceptance (LOA)
4.	Cost of the tender document	Rs 500/- DD drawn in favor of, SBIIMS Pvt. Ltd, Hyderabad
5.	Quantum of Earnest Money Deposit (EMD)	Rs.2,000/- DD Drawn In Favor of “SBIIMS Pvt. Ltd, Hyderabad”, Payable at Hyderabad
6.	Initial Security Deposit	2% of the contract value including EMD
7.	Retention amount	5% of the contract value including Security deposit.
8.	Availability of tender document	Upto 10/12/2018.2018
9.	Last date and time of receipt of tender	On or Before 10/12/2018 by 3.00 PM
10.	Address at which the tenders are to be submitted	The Sr. Vice president, SBI Infra Management Solutions Pvt. Ltd., Ground Floor, SBI LHO Campus, Bank Street, Koti, Hyderabad – 500 095, Telangana
11.	Date and time of opening of tender	1/12/2018 by 3:10PM
12.	Place of opening tenders	The Sr. Vice president, SBI Infra Management Solutions Pvt. Ltd., Ground Floor , SBI LHO Campus, Bank Street, Koti, Hyderabad – 500 095, Telangana
13.	Defects Liability Period	12 months from date of completion of the work
14.	Validity of offer	90 days
15.	Liquidated Damages	0.5% of the total contract amount per week beyond the date of completion subject to maximum of 5% of the contact value
16.	Value of Interim Certificate	Only Final bill
17.	For clarification and other details	Please contact :Civil Engineer: K. Srinivasa Rao (DM - Civil) : 7702614111
1) All Civil contractors who are empanelled with SBI, LHO Hyderabad are eligible		
In case the date of opening of tenders is declared as a holiday, the tenders will be opened on the next working day at the same time.		
SBIIMS has the right to accept/reject any/all tenders without assigning any reasons.		
<div style="text-align: right;">Sr. Vice President For and behalf of SBI Infra Management Solutions Pvt. Ltd</div>		

ATM ROOM INTERIOR WORKS AT KODAGANDLA BRANCH

INSTRUCTIONS TO THE TENDERERS

1.0 Scope of Work

Sealed Tenders are invited by State Bank of India for the work of “**ATM ROOM INTERIOR WORKS AT KODAGANDLA BRANCH**”

1.1 Site and Its Location

The proposed work is to be carried out at **SBI KODAGANDLA Branch**

2.0 Tender Documents

2.1 The work has to be carried out strictly according to the conditions stipulated in tender consisting the following documents and the most workmen like manner,

- > Instructions to tenderers
- > Drawings
- > Priced Bid

2.2 The above documents shall be taken as complementary and mutually explanatory of one another but in case of ambiguities or discrepancies, shall take precedence in the order given below:

- > Price Bid
- > Drawings
- > Instructions to Tenderers

2.3 The tender documents are not transferable.

3.0 Site Visit

3.1 The tenderer must obtain himself on his own responsibility and his own expenses all information and data which may be required for the purpose of filling this tender document and enter into a contract for the satisfactory performance of the work. The Tenderer is requested satisfy himself regarding the availability of water, power, transport and communication facilities, the character quality and quantity of the materials, labour, the law and order situation, climatic conditions local authorities requirement, traffic regulations etc; The tenderer will be fully responsible for considering the financial effect of any or all the factors while submitting his tender.

4.0 Earnest Money

4.1 The tenderers are requested to submit the Earnest Money of Rs. Nil/- All Drafts/BCs shall be in favor of " SBIIMS, Hyderabad "

4.2 EMD in any other form other than as specified above will not be accepted. Tender not accompanied by the EMD in accordance with clause 4.1 above shall be rejected.

4.3 No interest will be paid on the EMD.

4.4 EMD of unsuccessful tenderers will be refunded within 30 days of award of Contract.

4.5 EMD of successful tenderer will be retained as a part of security deposit.

6.0 Initial Security Deposit

6.1 The successful tenderer will have to submit a sum equivalent to 2% of contract value by means of D/D drawn in favor of " CM, (CS), Hyderabad within a period of 7 days of acceptance of tender

6.2 No interest shall be paid to the amount retained by the Bank as Security Deposit.

7.0 Signing of Contract Documents

The successful tenderer shall be bound to implement the contract by signing an agreement and conditions of contract attached herewith within 15 days from the receipt of intimation of acceptance of his tender by the Bank. However, the written acceptance of the tender by the Bank will constitute a binding agreement between the Bank and successful tenderer whether such formal agreement is subsequently entered into or not.

8.0 Completion Period

15 Days from Date of Issue of Letter of Acceptance

9.0 Validity of Tender

Tenders shall remain valid and open for acceptance for a period of 3 (Three) months from the date of opening price bid. If the tenderer withdraws his/her offer during the validity period or makes modifications in his/her original offer which are not acceptance to the Bank without prejudice to any other right or remedy the Bank shall be at liberty to forfeit the EMD.

10.0 Liquidated Damages

The liquidated damages shall be 0.5% per week subject to a maximum of 5% of contract value.

11.0 Rates and Prices

11.1 In case of item rate tender

11.1.1 The tenderers shall quote their rates for individual items both in words and figures in case of discrepancy between the rates quoted in words and figures the unit rate quoted in words will prevail. If no rate is quoted for a particular item the contractor shall not be paid for that item when it is executed.

The amount of each item shall be calculated and the requisite total is given. In case of discrepancy between the unit rate and the total amount calculated from multiplication of unit rate and the quantity the unit rate quoted will govern and the amount will be corrected.

11.1.2 The tenderers need not quote their rates for which no quantities have been given. In case the tenderers quote their rates for such items those rates will be ignored and will not be considered during execution.

11.1.3 The tenderers should not change the units as specified in the tender. If any unit is changed the tenders would be evaluated as per the original unit and the contractor would be paid accordingly.

The tenderer should not change or modify or delete the description of the item. If any discrepancy is observed he should immediately bring to the knowledge of the Architect/ Bank.

11.1.4 Each page of the BOQ shall be signed by the authorized person and cutting or overwriting shall be duly attested by him.

11.1.5 Each page shall be totaled and the grand total shall be given.

11.1.6 The rate quoted shall be firm and shall include all costs, allowances, taxes, GST Will be Paid Extra , levies, etc.

Date:

Place:

Signature of the Contractor

With Seal

UNDERTAKING TO BE SUBMITTED BY THE
CONTRACTORS ALONG WITH THE TENDER

Date:

**The Sr. Vice president,
SBI Infra Management Solutions Pvt. Ltd.
Ground Floor , SBI LHO Campus,
Bank Street, Koti,
Hyderabad – 500 095
Telangana.**

Dear Sir,

“ATM ROOM INTERIOR WORKS AT KODAGANDLA BRANCH”.
Region 6, RBO RC PURAM, AO NIZAMABAD

Having examined the **Proposal Documents**, the receipt of which is hereby duly acknowledged, we, the undersigned, offer to execute the “**ATM ROOM INTERIOR WORKS AT KODAGANDLA BRANCH**” in conformity with the said Proposal documents for the sum of Rupees.....
or such other sums as may be ascertained in accordance with the Schedule of Prices attached herewith and made part of this Proposal.

We undertake, if our Proposal is accepted, to complete the work **within 15 days** after handing over the site.

We agree to abide by the proposal and the rates quoted therein for the contract awarded by the Bank.

Until a formal contract is prepared and executed, this proposal, together with your written acceptance thereof and your notification of award, shall constitute a binding Contract between us.

WE UNDERSTAND THAT SBIIMS RESERVES THE RIGHT TO ACCEPT OR REJECT ANY OR ALL BIDS WITHOUT ASSIGNING ANY REASON WHATSOEVER THEREOF.

DATED THIS ____ DAY OF _____ 2018

Signature of Contractor in the capacity of

Duly authorized to sign Proposal for and on behalf of

**LIST OF APPROVED MANUFACTURERS / NATURAL SOURCES OF MATERIALS TO BE USED
IN THE INTERIOR WORKS SUBJECT TO THE APPROVAL OF SAMPLES BY SBIIMS /
ARCHITECT.
(ALL THE MATERIALS USED HAVE TO CONFIRM TO GREEN INTERIOR NORMS OF IGBC)**

<u>S. No.</u>	<u>MATERIAL NAME.</u>	<u>BRAND / MANUFACTURER.</u>
1.	MDF - Exterior Grade (Medium Density Fibre Board) - CONFIRMING TO IS : 12406 - 2003. (Density: 750 - 850 Kgs/m ³)	GREEN PLY / MERINO / TESA / CENTURY / ARCHID.
2.	FLEXI PLYWOOD - BWP (Boiling Water Resistant, Termite Resistant & Borer Resistant) - CONFIRMING TO IS: 303.	GOLDENPLY / SARDAPLY / ARCHID / GREENPLY / CENTURY / UNIPLY / RAMA PLY / MAYUR / NATIONAL PLYWOOD.
3.	BLOCK BOARD - CONFIRMING TO IS :11255 - 2003.	NIKON / GOLDEN / TRUWUD / MAYUR/ ARCHID / GREENPLY.
4.	FLUSH DOOR - CONFIRMING TO IS : 2202 (Part - 1) - 1991.	NIKON / GREENPLY / EGG WOOD / MAYUR / RAMA.
5.	LAMINATE - CONFIRMING TO IS : 2046- 1995.	GREENLAM / MERINO/ CENTURY / ARCHID / VIR LAMINATE / BRAVIA.
6.	GLASS.	SAINT GOBAIN / GUJRAT GUARDIAN / TRIVENI / MODIFLOAT / ASAHI FLOAT.
7.	HARDWARE.	EFFICIENT GADGETS / EARL BEHARI (EBCO) / HARDWIN / ETALICA.
8.	BEECH WOOD.	AS APPROVED BY SBIIMS / ARCHITECT.
9.	SCREWS.	GKW NETTLEFOLD OR AS APPROVED.
10.	ADHESIVES.	MOVICOL / FEVICOL SH / ARAALDITE.
11.	PAINT.	ASIAN / NIPPON / BERGER / KANSAI NEROLAC.
12.	FLOOR SPRING / DOOR CLOSER.	DOORSET / STERLING / DORMA / OZONE.
13.	LOCKS.	DOORSET / GODREJ.
14.	GI SUPPORT SYSTEM FOR PLAIN FALSE CEILING.	GYPROC ULTRA / US BORAL.
15.	GI DRY WALL PARTITION SYSTEM.	GYPROC / US BORAL / FRAME WORK / RONDO / BMS.
16.	GYPSUM / PLASTER BOARDS.	GYPBOARD / LAGYP.
17.	GI SUPPORT SYSTEM FOR GRID CEILING.	ARMSTRONG / GYPROC ULTRA / US BORAL.
18.	CEILING TILES.	ARMSTRONG / GYPROCK / US BORAL.
19.	ACRYLIC SOLID SURFACE.	LG Hausys, HI - MACS / DUPONT - MONTELLI / MERINO - HANEX / LOTTE - STARON.
20.	TEXTURED PAINT.	TERRACO / SPECTRUM.
21.	VINYL FLOORING.	LG / WINNER.
22.	WRITING BOARD.	WHITE MARK OR APPROVED.
23.	VITRIFIED, CERAMIC AND GLAZED TILES.	JOHNSON / SIMPOLO / KAJARIA / RAK.
24.	SANITARY FAUCETS AND FIXTURES.	JAGUAR / HINDWARE / KOHLER.
25.	ALUMINIUM COMPOSITE PANELS.	ALSTRONG / EUROBOND /

		ALUDECOR.	
26.	CARPET TILES FLOORING.	GODREJ / ELEMENT / UNITEX / FLOTEX.	
27.	CEMENT FIBER / CALCIUM SILICATE / REINFORCED MAGNESIUM SILICATE BOARD.	VISAKA / TRILITE / SHERA / BISON.	
APPROVED BRANDS FOR ELECTRICAL WORKS			
MCCB		ABB/LT/SIEMENS/GE/MDS/CG	
TPN SFU		ABB/GE/LT/CG	
CHANGEOVER SWITCH		L&T/HPL/C&S	
CABLES		CCI/UNIVERSAL/POLYCAB/HAVELLS/RALLISON	
KITKAT		GECO/ANCHOR/KUNDAN	
MS CONDUITS		GUPTA/BHARAT	
PVC CONDUITS		PRECISION/SUDHAKAR	
METAL CLAD SOCKETS		MDS SLEEK/SIEMENS/HAVELLS	
LIGHT FIXTURE		PHILIPS/WIPRO/CG/BAJAJ/GE	
CFL FIXTURES		PHILIPS/CG/GE/WIPRO/BAJAJ	
CAPACITORS		L&T/ CROMPTON/ NEPTUNE DUCATI/ ASIAN	
CEILING/WALL FANS		CROMPTON/ BAJAJ	
CABLE GLANDS		SUNIL/HMI/BRACO/COMET	
CABLE LUGS		DOWELL/3D	
HRC FUSES/BASE		GE/ OR APPROVED MAKE	
INDICATING METERS		AE/IMP/MECO/ENERCON	
RELAYS		GE/TELEMECANIQUE/PROK DEVICES/	
CT'S RESIN-CAST		KAPPA/IMP/AE/KALPA	
SELECTOR SWITCHES		L&T/SIEMENS/KAYCEE	
INDUSTRIAL EXHAUST FANS		CROMPTON/ GEC/ARMONALD / BAJAJ	
CEILING/EXHAUST FANS		CROMPTON / BAJAJ	
PVC CONDUITS		MODI/SUDHAKAR/VIP/PRECISION/ATUL	
BUS BAR TAPING BOX		SIEMENS/SCHNEIDER/ABB	
M S CONDUITS		BHARAT / ZINDAL	
CASING / CAPPING		CLASSIC/ MODI	
cables for run of mains		rr/polycab/finolex	
Important: Please Tick (/) the make of materials considered in the Tender.			

NOTE: The Contractor shall use only above mentioned material. All other materials shall confirm to the specifications laid down. The Contractor shall take this into account while tendering rates / prices. All materials and sections used should adhere to the manufacturer's guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified product / sections.

**DETAILS OF SHADES OF MATERIALS TO BE USED IN THE PROPOSED
INTERIOR WORK.**

1mm Gloss Laminate: BLUE COLOR.

<u>Brand. / Manufacturer.</u>	<u>Product Code.</u>	<u>Product Shade.</u>
GREENLAM.	291 - HDG.	ELECTRIC BLUE.
MERINO.	21122 - HGL.	KINGFISHER BLUE.
VIR.	1031 - SG.	CARBON BLUE.
CENTURY.	245 - LU.	BLUE.
BRAVIA.	452 - HG	ROYAL BLUE.
ARCHID.	11025 - HG.	ELECTRIC BLUE.
FORMICA.	1568 - DGL.	ELECTRIC BLUE.

1mm Gloss Laminate: WHITE COLOR.

<u>Brand. / Manufacturer.</u>	<u>Product Code.</u>	<u>Product Shade.</u>
GREENLAM.	108 - HDG.	ABSOLUTE WHITE.
MERINO.	21081 - HGL.	WHITE LILY.
VIR.	1001 - SG.	WHITE
CENTURY.	101 - LU.	WHITE.
BRAVIA.	401 HG	WHITE.
ARCHID.	11023 - HG.	WHITE.
FORMICA.	1324 - DGL.	SUPPER WHITE.

1mm Gloss - Textured Laminate: WHITE COLOR.

<u>Brand. / Manufacturer.</u>	<u>Product Code.</u>	<u>Product Shade.</u>
GREENLAM.	108 - HDG + RFF.	ABSOLUTE WHITE.
MERINO.	21081 - DZL.	WHITE LILY.
VIR.	4001 - SG + NT.	WHITE
CENTURY.	101 - LU + WK.	WHITE.
BRAVIA.	401 - HG + AW.	WHITE.
ARCHID.	1023 - HG + WV.	WHITE.
FORMICA.	1324 - DGL+ATO.	SUPPER WHITE.

6mm Acrylic Solid Surface:

<u>Brand. / Manufacturer.</u>	<u>Product Code.</u>	<u>Product Shade.</u>
LG Hausys, HI. - MACS.	P001	PERNA WHITE.
MERINO - HANEX.	P004	SOLARIS.
DUPONT - MONTELLI.	M1518	GLITTERING WHITE.
GREENPLY - AVONITE.	8206	ALPINE SHIMMER.
LOTTE - STARON.	EG501	GLARING WHITE.

PRICE BID

Bill of Quantities for ATM ROOM INTERIOR WORKS AT KODAGANDLA BRANCH ”

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Unit.</u>	<u>Quantity.</u>	<u>Rate.</u>	<u>Amount.</u>
1	FIXED GLASS WORKS: (12MM TOUGHENED GLASS WORK)	Sq.M.	9		
	Providing, making and fixing in position Fixed 12mm toughened glass as fixed glass from Floor to available Ceiling level. The glass is to be fixed with patch fittings and all the edges of the glass have to be polished for a smooth finish. The work includes cost of all materials, approved hardware, making necessary template before toughening of glass and fixing the same as per site conditions to a neat finished work as per drawings and directions etc., complete.				
2	12MM TOUGHENED GLASS MAIN ENTRANCE DOOR AND PARTITION DOORS:	Sq.M.	3		
	Providing, making and fixing in position Fixed 12mm toughened glass openable shutters work as per specifications given below and for the openings mentioned. Main Entrance Glass Work comprising of Door opening of approximate size 1800mm x 2250mm - 2400mm in two pieces, and Partition Doors of approximate size 900 - 1000mm x 2250mm - 2400mm. The entire work to be done as per site conditions with following specifications etc., complete as directed.				
	(a) Entrance door - Providing, fixing in position glazed entrance Double door and Single door with patch fitting or approved make (Double Door approx. Size: 1800mm - 1500mm x 2400mm - 2250mm and Single Door approx. Size: 900mm - 12mm x 2400mm - 2250mm) using 12mm / 10mm toughened glass edge polished. The Door to consist of Heavy Duty Floor spring, Upper Patch, Bottom Patch, Lock Keeper Plate, Euro Profile Cylinder (EPC), "H" Type Handle 32 x 600mm, Corner Lock and the side fixed glass to have 2 Nos. Bottom Patch and 2 Nos. Upper Patch for each door to a neat finish etc., complete as per drawing.				
	(b) The work includes cost of all materials, approved hardware, making necessary template before toughening of glass and fixing the same as per site conditions to a neat finished work as per drawings and directions etc., complete.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Unit.</u>	<u>Quantity.</u>	<u>Rate.</u>	<u>Amount.</u>
3.0	WALL PANELLING:				
3.1	WALL PANELLING IN BANKING HALL:	Sq.M.	21		
	Providing and fixing metal stud dry wall partition with following specifications: The Partition will be fully opaque OR partly opaque and partly glazed as per specific site conditions and drawings.				
	(a) Supporting system comprising of 51mm / 50mm x 35mm / 34mm x 0.5mm metal studs at 600mm c/c and 51mm / 50mm x 32mm x 0.5mm metal tracks at floor, middle, door and ceiling level with joints staggered to avoid through joints. The vertical members should touch the ceiling with horizontal ceiling channel at slab / beam bottom. The rate should also include necessary strengthening with studs / tracks or channels at doors and other openings.				
	(b) 12mm MDF Exterior Grade Board fixed with 25mm dry wall screws for the entire height of the partition.				
	(c) Partition from floor level upto 2350mm level to have 8mm x 100mm Fiber Cement Board / Calcium Silicate Board / Reinforced Magnesium Silicate Board as Skirting clad with 1mm glossy Laminate (blue color) at bottom + from 100mm to 300mm level to have 1mm Glossy Laminate (blue color) + from 300mm level to 950mm level to have 1mm Glossy Laminate (white color) + from 950mm level to 1100mm level 1mm Glossy Laminate (blue color) + from 1100mm level to 2250mm level to have 1mm Textured Glossy Laminate (white color) + from 2250mm level to 2350mm level 1mm Glossy Laminate (blue color) on both sides as shown in drawing.				
	(d) Partition to have 8mm clear float glass fixed with 85mm x 18mm around MDF Exterior Grade jamb and 12mm x 12mm MDF Exterior Grade button beading on both sides of the glass, to a neat finish as per drawings and directions etc., complete.				
	(e) Partition above 2350mm level to have NO VOC or LOW VOC plastic emulsion paint With wood luppam finish on both sides as shown in drawing.				
	(f) All exposed surfaces of MDF Exterior Grade members to have minimum two coats of				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Unit.</u>	<u>Quantity.</u>	<u>Rate.</u>	<u>Amount.</u>
	LOW VOC with luppam or NO VOC duco paint finish.				
	(g) All sections used should adhere to the manufacturer's guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified sections.				
4.0	FALSE CEILING:				
4.1	GRID FALSE CEILING:	Sq.M.	8		
	Providing & Fixing of Mineral Fibre Acoustical Suspended Ceiling System with 15mm Tiles and Exposed GRID. The tiles should have Humidity Resistance (RH) of 90% - 99%, NRC 0.5, Light Reflectance $\geq 87\%$, Thermal Conductivity $k = 0.052 - 0.057$ w/m K, Colour White, Fire Performance UK Class 0 / Class 1 (BS 476 pt - 6 & 7) in module size of 600 x 600 x 16mm, suitable for Green Building application, with Recycled content of 30% - 45%.				
	The tile shall be laid on Microline / Silhouette profile grid system with 15mm - 16mm white flanges incorporating a 6mm central reveal in white/black colour and with a web height of 38mm and a load carrying capacity of minimum 8 Kgs/M ² & minimum pull out strength of 100 Kgs. Microline / Silhouette, Main Runners & Cross Tees to have mitred ends & "birdsmouth" notches to provide mitred cruciform junctions. The T Sections have a Galvanizing of 90 grams per M ² and need to be installed with Suspension system as per manufacturers details.				
	The Installation to comprise main runner spaced at 1200mm centres securely fixed to the structural soffit using US Boral / Gyproc / Armstrong suspension system (specifications below) at 1200mm maximum centre. The First/Last suspension system at the end of each main runner should not be greater than 450mm from the adjacent wall.				
	Flush fitting 1200mm long cross tees to be interlocked between main runners at 600mm centre to form 1200 x 600 mm module. Cut cross tees longer than 600mm require independent support. 600 x 600mm module to be formed by fitting 600mm long flush fitting cross tees centrally between the 1200 mm cross tees. Perimeter trim to be Wall angles of size				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Unit.</u>	<u>Quantity.</u>	<u>Rate.</u>	<u>Amount.</u>
	3000mm x 19mm x 19mm, secured to walls at 450 mm maximum centres.				
5.0	Electrical Works				
1	<u>MODULAR SOCKETS:</u>				
a	Supply and fixing of 2nos. 6A sockets with 1 no 6A switch fixed on a suitable module metal box and white front plate (Modular type) including all interconnections as required UPS power for TVs and mike system	no	3		
b	Supply and fixing of 1nos. 16A socket with 1 no 16A switch fixed on a 3 module metal box and white front plate (Modular type) including all interconnections as required for projector and calling bell	no	3		
c	Supply and wiring with 3 core 4 sq.mm 1100 V grade PVC insulated multi strand copper cable conforming to IS 694 (with latest amendments) for above points	mtr	40		
2	<u>LIGHT & FAN POINT WIRING</u>				
a	Point wiring with 1.5sqmm 650V grade multistranded PVC insulated copper wire in MS/PVC PIPE for lights, fans including supply & fixing of 5 amp modular switch in concealed MS switch box, front plate, 3 plate ceiling rose, and concealed circuit wiring with 3 Nos (P,N,E) 2.5sqmm. and all interconnections as required.	pts	4		
c	Supply and installation of 6A modular socket with a switch in the above modular switch boards.	nos	1		
3	<u>UPS, RAW POWER & TEL WIRING:</u>				
a	Supply and wiring with 3runs of 2.5 sq.mm 1100 V grade PVC insulated multi strand copper conductor wires conforming to IS 694 (with latest amendments) in suitable size PVC CONDUIT of 2mm thick concealed in the above ducts in the floor and supply of all fixing materials and accessories, interconnections complete as required for the UPS power sockets in the single window counters and officer tables.	Nos.	3		
b	Same as above but looping with 3runs of 1.5 sq.mm 1100 V grade PVC insulated multi strand copper conductor wires conforming to IS 694 (with latest amendments) in suitable size PVC CONDUIT from the UPS power primary sockets	sets	3		

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Unit.</u>	<u>Quantity.</u>	<u>Rate.</u>	<u>Amount.</u>
8	<u>FIXTURES/FANS</u>				
a	Supply of Green 18W Led Down light fixture including frames (PHILPS make)	Nos	4		
	Removing the existing split Acs and re located at new position after servicing.	Nos	2		
d	Removing the existing Light and fixtures and handing over to bank officials	LS	1		
	TOTAL FOR INTERIOR WORKS:				

NOTE:

GST will be paid extra as per actual

Date:

(Signature of the Contractor)

Place: