

Schedule of Gosalpur Branch

PRICE BID					
Interior & Furnishing works for Gosalpur Branch, Region-1, Jabalpur					
S.No	Description of Items	Unit	Qty	Rate	Amount
1	<b>INDEPENDENT TYPE STANDARD COUNTER:</b>				
	Providing, fabricating and fixing at site and in position independent type modern single window counters as per detailed drawing and or as directed at site consisting of 19mm thick approved make commercial borer and termite block board/18 mm ply having 32" wide writing/work top as per drawing /site details including providing drawer unit of standard size with telescopic channels of Ebco or equivalent approved make as directed by Bank. Each counters shall be made 5'0" long or as per site conditions and approved layout plan and consisting of 19 mm thick commercial finished block board/18 mm commercial ply of specified makes. The front side (Public side) of the counters shall be consisting of 18 mm ply/ block board of approved makes. All external faces of the counter including front face of the drawer cum cupboard unit etc. shall be finished with 1.0 mm plain and metallic approved shade high gloss lamination and internal faces with 0.8mm laminate as per sample approved by bank. The public side of the counter shall be approved with skirting 100mm high finished with approved quality and shade laminate. The rate should include providing and fixing seasoned teak wood beading of size 19mm x 5 mm or as required to all exposed edges of the block board/ply. Each cupboard/drawer shall be provided with approved quality handles/knobs and Godrej / Doorset make approved quality cupboard auto locks. The rate should include providing and fixing seasoned wood / block board foot rest to each counter complete as per the layout plan and as directed by Bank's Engineer	Rmt	6.00		
2	<b>12MM THICK ETCHED GLASS TO SINGLE WINDOWS COUNTERS</b>				
	Providing and fixing 12 mm thick ATUL/SAINTGOBIN float glass with polished edges and etching as per approved pattern fixed suitably to the public side and transaction top of counters including cutting suitable size transaction/ conversation window, finishing the supports in matching 1.00 mm plain and metallic high gloss laminate complete as directed at site.	Sqmt	10.00		
3	<b>LOW HEIGHT PARTITIONS</b>				
	Providing and fixing in position 1250/1200 mm height double skin wooden partition made out of 2nd quality seasoned second class teak wood framing using sections of 40 X 50 mm horizontally and vertically placed about 60 cm c/c in both directions. The spacing of the members may vary either side depending upon the site conditions as per approval of Bank Engineer. The partition shall be provided 8mm MR ply of approved make on both sides finished with 1.0mm plain high gloss laminate of approved makes in combination and shade up to about 750mm height. The remaining upper portions of the partitions shall have 12 mm thick plain float glass with etching and polished edges of SAINTGOBIN/MODI/TRIVENI. Rate inclusive of beadings etc. complete in all respects.	Sqmt	30.00		
4	<b>FULL HEIGHT PARTITIONS</b>				

Schedule of Gosalpur Branch

	Providing and fixing full height partly double skin wooden partitions made out of seasoned second class teak wood frame of sectional size 40 X 50 MM fixed in position/embedded to wall, floor or slab with 65 to 75 mm long screw. The vertical wooden members shall be placed at 450 to 500 mm center to center and horizontal members to be placed at 600 mm c/c or as directed by the Bank's Engineer as per site conditions with necessary grooves and cuts etc. including anti-termite treatment to all wooden members.				
	The lower and upper panel should be provided with 8 mm MR ply of approved make on both sides duly levelled and finished both sides with 1.00 mm thick approved quality plain and metallic high gloss laminate as per approved design/pattern. The middle panel shall be provided 8mm thick float glass of approved make with necessary etching/frosting as per design. Rate inclusive of material, transportation, loading/unloading labor, tools etc. for all heights complete in all respects. The rate should also include the following:-				
	(a) Applying anti-termite and anti- borer paint to wooden frame work wherever directed				
	(b) Applying three or more coats of melamine polish /painting of approved quality and shade to have desired, finish to all exposed surface of teak wood members beadings, board etc. including preparing of surface by sand papering, applying putty etc. complete	Sqmt	25.00		
5	<b>Providing in position Officer's table of sizes mentioned hereinafter.</b> It shall consists of 19mm thick block board/18 mm ply of approved make on the top finished with 1.00 mm approved quality plain and metallic high gloss lamination as per approved sample design. The writing top shall be supported over two vertical supports made out of 19 mm thick block board/18 mm ply of above specified makes with lamination as above. The supports shall be connected together with 19 mm thick board laminated front as per approval and design/detail.				
	The table shall be complete with one drawer unit having a drawer at top and cupboard with shelves at lower, necessary hardware's, sliding channel, knobs, godrej / doorset multipurpose locks etc. The rate should include providing and fixing suitable foot rest, providing 0.8mm approved quality white laminate to all internal faces and applying 3 coats of melamine spray polishing/ painting etc. to the moldings/ beadings, providing plastic shoes complete. The rate should include providing and fixing seasoned teak wood beading of size 19mm X 5mm or as required to all exposed edges the block board as desired by the bank.				
	(i) Table of size 7'6"0" X 3'0" X 2'6" height with table top and front to be in curved shape as per detailed drawing with 12mm thick bevelled/ polished edges Glass top.	No.	1.00		
	(ii) Table of size 5'0" X 2'6" X 2'6" ht. As per detailed drawing.	No	3.00		

Schedule of Gosalpur Branch

	(iii) Table of size 4'6" X 2'6 X 3' ht. as per detailed drawing for Grahak Mitra with front curve design and 12 mm glass with SS Studs etc. direction.	No	1.00		
6	<b>Providing in position side tables of sizes mentioned hereinafter.</b> It shall consist of 19mm thick board of approved make on top, middle shelf, bottom and sides as per detailed drawing. The top and bottom shall be laminated with 1.0 mm thick approved quality and shade plain and metallic high gloss laminate as per design detail. The cabinet shall be covered from back with 6.0 mm ply, providing drawers at the top and cupboards with laminated block board shutter in remaining lower partition with necessary hardware, knob, telescopic sliding channel, godrej lock etc. complete as per sample approved. The rate should include providing 0.8mm white laminate to all internal surfaces and applying 3 coats of melamine polishing/painting to beadings/moldings etc., providing plastic shoes and also providing and fixing 19 X 4 mm suitable wood beading to all exposed edges to all the block boards etc. as per Bank's approval.				
	(a) Side rack of size 4'0" X 1'6" X 2'6"				
	(b) L-Support side rack of size 4'0" X 1'6" X 2'6"				
	one end tied to Table as per drawing.	No	8.00		
	(c)L-Support side rack of size 3'6" X 1'6" X 2'6"				
	for other officers.				
	(d) L-Support side rack of size 3'0" X 1'6" X 2'6"				
	one end tied to Table as per drawing.				
7	<b>Providing and fixing 6 lever Godrej</b> night latch lock with non-interchangeable key to doors of cash department. Rate inclusive of materials, transportation, unloading/loading labor, tools and tackles up to any lead and lift complete in all respects.	No.	4.00		
8	<b>Providing and fixing voucher writing table</b> with about 5 voucher slots/pockets as per the detail drawing consisting of 19 mm commercial block board /MR ply of approved makes duly laminated using 1.0mm plain and metallic high gloss laminate approved by the bank having slanting top and waste paper box with dumping and cleaning window, in the lower supporting column including polishing/enamel painting etc. complete.	No.	1.00		
9	<b>Providing and fixing wall/column panneling</b> made out of 18 mm double ply / seasoned second class teak wood framing in vertical and horizontal sections placed at 45 c/c both ways or as per site conditions finished with 8mm MR ply grade and 1.0mm thick approved quality and shade plain and metallic high gloss laminate. The rate to include providing 6mm thick seasoned teak wood beading/lamination to exposed edges wherever required complete.	Sqmt	110.00		
10	<del>-----do-----</del> <b>as above but in 4 to 6 wide</b> bands, doors windows jambs, lintel etc. made out of 19 mm block board/18 mm MR grade ply finished with color contrast 1.0 mm high gloss laminate. TW lipping to edges completed as directed at site.	Sqmt	20.00		

Schedule of Gosalpur Branch

11	<b>Providing and fixing 35/40 mm thick solid core flush door shutters of CORBAT/REGAL/GOLDEN FOREST or per sample approved by the Bank finished with approved quality and shade 1.0mm thick lamination plain &amp; metallic high gloss on both side of the shutter with matching wood beading duly melamine polished. The rate should include the following:-</b>				
	(I) Providing 8 mm thick float glass of MODIGUARD/SAINTGOBIN or other equivalent make approved by the Bank with necessary etching/frosting as per design fixed in position with 40x20mm seasoned teak wood suitable beadings.				
	(ii) Providing 100mm high skirting with 1.0mm approved quality high gloss lamination on both sides.				
	(iii) Door shall be hinged on 4 nos. 125 X 30 X 3 stainless steel bearing hinges, providing door stopper, door handles 200mm long. Doorset mortised lock tower bolt etc. as per samples approved and as per site requirements.	Sqmt	5.00		
12	<b>Providing and fixing suspended false ceiling made out of 12.0 mm (apprx.) thick Gypsum Plaster Boards of Indian Gypsum or equivalent made G.I standard section framework in the pattern and design directed by the Bank Engineer. The G.I. Section frame work shall be tied to the roof and walls with the anchor fastener screws/bolts of appropriate size recommended by the Indian Gypsum. The boards shall be fixed to the frame work with the screws and the joints shall be flushed and finished with requisite jointing compounds paper tapes etc. Rates includes execution of works in different levels/offsets etc. The surface shall be finished evenly by applying putty,sand papering,applying primer evenly complete. Rate inclusive of materials transportation, loading/unloading labor, tools and tackles up to any lead and lift complete in all respects.</b>	Sqmt	70.00		
13	<b>Providing and fixing 600 mm X 600 mm size mineral fibers tiles acoustical ceiling with tegular edge as approved by the Bank of 15 mm thick RH 90 or equivalent approved make board tiles fixed in position on STICHD TRULOK/24 mm PRELUDE exposed system hot dipped galvanized steel with white precooked exposed can and the frame shall comprise of:-</b>				
	24mmX38mm- Main Tee of 3600mm				
	24mmX30mm-Cross Tee of 1200mm				
	24mmX25mm-Cross Tee of 600mm				
	22mmX22mm-Wall Angle of 3000mm length				
	The G.I. Wall angle to be fixed the G.I. Wall angle to be fixed along the perimeter fixed with screws/rawl plugs. The G.i. Main runners spaced at 1200 mm counters securely fixed to the structural soffit by approved hangers of 2.0mm GI wire pre stressed at 1200mm Max. centers. Flush fitting 1200mm long cross tee.				
	To be interlocked between main runners at 600 mm centers. The 600mm cross tees are placed between 1200mm Cross Tee (parallel to main runner) to form a 600 X 600 mm module. Extra suspension to be provided around light fixtures.	Sqmt	80.00		
	Make: ARMSTRONG				

Schedule of Gosalpur Branch

14	<b>Low back visitors sofa without arms</b> made out of 25 mm thk block board structure finished with 4 mm thick veneer and 1.0mm lamination in combination as per sample approved with melamine polish complete. The seat size should be 21" X 21" upholstered over 4" thick high density ISI mark foam 40 density foam on back using approved quality and shade upholstery cloth costing Rs 450/mt.				
	(a) Three Seater	Nos.	1.00		
	(b) Two Seater	Nos.	2.00		
	(c) Single Seater	Nos.	2.00		
15	<b>Providing and fixing heavy duty DOOR CLOSURE</b> of Hardwyn / Everite make with stainless steel cover plate.	Nos.	3.00		
16	Providing and fixing in position stainless steel body with door set or approved equivalent <b>6 lever Cylindrical lock</b> .	Each	2.00		
17	<b>Providing and fixing wooden wicket gates</b> of apprx. Size 900mm X 1200 mm made out of 19mm thick block board both sides laminated with hinges, latch, double thickness at edges with painting/ polishing etc. wherever required complete	Sqmt	3.00		
18	<b>Providing and applying Birla white putty to walls</b> in proper lines and level including making grooves and preparing the surface by scraping and removing existing paint from walls, hacking etc. complete as per the direction of the Bank's Engineer.	Sqmt	50.00		
19	<b>Supplying and applying synthetic enamel paint</b> in 2 or more coats of approved shade, quality and make like Nerolac, Asain, Berger after preparations of surface properly with all labors and materials in all floors complete as per drawings, specifications and instructions of Engineer- Incharge. Rate inclusive of cost of materials, transportation, loading/ unloading, labor tools and tackles etc.	Sqmt	25.00		
20	<b>Providing and applying 3 coats of plastic emulsion paint</b> in roller finish to wall surfaces to give an even shade including necessary scaffolding etc complete as per approval of Bank Engineer	Sqmt	50.00		
21	<b>Providing and fixing in position 450 mm deep storage cabinet as directed made out of approved quality 19 mm thick MR grade borer &amp; termite resistant block board.</b> Shutter shall be of 19 mm thick block board with all hardware like 75 mm X 18 mm X 18 mm stainless steel bearing hinges, magnetic catchers, stainless steel handles, locks etc. complete as per sample approved. All internal surfaces of the cabinet including shutters and shelves to be finished with 0.8 mm thick white laminate of approved make and shade as per design. Rate to include providing 8mm thick BWP ply, providing and TW lipping to exposed edges of Block board, polishing/painting etc. complete.	Sqmt	10.00		
22	<b>Renovation of existing flush door/panelled shutters</b> by providing 6.00 mm MR grade ply and 1.00 mm laminate, TW edge lipping, polishing including necessary hardware etc. complete.	Sqmt	2.00		

Schedule of Gosalpur Branch

23	<b>Providing and fixing 2'6" wide work top consisting of 19 mm thick VENUS or equivalent approved make block board finished with approved quality and shade laminate of GREEN/ROYAL TOUCH or equivalent approved made with 19 mm thick block board supports at every 4' to 5' center to center. The rate should include providing 19 X 4 mm teak wood molded beading as per sample approved to the exposed edges of the block board and polishing/painting of all un laminated surface of block board etc with 3 or more coats of wax polish in approved shade complete as per detailed drawing and instructions of Bank's Engineer. The rate should also include providing Tower type CPU compartment, key board drawer fixed on approved quality channels, 1 Nos. drawer 4" deep and Electrical switch board complete at every 4' length of work top as per directed.</b>	Rmt	5.00		
24	<b>MAIN ENTRANCE DOOR:</b> Providing and fixing shutter to be made of 12 mm thick float glass with teak wood top, bottom rail and styles of section 125 X 45 mm(finished size) including Teak wood beading for fixing glass. All teak wood to be finished with melamine polish. The float glass to be etched as per approved design including etching color STATE BANK OF INDIA (SBI) logo as directed.				
	The rate should include necessary hardware's fixtures with heavy duty floor spring with stainless steel cover plate and one pivot at top, 2 Nos. 300 mm long decorative brass handles for each shutter. The teak wood surface will be melamine polished to the satisfaction of Bank Engineer.	Sqmt	5.0		
25	Laying of <b>Etching film on Glass</b> - Providing etching film on glass in required design, pattern & shape wherever required and instructed.	Sqmt	5.0		
26	<b>Vertical Blinds</b> - Providing & fixing vertical blinds 100mm wide of washable synthetic material with extruded powder coated hearail housing control units spacers, runners, tilt rod with reduction gear mechanism tilt control for 180 degree Louvers made of approved fabric and colour having scratchguard coating to be provided.	Sqmt.	20.0		
27	<b>Dismantling of existing wiremesh partitions/m.s. Grill/ false ceiling</b> and stored the same in a suitable places as per the instruction of the Branch including cleaning, shifting charges within the Branch premises etc. complete.	Job	1.0		
28	<b>Dismantling of cash, clerical counters, tables, side units etc.</b> and shifted the same in a suitable places as per the instruction of the Branch including cleaning, shifting charges within the Branch premises etc. complete.	Job	1.0		
29	<b>Dismantling of old Aluminium /Glass/ wooden partitions/ brick partition wall/flooring/sanitary fittings /water pipes</b> and shifting to a suitable place as per the instruction of the branch including shifting charges within the branch premises etc. Complete.	Job	1.0		

Schedule of Gosalpur Branch

30	<b>Providing and fixing of wall papers</b> as per approved make and brand on wall surfaces including Teak wood edges/corner with melamine polish and surface preparation with all material and labour complete.	Sqmt	10.0		
31	<b>Providing and fixing of green channel box</b> on the column made out of 18 mm thick commercial block board and green coloured 1mm thick laminate as per design and as directed by the Engineer Incharge.	No.	2.0		
32	P/F of ventilation <b>Aluminium Powder coated Jaali 1mtr long each</b>	No.	2.0		
	<b>E-Lobby</b>				
33	<b>ACP Panelling on walls</b> - Providing and fixing 3 mm thick ACP Wall Paneling to internal/external surfaces of the walls of the ATM and Branch including necessary aluminium pipe framework (50x25mm 2mm thick Al tubes @ 60cms C/C bothways) and using approved quality double sided adhesive Tape, screwing the ACP sheet to the pipe framework including providing silicon gel filling to joints complete as directed at site. The pipes to be placed both ways at adequate spacing as per manufacturer's specifications to avoid perfectly leveled surface free from undulations etc. complete .	Sqmt	80.0		
34	<b>Providing and fixing ACP panelled Rolling shutter boxing</b> with aluminium composite panel fixed to Aluminium pipe framework placed at adequate spacing as specified in item 28 herein above complete.	Sqmt	20.0		
35	<b>False Ceiling:-(Metallic type)</b> Providing and fixing false ceiling G.I tiles metal sheet semi-perforated of size 600 X 600mm G.I. Section for grid suspension system cut outs to be made for accommodation light fixtures complete in all respect as per site condition	Sqmt	15.0		
36	<b>Providing and fixing of Modiguard/ SAINTGOBAIN / TRIVENI or equivalent approved make 12 mm thick Toughen glass partitions</b> fixed with Enox or equivalent approved make patch fittings, cutting of glass to size including wastage making holes, mirror polishing to edges complete as directed .	Sqmt	15.0		
37	---do--- as above but providing and fixing 12mm thick Toughen <b>Glass door</b> including cutting making holes, edges polishing etc complete.	Sqmt	3.0		
38	Providing and fixing self-adhesive Sparkle Series of 3M make <b>designer frosted film/and / or One-way Vision Film/ flex paintings</b> to 12 mm glass partitions / doors as per approved pattern and design complete as directed at site.	Sqmt	5.0		
	<b>TOTAL OF INTERIOR FURNISHING WORK</b>				

(GST will be paid additionally by the Bank as applicable)

**SEAL & SIGNATURE OF CONTRACTOR**