

SEALED BID FORMAT FOR INTERIOR FURNISHING (RENOVATION) WORKS AT SBI SREEKANDAPURAM BRANCH, RBO VI KANHANGAD, UNDER AO KOZHIKODE

Sl No	Description of work	Qty	Unit	Rate(Rs.) (Exclusif of GST)	Amount (Rs.) (Exclusif of GST)
1	<p><b>SINGLE WINDOW SYSTEM:</b> Providing and fixing of Single window system without partitions as shown in drawings comprising of each counter size 1600 mm &amp; 2500 length or as per layout and 750 mm height or as per layout with below specifications and provisions: Counter and writing top at front, with counter 1600 mm length and 900 mm width at about 750 mm height. The Top shall be fixed with <b>18 mm thick marine plywoord of approved make with 12 mm thick clear</b> polished glass top as per drawing. The shape of the modesty is as shown in the drawing . For the cured shape of three layers of 6 mm flexy plywood is used. The exposed front portion of the table for a height of 40 cm from the bottom is made of Aqua blue shade of saint gobain glass as per the drawing. 18 mm marine ply of approved make for sides and for front shaped support and finished with 1mm laminate of approved color.12 mm thick clear toughened glass to shape with etching is fixed with patch fittings fixed at front (600mm) above the counter as shown in the drawing.</p>	14	RM		
	<p>Modesty fixed with 8mm thick of Aqua Blue shade of saint Gobain glass fixed at 18mm thick marine ply vertical finished. The sides of the counter, boxing on either side to shape as shown in the drawing with 18 mm marine ply of approved make and to be finished with 1 mm thick laminate of approved color from floor level to 1200 mm level at places shown in the drg. Necessary wicket door shutters are to be provided using 18 mm marine ply and finished with 1mm laminate of approved color and shape as shown in the drawing One set of 3 drawers about 450 mm width, 712.5 mm height and 600mm deep supported with 18mm MDF at bottom, sides and rear.</p>				

	Drawers 3Nos. Of which 2 Nos of equal height and 1No. Drawer at the bottom of 230mm height made out of 12mm thick marine ply for sides, rear , bottom and face of drawers with 18 mm marine ply and finished with 1mm thick laminate on both inside and exposed faces and 2 mm thick PVC edge band of approved color, telescopic drawer slides, locking arrangements with <b>auto closing locks</b> , 100mm long brush finish S.S. handles, etc. complete. Top most cash drawer should be arranged with provision for denomination with 8mm thk marine ply. MS Powder coated Telescopic keyboard tray and MS wire manager of 50mm dia of approved quality . Foot rest cum CPU stand of required length with 18mm thickness marine ply to shape as shown in the drawing.				
	All concealed faces of marine ply to be finished with two coat of enamel paint and exposed faces of 2 mm thick PVC edge band. The inner side of the unit finished with 1mm Laminate. The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge.. The rate of low height partition is not included and is paid separately				
2	SINGLE WINDOW SYSTEM (With Out Front Glass) The same as above specification without front toughened glass. The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge.	1.7	RM		
3	Supplying and fixing <b>side tables</b> with 19mm marine plywood finished with <b>1mm decorative laminate</b> over it on all exposed faces, 25mm thick <b>marine ply with 1 mm thick laminate on top</b> having underside covered with balancing laminate and 2 mm vc edge banding on all exposed edges as per the <u>sketch</u> enclosed. The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge.				
(i)	<b>150 x 40 x 60cm</b> ht.	12	Each		
(ii)	<b>100 x 40 x 75cm</b> ht.	8	Each		
4	Supplying and installing double skin wooden partitions <b>120cm height</b> around the clerical counters with 50x50mm size hard wood frame work (Thambakam/Irul) for horizontals at floor level and 75cm ht. and verticals @ 75 cm c/c and 6mm marine ply on both sides finished with 1mm laminate and with as per the <u>sketch</u> enclosed including providing necessary doors 40mm thick with <b>Godrej night latch fixed at 45 cm ht. from floor level</b> , tower bolts, etc. as per the layout plan.	91	Sq.M		

5	Supplying and fixing <b>counters</b> 75cm ht. inside the <b>server room</b> as per specifications in item no.(1) having one drawer & cupboard with locks, handles, computer key board tray, etc.and excluding front glass as per the <u>sketch</u> enclosed. Table top to be provided with 18mm marine ply finished with 1 mm laminate of approved make. 2 mm thick PVC Edge band to be provided on all exposed edges. The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge.	3	RM		
6	Supplying and fixing <b>low level storage units</b> made of 19mm marine plywood finished with 1mm decorative laminate over it on all exposed faces, top with 18mm thick <b>marine ply with 1 mm laminate and edgeband in all exposed edges</b> including providing one shelf, necessary locks, handles, etc. as per the <u>sketch</u> enclosed. All the exposed edges of plywood are to be finished with 2 mm thick PVC edge band and all the inside portion finished with primer and 2 coats of enamel paint. <b>One shelf to have minimum 40 cm height.</b> The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge.				
(i)	<b>units 75cm height</b>	27	RM		
7(a)	<b>Toughened Glass Partition:-</b> Providing and fixing <b>12mm</b> Toughened glass Partition with patch fitting (make – dorma) at height of 270/300 cm for <b>entrance area, BM s Cabin</b> etc. Necessary etching pattern to be provided in the glass. The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with patch fittings, glue, nails, screw etc. complete as directed by the Engineer in charge.	52	SqM		
7 (b)	<b>Toughened glass door:-</b> Providing and fixing Toughened glass door with handle for the <b>Entrance/ Bms Cabin</b> with <b>12mm</b> toughened glass and patch fittings. Necessary etching pattern to be provided. The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge.	14	SqM		
8 I)	Supplying and fixing <b>hydraulic floor spring for entrance doors.</b> (Dorma or approved equivalent with ISI mark) . The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge.	5	Each		
ii)	Supplying and fixing <b>hydraulic door closers</b> on doors. (Dorma or approved equivalent with ISI mark) . The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge.	4	Each		

9	Supplying and fixing suspended seamless <b>false ceiling</b> with 12 mm thick <b>gypsum board</b> over standard GI sections including perimeter channels as per the specification of 'India Gypsum'. to correct lines and levels finished with <b>two coats of plastic emulsion</b> paint of approved make and shade with roller application including providing <u>necessary openings</u> for electrical fittings, <b>cove lighting as per design</b> , A/c, security device, etc. The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the	440	SqM		
10	Engineer in charge. <b>Painting</b> over the walls with <b>two coats</b> of plastic emulsion paint of approved make and shade with one coat primer after rubbing and finishing the surface. The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge.	230	SqM		
11	Supplying and providing <b>panelling for columns</b> with 9mm thick marine ply finished with 1 mm thick laminates including providing beech wood beading over the edges and top. The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge.	45	SqM		
12	Supplying <b>Officer tables</b> as per the <u>sketch</u> enclosed with 18 mm thick marine ply table top laminated with 1 mm thick laminate of approved make as in item no.1 Foot rest cum CPU stand of required length with same 18 mm. MS Powder coated Keyboard tray and 50mm Dia MS wire manager of approved quality . One set of 3 drawers with 18 mm marine ply of approved make at bottom, sides and rear with necessary edge bands, telescopic drawer slides, locking arrangement, 100 mm long brush finish S.S. handles, etc. complete.				
	All concealed faces of marine ply finished with two coat of enamel paint and exposed faces with 2 mm thick PVC edge band to the satisfaction of the Bank. The inside faces of drawer should be waxed and finished with varnish of app color and shade. the table modesty shall be fixed with 8mm thick of Aqua blue shade of saint Gobain (or) equivalent toughened glass panel fixed on the 18mm thick front vertical marine plywood and finished with 1mm thickness laminate. The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge.				
i)	<b>180 x 90</b> x 75cm ht.	1	Nos		
ii)	<b>160 x75</b> x 75cm ht.	10	Nos		

13	Supplying & fixing <b>voucher stand</b> on wall made of 19mm thick ply & laminate with beechwood beadings, <b>8mm glass on top</b> and 5mm glass compartments with polished exposed edges as per the <u>sketch</u> enclosed.	2	Nos		
14	<b>Double Skin solid Partition and door:-</b> Providing and fixing Double skin solid partition <b>for UPS Room, Records room, and passage.</b> The frame work with hard wood frame 25cmx5cm at the top and bottom finished with 6mm ply and 1 mm laminate of approved make on both side. Above 270 cm the partition are to be firmly fixed to the ceiling . The partition upto false ceiling only be measured. Necessary handles locks etc. to be provided. The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge.	70	SqM		
15	Flooring & skirting with vitrified tiles of superior quality and approved colour and 10mm thick 60x60cm or nearest size with base Rs.800/m2. over a bed of cement mortar 1:6, 12 mm thick and paving tiles to correct line and levels etc.complete. (The make of vitrified tiles is of Johnson, RAK bell dark colour and the tile adhesive of carafill/cerafill/Pedilite).	455	SqM		
16	Making temporary arrangement by shifting the existing SWO Counters and other cabins completely to specified position as directed by engineer in charge	1	LS		
17	Demolishing/ dismantling the old counters, partitions, panelling, false ceiling etc in existing area of around 3000 sqft carefully stacking usable items in a place suggested by bank. All the unusable materials ( as determined by the bank ) shall be cleared off from the site. Site shall be cleaned off of all debris to the satisfaction of the bank.	1	LS		
	Total amount				
	GST @ 18%				
	<b>Grand Total</b>				
	(Rupees _____ only)				