

TENDER
STATE BANK OF INDIA
LHO, KOLKATA

Construction of 11 nos Store Rooms for safe keeping of Official documents at Basement of SBI SRIBIDDHI BHAWAN

| Sl.No | DESCRIPTION | UNIT | RATE | QNTY | AMOUNT Rs. P. |
|-------|---|------|------|--------|------------------|
| 1. | Supply and Providing 230 mm thick Class A Brick Work from floor level to ceiling level at basement floor slab with cement sand ratio 1:4, with laying of two nos 6 mm reinforcement steel after every lift of 500 mm of brick work, with extra lap of reinforcement steel of 500 mm, embedded in column also, with racking, curing, hacking, cost of scaffolding, labour, materials, tools & tackles, provision for cut out for exhaust fan of dia 300 mm, cutout for ac ducting as per existing layout, transportation, OHP, etc to complete the work as per standard specification and as per drawing, as per instruction of Engineer In-Charge | cum | | 142.06 | |
| 2. | Supply & provisioning of RCC Lintle (size 150 mm x 100 mm) of cement: Sand : Stone chips ratio 1:2:4 ratio, cost is inclusive of scaffolding, shuttering, reinforcement steel, etc to complete the work as per standard IS specification and as per drawing, as per instruction of Engineer In-Charge | Cum | | 4 | |
| 3. | Applying 16mm thick plaster of both side of brick work with proper line level with racking, curing, hacking, cost of scaffolding, labour, materials, tools & tackles, provision for cut out for exhaust fan of dia 300 mm, cutout for ac ducting as per existing layout, transportation, OHP, etc to complete the work as per standard IS specification and as per drawing, as per instruction of Engineer In-Charge | Sqm. | | 1180 | |
| 4. | Providing and applying 6mm Birla White Putty / Equivalent as per standard IS specification, etc to complete the work as per direction of Engineer In Charge. | Sqm. | | 2100 | |
| 5. | Applying two coats of Washable Distemper paint over a coat of primer as per standard IS specification, etc to complete the work as per direction of Engineer In Charge. | Sqm. | | 2100 | |
| 6. | Supplying of 38 mm thick Century / Sylvan/ Regal/ Globe/ equivalent Flush Door with 1 st class Sal wooden Frame with hardware, etc. Each door and door frame should have 6 nos anchor fastners for each frame, brass tower bolt 12 " from inside, Brass handle from inside and outside, door stopper, hinges, brass hash bolt / L Drop with locking arrangements from outside. | Nos. | | 11 | |
| 7. | Supply and provisioning of screed flooring (FOR DAMAGED PARTS ONLY), maintaining the line & level with cement:sand:6mm down stone chips 1:2:4 ratio, complete the work as per specification, instruction of Engineer In Charge, stand IS specifications. | Sqm. | | 121.06 | |
| | TOTAL | | | | |

(Amount in Words: Rupees

Signature & Seal of Vendor

