



SBI INFRA MANAGEMENT SOLUTIONS PVT.LTD.

**CIRCLE OFFICE, THIRD FLOOR, STATE BANK OF INDIA, SYNERGY BUILDING,
C-6, G-BLOCK, BANDRA KURLA COMPLEX, BANDRA EAST, MUMBAI-400051**

PART – B: FINANCIAL BID

TENDER FOR:

PROPOSED INTERIOR WORK FOR ADB BRANCH, AMRAVATI

TENDER SUBMITTED BY:

NAME : _____

ADDRESS : _____

DATE : _____

TENDER INVITED BY:

Vice President & Circle Head,

SBI Infra Management Solutions Pvt. Ltd; 3rd floor, Circle Office, State Bank of India, Synergy building, C-6, G-Block, Bandra -Kurla complex, Bandra East, Mumbai-400051.

ARCHITECT :

Ashfaque Ahmed Consultancy Services Pvt.Ltd.,

289, New Colony,Sadar Nagpur – 440001

Tel : 9823054655 / 0712-2595752 / 25833493 E-Mail : craftteam9@yahoo.co.in

Tender pepar of Interior Work for ADB Branch, Amravati.

Sr. No.	Particulars	Qty.	Unit	Rate	Amount
1	<u>False Ceiling</u>				
	Providing and fixing in position 12,5 mm thick gypsum board false ceiling fixed with 16 gauge galvanised frame uported from and fixed to RCC slab with Anchor bolts. The ceiling should contain approx 40%of the ceiling area of 12mm thick Armstrong ceiling (600x600mm) beuti sky or other approved pattern and stepping. all the joints to be properly sealed with jointing tape and finished with approved jointing material. The item includes making cutouts and providing necessary frame work for light fitting, grill diffusers and ducts etc. which have to be made with frame of perimeter chanel of size 20mm x 30mm x 0.55mm. thick supported suitably and angle bead is to be used at steps to get straight line finish etc. complete. The item rate shall also include preparation of surface with sanding and 3 coats of acrylic emulsion painting approved shade over a coat of primer/ putty including necessary work etc.	330	Sq.m		
2	<u>Full Ht Glazed / Partly Glazed/ Partly Paneled Partition</u>				
	Providing and fixing in position partly glazed and partly paneled partition made of 50 mm x 50 mm x 1.2mm medium alluminium hollow square pipes framed at 0.60m to 0.45m c/c both ways covered 6 mm MR grade ply and 1mm multi-colour laminate of approved make and shade and make with 6mm thick glass panel with etching as per design and / or necessary beading patti including 3 coats of french polish including door shutters as per architectural design with heavy duty hinges handles/ locks, etc. of approved make.	41.7	Sq.m		
3	<u>Full Ht Partly glazed Partition for Server Room</u>				
	Providing and Fixing in position partly glazed & partly paneled partition made of 50mm x 50mm x 1.2 mm medium duty alluminium hollow square pipes framed at 0.60m to 0.45m c/c both ways covered with 6mm MR Grade ply and 3mm aluminium composite pannel of approved shade necessary beading patti including 3 coats of french polishing including door shutters as per architectural design with heavy duty hinges/ handles/ locks etc..of approved make.	18.7	Sq.m		

4	Low / medium height partition				
	Providing and fixing in position low/ medium height partition made of 50mm x 50mm 1.2mm medium duty aluminium hollow square pipes framed at 0.6 to 0.45 m c/c both ways covered with 6mm MR grade ply and 1mm thick laminate of approved shade and make, both sides including necessary opening / outing for receiving cheques and other papers and to receive 8mm thick float glass including all necessary openings for electric/ telephonic conduits, etc. as per requirements. (Glass area in the partition will be deducted in the measurements of the partition)	15	Sq.m		
5	Glass partition				
	Providing and fixing 8 mm thick glass with etching as per design for low height partition held with SS clips (D brackets). All exposed glasses with rounded moulding and crystal polish. All exposed woodwork to be finished in 3 coats of french polish / melamine polish.	7	Sq.m		
6	Single window counter				
a	Providing and fixing in position single window counter as per design, made of 18mm/ 19mm thick MR grade ply structure and laminated glass in approved shade, and front side teak moulding patti, duly finished with three coats of PU. Finish. All exposed external surfaces finished with 1mm laminate and internal surfaces finished with 0.8 mm laminate of approved shade and make with foot rest of 75x38mm 18mm thick ply, with 12 mm thick plain glass of 150 mm deep of counter length at service top adjacent to top with 12mm thick and 380 mm height etching glass at front including making half round opening of 150 mm dia duly finished with crystal polish and having CPU stand of 19 mm thick MR grade ply including cable manager, a key board tray with telescopic arrangement.	4.5	Rmt.		
7	Server Room Table				
	Providing & fixing server room table with 2'-3" depth using 18mm/12mm/6mm thk. MR Grade ply for all structure work, Table top, shelves, shutter, drawer, keyboard etc with 1mm thk. Laminate finish on exposed side and enamel paint finish on internal side. Locking arrangement should be done to drawers and shutters should have S.S handles of brush finish of 6" ht as approved by consultant. Provision for 3 sets of CPU stand, footrest & keyboard should be given. Wire manager should be provided at the corner of the working top.	1.8	R.mt		
8	Removing of Existing Partiton & other non re-usable furniture & disposal of same as directed out side municipal limits.		LS		
	TOTAL				
9	Removing Existing re-useable furniture excluding chair carefully and buy back of		LS		
	GRAND TOTAL				
In Words:					

Total Amount

Rupees in words:

Date _____