ANNEXURE-I

BILL OF QUANTITY FOR TELEPHONE CABLING AT AO VARANASI GROUND FLOOR, FIRST FLOOR AND SECOND FLOOR

Sr.	DESCRIPTION OF ITEMS	QTY			Amount (Rs.)
No.		(Approx)		-	(Exclusive of
			mnt	of GST)	GST)
1	Supply & Fixing of Rectangle 50 Pair MDF Box with Krone Module	12	Qty		
2	Supply & Fixing of Rectangle 300 Pair MDF Box with Krone Module	1	Qty		
3	Supply & Fixing of 50 Pair Telephone Cable 0.50 mm in solid bare	100			
	conductor with HDPE Insulation and Flame Retardant Jacketing having		Meter		
	lower cross talk and attenuation(Finolex/Polycab/Dalton).	100			
4	Supply & Fixing of 10 Pair Telephone Cable 0.50 mm in solid bare		Matar		
	conductor with HDPE Insulation and Flame Retardant Jacketing having		Meter		
5	lower cross talk and attenuation (Finolex/Polvcab/Dalton). Supply, Laying and fixing of CAT 5 Data Cable with all accessories through	4400			
5	PVC Conduit/ channel as above in SI NO. 1. Testing and ferruling (D-	1100	Meter		
	LINK/ MOLEX/ AMP/ COMMSCOPE/Schnider				
6	Supply, Laying and fixing of Heavy Duty Rigid 1" PVC Pipe/ PVC Channel	3500	Meter		
	(only AKG/CAP/PLAZA/ Allied Conduits/ SRG/New India Trading OR ISI				
	MARK), Rates are to be quoted with all accessories i.e. with bend, Saddle		i lecel		
	etc Supply 9. Fiving of Modulay, Tolonhone, Cookete DJ, 11	270	01		
/	Supply & Fixing of Modular Telephone Sockets RJ-11	270	Qty		
	Total Cost				