

**STATE BANK OF INDIA**  
**PRICE BID FOR ELECTRICAL WORKS OF SUDAMBI BRANCH**

Sl No	Particulars : Detailed Specifications	Unit	Qty	Rate	Amount
<b>PART-A : ELECTRICAL WIRING WORKS</b>					
1	<p><b>ENERGY METER CUBICLE</b> : Fabrication, Supply, Installation, testing &amp; Commissioning of energy Meter cubicle made out of</p> <p>3 Nos. 63A Open Type bakelite cutout fuse unit with 63A HRC</p> <p>1 no. 63A 4 pole SFU with 63A HRC fuse (HPL/C&amp;S/Indoasian)</p> <p>Complete with all inter connections and powder coated painting-RAL 7032 siemens grey.</p>	Set	0		
2	<p><b>BUILDING MAIN PANEL : MAINS CHANGE OVER PANEL</b></p> <p>Supply and installation of 63A 4pole ON Load Change over switch with suitable metallic enclosure with cable entry Box and Powder coated painted with 6nos of 2A SP MCB and LED (R,Y,B) indicators for the identification of EB/ DG Set – ON &amp; neat marking thereof: (GA drawing to be got approved from consultant/Engineer before fabrication &amp; supply)</p> <p>a. Change over switch : 63A On-Load COS</p> <p>b. MFM - (c 0.5) to show the V,A,pf,kW,kVA,etc details (L&amp;T or Schnider)</p> <p>c. SPD - Type-1+2</p> <p>d. R,Y,B Indicators for EB &amp; DG supply (6nos)</p> <p>e. 1A SP MCB - 6 nos</p> <p>Complete with all inter connections and powder coated painting-RAL 7032 siemens grey.</p>	Set	1		
3	<p>Supply &amp; Installation of 20 KVAR automatic capacitor panel cubical type, floor mounting made of 16.SWG CRCA sheet.,</p> <p>Incoming</p> <p>63A, 25kA, 4P MCCB with spreader</p> <p>0-100A ammeter with selector switch</p> <p>RYB indicating lamp</p> <p>0-500 Volts, Voltmeter</p> <p>6 Stage A.P.F.C. Relay</p> <p>Outgoing</p> <p>63A TPMCB</p> <p>Capacitor duty contactor</p> <p>5KVAR Resin Capacitor with Harmonic fitter</p> <p>ON-OFF push button &amp; Ind Lamp</p>	Set	0		
4	<p>Main DB – (VTPN - DB): Supply, Installation, testing and Commissioning of Double Door TPN DB consisting of the following.</p>	Set	1		

	<p><b>Double door 4-way VTPN MCCB VDB</b></p> <p><b>Incomer</b>  40A, 4P MCCB, 16kA</p> <p>Outgoings :</p> <ul style="list-style-type: none"> <li>40A, TP MCB (C-series) -0nos</li> <li>25A, TP MCB (C-series) -1nos</li> <li>16A,TP MCB (C-series) - 2nos</li> <li>10A, SP MCB (C-series) - 3nos</li> </ul> <p>80A COPPER Bus-bar for 3 phase  Complete with all inter connections.</p>				
5	<p>ACDB – (TPN - DB): Supply, Installation, testing and Commissioning of Double door (4-way) TPN MCB VDB consisting of the following.</p> <p><b>Double door 4-way TPN MCB VDB</b></p> <p><b>Incomer</b>  25A,300mA 4P RCCB +25A MCB C-series</p> <p>Outgoings :</p> <ul style="list-style-type: none"> <li>25A, TP MCB (C-series) -1nos</li> <li>16A, SP MCB (C-series) - 3nos</li> <li>10A, SP MCB (C-series) - 0nos</li> </ul> <p>80A COPPER Bus-bar for 3 phase  Complete with all inter connections.</p>	Set	1		
6	<p>L+RPDB: Supply, Installation, testing and commissioning of Double door TPN MCB DB consisting of the following.</p> <p><b>Double Door 4-way TPN MCB DB</b></p> <p>Incomer:  16A,100mA 4P RCCB +16A MCB C-series</p> <p>Outgoings :</p> <ul style="list-style-type: none"> <li>16A,30mA DP RCCB - 2 nos.</li> <li>10A, SP MCB (C-series) 8 nos.</li> <li>6A, SP MCB (C-series) -4 nos</li> </ul> <p>Complete with all inter connections</p>	Set	1		
7	<p>LDB: Supply, Installation, testing and Commissioning of Double door TPN MCB DB consisting of the following.</p> <p><b>Double door 4-way TPN MCB DB</b></p> <p>Incomer :  25A,30mA 4P RCCB + 25A MCB (C-series)</p> <p>Outgoings :</p> <ul style="list-style-type: none"> <li>10A, SP MCB (B-series)-8 nos</li> <li>6A, SP MCB (B-series) -4 nos</li> </ul> <p>Complete with all inter connections.</p>	Set	0		

8	<p>ESSENTIAL DB : Supply, Installation, testing and commissioning of Double door TPN MCB DB consisting of the following.</p> <p><b>Double Door 6-way TPN MCB DB</b></p> <p>Incomer: 32A MCB C-series</p> <p>Outgoings : 25A, TP MCB (C-series) -2 nos. UPS input, 16A, SP MCB (C-series) 0 nos. Board light 6A, SP MCB (C-series) - 2 nos. UPS room exhaust fan 24hr digital timer 1NO,1NC -2 Nos exhaust fan &amp; Signage lights</p> <p>Complete with all inter connections.</p>	Set	1		
8.a	<p>ATM DB : Supply, Installation, testing and commissioning of Double door TPN MCB DB consisting of the following.</p> <p><b>Double Door 6-way TPN MCB DB</b></p> <p>Incomer: 25A MCB C-series</p> <p>Outgoings : 25A, TP MCB (C-series) -0 nos. UPS input DP 20A RCCB 30mA, 16A SP MCB (C-series) 1 nos. Board light</p> <p>DP 16A RCCB 300mA, 16A SP MCB (C-series) 1 nos. AC 10/6A, SP MCB (C-series) -3 nos. Lighting 24hr digital timer 1NO,1NC - 2 Nos Board light ( Branch +ATM)</p> <p>Complete with all inter connections.</p>	Set	0		
9	BUS BAR Box – Supply, Installation, testing and Commissioning of single door Bus bar box with following .				
a.	100A Copper bus bars-25mmX3mm X150mm -4nos with insulators mounted on insulator bushes. \ \  for remote UPS Rooms	Set	0		
b.	200A Copper bus bars-25mmX4mm X150mm -4nos with insulators mounted on insulator bushes. \ \  for remote UPS Rooms	Set	0		
c.	63A 4P Isolator with metal enclosure as Non- essential load cut-off switch at entrance.	Set	1		
10	<b>UPS IN PUT DB</b> Supply and installation of 40 A FP MCB ISOLATOR in suitable metallic enclosure for UPS Input.	Set	2		
11	<b>UPS OUT PUT DB</b> Supply and installation of 32A DP MCB ISOLATOR in suitable metallic enclosure for UPS Input.	Set	2		

12	<b>UPS CHANGE OVER PANEL:</b> Supply erection testing and commissioning of 2 Nos. 40 A rotary type change over switch in suitable metal box with 4 Nos. LED indicator for input / output identification. UPS Output change over switch board. Complete with all inter	Set	1		
13	<b>COMPUTER DB:</b> Supply, erection, testing and commissioning of wall mounted type double door dust and vermin proof SPN MCB DB fixed on wall comprising the following:  8WAY SPN MCB DB - Incomer : 20A, DP MCB (C-series) Outgoings : 10A, SP MCB (C-series) 6A, SP MCB (C-series) Complete with all inter connections.	Set	2		
14	Supply and installation of suitable weather proof enclosure for local control of 3ph/1ph air conditioners. a. Supply and installation of 64A FP MCB (D-series) in suitable weather proof enclosure(IP65) for local control of 3ph conditioners. b. Supply and installation of 20/32A DP MCB in suitable weather proof enclosure(IP65) for local control of 3ph/1ph air conditioners.	Set	0		
	c. Supply and installation of 20/32A TP MCB in suitable weather proof enclosure(IP65) for local control of 3ph air conditioners.	Set	2		
		Set	1		
15	Supply and installation of DOL starter for PUMP motor with thermal overload protection, for 2kW motor	Set	0		
16	<b>CABLE LAYING AND TERMINATIONS:</b> Supply, laying and dressing of the following size of 1.1 KV grade <b>XLPE</b> insulated armoured cable with aluminium conductor concealed or clamped on wall / ceiling / trench / cable tray if necessary.  i) 4x240 Sq.mm AYFY ii) 4x95 Sq.mm AYFY iii) 4x70 Sq.mm AYFY iv) 4x50 Sq.mm AYFY v) 4x35 Sq.mm AYFY vi) 4x25 Sq.mm AYFY vii) 4x16 Sq.mm AYFY viii) 3x6 Sq.mm AYFY	m	0		
		m	0		
		m	0		
		m	0		
		m	0		
		m	30		
		m	60		
		m	30		
		m	0		

17	End termination of the following size of cables using flange type cable glands and heavy duty tinned aluminium crimping type cable sockets including gland earthing. i) 4x240 Sq.mm AYFY ii) 4x95 Sq.mm AYFY iii) 4x70 Sq.mm AYFY iv) 4x50 Sq.mm AYFY v) 4x35 Sq.mm AYFY vi) 4x25 Sq.mm AYFY vii) 4x16 Sq.mm AYFY viii) 4x10 Sq.mm AYFY	set set set set set set set set	0 0 0 0 0 2 6 2		
	xi) 4x6 Sq.mm AYFY	set	0		
18	<b>GI - CABLE TRAY:</b> Supply and installation of medium duty GI Ladder type cable tray of following size. (Rate shall be inclusive of all bends supports,etc. And supports to be not more than 1000mm apart) i) 500mmx50mm(WxH) ii) 650mmx50mm(WxH)	m m	15 0		
19	<b>EARTHING AND LIGHTING PROTECTION</b> a. Supply and providing ISI pipe earthing as per IS 3043 with 2.5m long 40mm dia B class G.I. pipe providing GI clamp at the top of the GI pipe test joint, filling around the GI pipe at the radius of 15cm with homogeneous mixture of charcoal, common salt and river sand up to height of 2.5m from the bottom and the rest of the portion with excavated soil, providing brick work masonries, plastering, fixing cast iron cover of 30x30cm size etc. complete b. Making of Copper plate(600mmx600mmx3mm) Earth-pit as per IS 3043 complete with charcoal, funnel set etc., including making of 450 x 450mm brick masonry chamber with CI / stone / fabricated / RCC cover with lifting handles stone / fabricated / RCC cover with lighting handles etc., complete as required. c. EARTH CONDUCTORS Supply and laying of the following size of bare copper conductor along with above cables, for interconnections between panels, DBs, change over switches etc.and also for interconnections between earth pits. i) No.10 SWG d. Supply and laying of 2 X No. 10 SWG copper conductor through 20mm PVC conduit for UPS earthing.	Set Set m m	2 2 50 50		

	e. Supply and laying of 25x3mm GI strip/tape supported on porcelain insulator on every 1m distance for lightning arrester system – the strip shall be insulated from having any direct contact from the building -shall use UPVC conduits while crossing the wall etc.	m	0		
	f. Supply and installation of - Copper Lightning arrestor spike – of 1m supported over proper insulator and connected to GL strip using proper nut bolt system.	Nos	0		
	g. Supply & installation of 4m length 40mm dia C-class GI pipe to be fixed over the terrace of the building to erect Copper lightning arrester spike. The pole shall be mounted on insulators.	Set	0		
	h. Supply and providing tinned copper earth bench using 25 x 3 mm copper strip (25 Cm in length)	Set	4		
20	<b>WIRING FOR LIGHT, FAN, PLUG, SOCKETS ETC</b> : Point Wiring: Supply and wiring for light /fan/exhaust fan/calling bell/mirror lamp/ bulkhead light/ wall fans etc . With 3plate ceiling rose and by using 3x1.5 sqmm. (1.5sqmm) . PVC insulated copper conductor wire in 20mm dia 1.5mm thick rigid PVC conduit , controlled by 5A modular switches with provision for modular type Ceiling fan regulator on separately fabricated MS Box. The M.S box should be earthed properly. One way point.				
	a. Single light point controlled by a 6 Amp switch.	Nos	39		
	b. each Secondary light point connected to the single light points controlled by a switch.	Nos	25		
	c. 2-WAY controlled lighting point for staircase, bed switch etc.	Nos	1		
	d. Wall fan / Exhaust fan point - 6A, 3 pin modular socket on suitable metal box for wall fan controlled by switch in common SB	Nos	9		
	e. Ceiling fan point - controlled by 6A switch in common SB with modular stepped regulator.	Nos	3		
21	Supply and fixing of Modular type <b>5A</b> 3pin plug points controlled by 5A modular switch mounted on suitable box (on common switch board) only in Strong room, Record/ Stationary rooms & Pantry	Nos	2		
22	Supply and fixing of Modular type <b>5A</b> 3 pin plug points with <b>5A</b> modular type switch in separate location.	Nos	7		
23	<b>Raw Power Switch Box</b> : Same as above but for <b>2 Nos.</b> modular type <b>5 A</b> 3 pin plug points with <b>2 nos. 5A</b> modular type switch in separate location. (both sides of cash cabin desk, nodes etc)	Nos	6		

24	Supply and fixing of modular type 15A plug socket with 15A modular type switch mounted on suitable Box. .(for Mgr cabin, Cash Cabin, Pantry, Water cooler, etc ) .	Nos	1		
25	Supply and installation of combined 5A modular plug socket with 5A modular switch & 15A combined modular plug socket with 15A modular switch in single box.(for EB supply at cashier counters / Manager cabin/UPS for ATM)	Nos	1		
26	Supply and providing <b>16A</b> plug top and 1.5m long 3 core 2.5Sqmm flexible copper cable (FRLS Type) for taking incoming supply from 16A socket. (For UPS/EB supply to back office manager & EB supply to strong room, line printer and record/ stationary rooms)	Nos	2		
27	Supply and Installation of <b>25A</b> Modular type 3 pin plug socket with suitable metallic box for air curtain/ air conditioners.	Nos	3		
28	Supply and Installation of <b>20A /32A</b> Modular type <b>DP</b> switch having indicator with suitable metallic box for the local control of the air conditioners/air Curtain.	Nos	3		
29	<b>UPS Power Stations</b> ::: Supply install Test and commissioning of computer power stations with 3nos 5A modular type socketswith 1nos 15A modular type sockets controlled with( 1nos. 15A modular type single pole switch with indicator mounted on M/S Box.) / controlled by master switch ( item 39) The boxes should be Fixed on – wall/ partitions(wooden, concealed or open as required at site. Maximum 3 sets per Circuit.	Nos	12		
30	Same as above but for 2 Nos. modular type 15 A 3 pin plug points with 2 nos. 15A modular type switch in separate location.(for Data Kraft rack / I/O Rack/ Cash cabin)	Nos	2		
31	Same as above but for 2 Nos. modular type 6 A 3 pin plug points with 2 nos. 6A modular type switch with indicator in separate location.(for countners, Head cashier , etc on wall panel/ partition - Above the tabe and on wall for token machine, CCTV, TV etc)	Nos	2		
32	Supply, install, test and commissioning of 16A modular type master switch with indicator with suitable PVC box for the main control of UPS stations in the counters.(common switch to control all UPS station in each counter)	Nos	12		
33	Supply & Installation of USB charger outlets controlled by 6A switch (in Privillage lounge/ Hall)	Nos	1		

34	<b>CIRCUIT WIRING:</b> Supply and wiring wall / floor etc. / recessed / surface as per colour code with 3 runs of 1.1KV grade 1.5 Sqmm PVC insulated flexible copper wire for phase neutral and earth conductor with standard colour coding, through ISI marked 20mm dia(medium) rigid PVC conduit with all accessories. The rate includes the cost of complete wiring from switch box to switch box. THE WIRING SHALL BE DONE CONSEALED .	m	50		
35	Same as above but with 3 x 2.5 Sq.mm PVC Insulated copper wire(FRLS Type).(for lighting main circuit, 15A plug points & UPS point wiring ) (power circuit to VRF IDUs)	m	500		
36	Same as above but with 3 X 4sqmm. PVC insulated copper wire(FRLS Type). (for 1.5 / 2 T AC and UPS Out put COS to computer DB and for the Name Boards if there are multiple name boards or extra ordinary lengthy– Name Boards )	m	70		
37	Same as above but with 3 x 6 Sq.mm PVC Insulated copper wire through rigid conduit (32mm) on wall and flexible conduit on floor for UPS Input.(4m length x 2 UPS) , AC input 3Tr/ 4Tr inv AC	m	30		
38	Same as above but with 4 x 2.5 Sq.mm with 2 x 1.5 sq.mm (for3ph 3T inverter AC units) in 32mm dia conduit	m	0		
39	Same as above but with 4 x 4Sq.mm with 2 x 2.5 sq.mm (for3ph 4T inverter AC units)	m	0		
40	Same as above but with 4 x 6 Sq.mm with 1 x 4 sq.mm (for3ph UPS input)	m	30		
41	Same as above but with 4 x 10 Sq.mm + 1 x 6 sqmmPVC Insulated copper wire through rigid conduit on wall of 38mm dia	m	0		
42	PVC CONDUITS:Supply and Fixing of following sizes of FRLS PVC conduit along with the accessories in surface in ceiling/ recess in walls, flooring including cutting the wall / floor etc., and making good the same in case of recessed conduit as required. a. 32mm dia. Conduit (Medium) b. 25mm dia. Conduit (Medium) c. 20mm dia. Conduit (Medium)	m m m	10 10 10		
43	<b>LIGHT FIXTURES &amp; FANS</b> a Supply and Installation of 36~40W 600mmx600mm Square recess mounting (gypsum board ceiling) LED type luminaire (including required fixing frame, chain for suspending from RCC ceiling ) -Wipro, HPL, Havells, Orcus, 595mmx595mm cut out	Nos	15		



b	Supply & installation of 20 ~18 Watts DLED type LED light fitting with lamps and white reflector on false ceiling ( UPS Light points) - ~ 205mm cut out	Nos	7		
c	Supply & installation of 9~10 Watts DLED type LED light fitting with lamps and white reflector on false ceiling - ~135mm cut out	Nos	25		
d	Supply and Installation of minimum 5m length flexible LED strip lights of 22~24 watts in false ceiling covers of Blue / warm White shades with necessary LED driver of same make	m	0		
e	Supply and fixing of 2~3 watts LED spot lamp / swivel downlight - warm light for photoframe / decor lighting	Nos	0		
f	Supply and fixing of 1 X 20W LED Batten light set on wall /ceiling. Slim with metal body	Nos	10		
g	Supply and Installation of 20~40W 2'x2' suspended / (drop) ceiling hanging type Round luminaire decorative (including required fixing frame ) -Wipro, HPL, Havells, Orcus, Philips	Nos	0		
h	Supply and Installation of 36~40W out door type street light fixture LED including required fixing frame/pipe, ) -Wipro, HPL, Havells, Orcus	Nos	0		
i	Supply & installation of 60 Watts LED light down lighter and on false ceiling (for double height area) - Wipro, HPL, Havells, Orcus, CGL.	Nos	0		
j	Supply & installation of calling bell	Nos	1		
k	Supply and installation of 9" size medium duty exhaust fan. (Toilets/ dining)	Nos	2		
l	Supply and installation of 12" size medium duty exhaust fan. (UPS Room)	Nos	2		
m	Supply and Installation of 400 mm sweep wall fan METAL BODY AND BLADES, 3 PIN TYPE PLUG	Nos	5		
n	Supply and installation of 1200mm sweep ceiling fan. <b>5 star rated.</b> (High Speed)	Nos	3		
o	Supply and providing fan rod with painting (upto 1m length) (other than that supplied with fan and if required)	Nos	0		
p	Supply and providing fan hook on ceiling.	Nos	0		
q	Supply and installation of 9W LED bulb with suitable batten holder (Toilets & UPS light points)	Nos	3		
r	Supply and Installation of step type modular electronic regulator, 100W	Nos	3		
44	Electrical safety - RUBBER mats of 1.1kV grade 1.8mx.0.9m	Nos	1		
45	Supply and fixing of : 1nos First aid kit, Safety chart, Danger boards-2nos , No Admission boards-1nos	Set	1		

46	Marking of Panels, DBs, its switch and fuse ratings, cable size, location etc (Neat identification from top to extreme load end of both light and power distribution including EB / UPS plug sockets and generator switch boards) using white / black paint and stencil. (free hand writing not allowed). Good quality stickers may also be used.	L.S	1		
47	Charges for Preparation of SLD (Single Line Diagram) , Network diagram of the whole electrical & LAN installations using AutoCAD, Lamination and displaying it inside the UPS room. (Size – A3 /A2/A1).	L.S	1		
48	Service charges for liaison work with EB authorities on behalf of bank for getting sanction for additional load, getting order for statutory payments, shifting/replacements of suitable. Energy meter meter if necessary, submission of completion report, obtaining final load sanction from concerned EB and displaying it in the UPS room after lamination. Etc.	L.S	0		
49	Arranging temporary wiring for counters and cabins during renovation work	L.S	0		
50	Removing old and unwanted wirngs, panels, fixtures from the premises, and disposing the same.	L.S	0		
	PART - A TOTAL AMOUNT IN FIGURES				

<b>PART-B TELEPHONE WIRING</b>					
1	Supply and wiring using 2 pair telephone cable (0.5mm <sup>2</sup> ) in 20mm PVC conduit from the KRONE Box to the individual points. One separate cable for each point. Number of cables in one conduit limited to 5.				
a.	2 pair telephone cabling	m	150		
b.	10 pair telephone cabling	m	0		
2	Supply and fixing of RJ 11 type modular telephone socket on suitable PVC / metal boxes.				
a.	Telephone socket - single (modular type)	Nos	3		
b.	Telephone socket - double (modular type)	Nos	1		
3	Supply and installation of KRONE connector telephone junction box of 40 pair (double door type).	Set	0		
4	Supply and installation of KRONE connector telephone junction box of 20 pair.	Set	1		
PART - B TOTAL AMOUNT IN FIGURES					
<b>PART-C : PA &amp; MUSIC SYSTEM</b>					
1	Supply and wiring as per colour code transparent speaker cable 1.50sqmm PVC insulated stranded copper wire 2 runs through ISI grade 20mm conduit for speakers.	m	0		
2	Supply and providing 9W recessed type speakers on ceiling CS 663 T Ahuja make speaker.	Nos	0		
PART - C TOTAL AMOUNT IN FIGURES					
<b>PART-D : DATA CABLING</b>					
1	Supply and laying of CAT 6 UTP cable through 25mm dia rigid PVC conduit with all accessories etc.	m	470		
2	Supply and fixing of 2nos of CAT 6 Modular Information outlet with suitable back box on wall / partitions etc.	Nos	6		
3	Supply and fixing of 1nos of CAT 6 Modular Information outlet with suitable back box on wall / partitions etc.	Nos	5		
4	Supply and installation of 9U wall mounted type rack. (HCL/Valrack make)	Nos	1		
5	Supply and Installation of CAT6 24 port patch panel in the floor/wall mounted type rack. With cable manager	Nos	1		
6	Supply and installation of CAT6 26 port (1000Mbps) switch in the wall/floor mounted type rack. Make/Model- Cisco2960/2960x only	Nos	0		
7	Supply and installation of 1 m long patch chord. (CAT 6)	Nos	17		
8	Supply and installation of 2 m long patch chord. (CAT 6)	Nos	11		
9	Supply and installation of 3 mlong patch chord. (CAT 6)	Nos	1		
10	Supply and installation of 5 mlong patch chord. (CAT 6)	Nos	0		

11	Testing of NODES with reports. (with PENTA scan reports)	Nos	17		
PART - D TOTAL AMOUNT IN FIGURES					
PART - A					
PART - B					
PART - C					
PART - D					
TOTAL (Excluding GST)					