

BILL OF QUANTITIES FOR INTERIOR WORKS AT STATE BANK OF INDIA, REGIONAL BUSINESS OFFICE-IV, AT JALANDHAR., (PB.)

Sr.no	Description Item of Work	Qty	Unit	Rate	Total Amount
1	Wooden Partitions with Laminate				
	Low/Full Height partly Glazed (with etching/filming) & partly both side laminated Partitions: Providing & fixing partition made of 44 mm X 44 mm X 16 Gauge aluminium extruded sections frame @ 2'-0" to 2'-0" c/c vertically & horizontally. The frame shall be fixed rigidly at floor level as well as ceiling with rawl plugs. The frame work to be cladded with 8mm thick commercial ply and 1.0mm thick laminate of APPROVED make in specified pattern as per interiors details on both sides .				
	Also 2 1/2"X5/8" teak wood section shall be provided with 12mm thk. glass including etching/ filming work as per interior details where ever specified. The rate shall also include for providing grooves in laminate & wood.The work also includes dismantaling/removal of any existing/old partition and removal of same from site to contractor owns dump. Note: (i) All ply to be sprayed with anty termite and anti borer spray. (ii) Rates to include all necessary supports and as per details (iii) Measurements to be recorded up to finished false ceiling level.				
	Full ht.	80.00	Sq.mt		
	Low ht.	7.50	Sq.mt		
	Comm. Ply/ Board : (Make : Century:Sainik/Green :Ecotech/Archidply)				
	Laminate : (Make: Greenlam,Merino,Century,AICA)				
	Glass : (Make: AIS/ Saint-Gobain/ Modigaurd)				
	Aluminium : (JINDAL/HINDALCO/MAHAVEER)				
2	Wooden Partitions with Teak Ply				
	Low/Full Height partly Glazed (with etching) & partly both side laminated Partitions: Providing & fixing partition made of 44 mm X 44 mm X 16 Gauge aluminium extruded sections frame @ 2'-0" to 2'-0" c/c vertically & horizontally. The frame shall be fixed rigidly at floor level as well as ceiling with rawl plugs. The frame work to be cladded with 8mm thick commercial ply and 4.0mm thick TEAK PLY as/approval make in specified pattern as per interiors details on both sides .				
	Also 2 1/2"X5/8" teak wood section shall be provided with 12mm thk. glass with etching work as per interior details where ever specified. The work includes spirit polishing of appprv. shade on teak wood moulding and Teak Ply complete in all respect to the entire satisfaction of the Architect/Engineer in charge.The work also includes dismantaling/removal of any existing/old partition and removal of same from site to contractor owns dump. Note: (i) All ply to be sprayed with anty termite and anti borer spray. (ii) Rates to include all necessary supports and as per details (iii) Measurements to be recorded up to finished false ceiling level.	48.00	Sq.mt		
	Comm. Ply/ Board : (Make : Century:Sainik/Green :Ecotech/Archidply)				
	Teak Veneer/Ply : As per Selection @70/- Sq.ft				
	Glass : (Make: AIS/ Saint-Gobain/ Modigaurd)				
	Aluminium : (JINDAL/HINDALCO/MAHAVEER)				
3	Fixed Toughned Glass Partitions				
	Providing & Fixing 12mm thk. Toughned Glass Panels with SS glass connectors as per manufacturers guidelines of approved make, rested/fixed on Wall Connecting Profile (paid separately) on floor surface, fixed in position, with other sides recessed in ceiling /partition with teak wood beading or conceled wooden members in ceiling as per interior details & open side to be grinded and polished as per the instruction of the Achitect/Engineer in charge.	8.50	Sq.mt		
	Hardware: (Make : Godrej/Dorma/Ozone/Stanley)				
	Glass : (Make: AIS/ Saint-Gobain/ Modigaurd)				

4	Wall Connecting Profile				
	Providing and fixing wall connecting profile in floor to hold 12mm thk. Toughened glass.	6.00	Rmt		
	Hardware: (Make : Godrej/Dorma/Ozone/Stanley)				
5	Toughned Glass Doors				
	Providing & Fixing Openable 12mm thk. Toughned Glass Door , holded with Patch fitting (i.e. bottom & top patch,L-Patch, floor machine & Door lock),fixed in position as per manufacturers guidelines including side grinded and polished. The Job also includes providing & fixing of 24" long SS handle & provisions of holes/cuts in glass panel to facilitate fixing of Patch fitting & Handle. The job shall be complete in all respects,including necessary hardware, complete in all respects as per the instruction of the Architect / Engineer in charge.	7.00	Sq.mt		
	Hardware: (Make : Godrej/Dorma/Ozone/Stanley)				
	Glass : (Make: AIS/ Saint-Gobain/ Modigaurd)				
6	Wall Paneling				
	Providing and fixing paneling over the existing wall made out of framework of 50 mm X 25 mm - 18 gauge section un anodised Aluminium (as per requirement) frame work @ 16" to 24" c/c vertically & horizontally.The frame work to be clad with 12.0 mm thick commercial ply/12mm thk. water proof MDF as per detail and following finishigs as per drawing and instructions. All exposed surfaces to be clad with teakwood moulding of size 30 mm X 12.0 mm made to shape.				
	The work should be complete in all respects including provisions of grooves duly designed & finished. All wood to be treated with wood preservatives of approved ISI quality. All exposed teak wood shall be spirit polished with matching pigment. Payments shell be made only for exposed surfaces & actual measurement at site, no payment shell be made for paneling behind furniture such as tables, Credenza , storage etc.The work also includes dismantaling/removal of any existing/old panelling and removal of same from site to contractor owns dump.				
	Comm. Ply/ Board : (Make : Century:Sainik/Green :Ecotech/Archidply)				
	Laminate : (Make: Greenlam,Merino,Century,AICA)				
	MDF : (Make: Green,Action Tesa,Century)				
	Teak Veneer/Ply : As per Selection @70/- Sq.ft				
i.	Panelling with Teak Ply with Spirit Polish	20.00	Sq.mt		
ii.	Panelling with laminate	16.00	Sq.mt		
iii.	Panelling with 12mmMDF with Spray Paint/Texture including additional 6mm MDF as per pattern and 1/2" to 1" size mdf moulding as per pattern or 1" to 2" thk. MDF Bands., complete in all respects.	10.00	Sq.mt		
v.	Panelling with laminate with additional 6mm thk. Mdf over existing ply base to create groove.	10.00	Sq.mt		
vi.	Korian Laminate (Charcolite) panelling. Providing and fixing as/drawing 3-4mm thk.Korian Laminate (Charcolite) panelling of Furns & Lams/Sibu make pasted with adhesives of Pidilite (probone) as per manufacturers specification and drawing.	8.00	Sq.ft		
8	Officer's & Staff Tables				
	Table made of 19 mm thk. Commercial ply with front and side visible vertical surfaces to be finsihed with laminate 1mm thick (of approved shade & with 35mm thk. Post forming top,as per drawing and thickness made by joining two boards.. The front of the table top shall be projected as per drawing.The modesty guard shall be finished with 12.0 mm thk. toughed glass with 4" wide S.S. Spacer. Provision for 3" dia. round / 3" square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the table. The PVC Edge binding tape will be provided on all the edges of the table, including bottom touching the floor and the drawers. The table shall have a keyboard tray of size 600 X 270 fixed on channels, as per manufacturers instructions / specifications.				
	A full depth CPU shelf 15" wide shall be provided at left hand side of counter underneath the working top, at 4" above the floor level and 3" away (horizontally), from vertical end which will be made of 19mm thick commercial ply finished with laminate 1mm thk. and PVC Edge binding tape on two visible sides. three lockable drawer running on side mounting drawer slides (channels) ofmade of 19 mm thick commercial ply with 1mm				

	thick laminate on front face, handle / knob and magnetic catcher shall be provided on one side of the table as per layout. The sides of the drawer shall be made of 19 mm ply, bottom of 8 mm thick plywood & front of 19 mm thick bply. A full length foot rest made of hard wood 3" x 1½" section shall be provided at 4" above floor level. Non-Visible/inside surfaces i.e. inside / leg-space of table, inside of drawer / cupboard shall be finished in 0.8mm thk. laminate of white/off white shade. The work also includes dismantling/removal of any existing/old furniture and removal of same from site to contractor owns dump. The Work also includes providing and fixing 8mm thk. glass top on table with grinded and polised edges including hole of cable manager.				
	Comm. Ply/ Board : (Make : Century:Sainik/Green :Ecotech/Archidply)				
	Laminate : (Make: Greenlam,Merino,Century,AICA)				
	Hardware: (Make : Godrej/Ozone/Hettich/Hafele/Harison)				
a	Size 5'0" X 2'6" X 2'6"	1.00	Nos		
b	Size 6'0" X 3'0" X 2'6"	1.00	Nos		
8	RECEPTION/ATTENDENT Desk Split Level Reception desk made of 19 mm thk. Commercial ply with front and side visible vertical surfaces to be finished with Teak Veneer 4mm thick (as/selection); with Table top @ 2'-6" ht finished in laminate ,and customer top at 3'-3"/3'-6"ht. with as per drawing finished in corian stone. Also the modesty guard made out of comm.ply shall be finished with corian stone as per drawing. Provision for 3" dia. round / 3" square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the table. The PVC Edge binding tape will be provided on all the edges of the table, including bottom touching the floor and the drawers. The table shall have a keyboard tray of size 600 X 270 fixed on channels, as per manufacturers instructions / specifications. A full depth CPU shelf 15" wide shall be provided at left hand side of counter underneath the working top, at 4" above the floor level and 3" away (horizontally), from vertical end which will be made of 19mm thick commercial ply finished with teak veneer				
	4mm thk. and PVC Edge binding tape on two visible sides . three lockable drawer running on side mounting drawer slides (channels) of approved make made of 19 mm thick commercial ply with 1mm thick laminate on front face, handle / knob and magnetic catcher shall be provided on one side of the table as per layout. The sides of the drawer shall be made of 12 mm thick plywood / 19 mm ply, bottom of 6 mm thick plywood & front of 19 mm thick bply. A full length foot rest made of hard wood 3" x 1½" section shall be provided at 4" above floor level. Non-Visible/inside surfaces i.e. inside / leg-space of table, inside of drawer / cupboard shall be finished in 0.8mm thk. laminate of white/off white shade.				
	Comm. Ply/ Board : (Make : Century:Sainik/Green :Ecotech/Archidply)				
	Laminate : (Make: Greenlam,Merino,Century,AICA)				
	Hardware: (Make : Godrej/Ozone/Hettich/Hafele/Harison)				
	Size 4'6"-5'-0" X 2'0" X(2'6" and 3'-3") split ht.	1.00	Nos		
7	Shifting & Re-furbishing of Existing Officer's & Staff Tables Shifting and Re-furbishing of existing tables., the work includes shifting of table from one location to another and re-arrangement of the same in new location, including providing and fixing of laminate as and where required of same color, wooden beading as and where required. The work also includes replacement of drawer and keyboard tray channels., complete the work as per the satisfaction of Engg-in-charge/Architect.				
a	Size 5'0" X 2'6" X 2'6"	2.00	Nos		
b	Size 6'0" X 3'0" X 2'6"	3.00	Nos		
10	Side Credenza				
	Providing & fixing Side credenza (18" deep) made of 19 mm thick commercial ply and 6 mm thick plywood on back side & 1mm thick laminate of approved shade on top horizontal surface & vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The credenza will have three drawers, horizontally running on side mounting drawer slides (channels) of approved make. The remaining part of the credenza will have cupboard with shutters and one shelf.				

	The shutters with handle / knob and magnetic catcher shall be provided beneath the drawers all non visible/inside surfaces shall be finished with white/off white laminate 1mm thk. and teak wood edges / lipping / beading shall be Spirit polished with matching pigment.				
	The work also includes dismantaling/removal of any existing/old furniture and removal of same from site to contractor owns dump.				
a	Officer's & Staff side credenzaas per Drawing & specification mention in item above. Size - 3'-0" / 4'-0" X 1'-6" X 2'-6" (W X D X H)	4.00	Rmt		
	Comm. Ply/ Board : (Make : Century:Sainik/Green :Ecotech/Archidply)				
	Laminate : (Make: Greenlam,Merino,Century,AICA)				
	Hardware: (Make : Godrej/Ozone/Hettich/Hafele/Harison)				
	Teak Veneer/Ply : As per Selection @70/- Sq.ft				
11	Back credenza / Storage				
	Providing & fixing back credenza 18" deep (top surface 18") & 30"/36" HT. made of 19 mm thick commercial ply board and 6 mm thick plywood on back side & 1mm thk laminate of approved shade on top horizontal surface & vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The credenza will have drawer 4"high, horizontally running on side mounting drawer slides (channels) .The remaining part of the credenza will have cupboard with shutters and one shelf. The shutters with handle / knob and magnetic catcher shall be				
	provided beneath the drawers and non-visible/inside surfaces should be finished in 1mm thk. laminate of white/off white shade and teak wood edges / lipping / beading shall be Spirit polished with matching pigment	8.00	Sq.mt		
	The work also includes dismantaling/removal of any existing/old furniture and removal of same from site to contractor owns dump.				
	Comm. Ply/ Board : (Make : Century:Sainik/Green :Ecotech/Archidply)				
	Laminate : (Make: Greenlam,Merino,Century,AICA)				
	Hardware: (Make : Godrej/Ozone/Hettich/Hafele/Harison)				
10	Shifting & Re-furbishing of Existing Storage Cabinets				
	Shifting and Re-furbishing of existing storages., the work includes shifting of storage from one location to another and re-arrangement of the same in new location, including providing and fixing of laminate as and where required of same color, wooden beading as and where required. The work also includes replacement of handles. magnetic catchers, tower bolt etc., complete the work as per the satisfaction of Engg-in-charge/Architect.	15.00	Sq.mt		
	Comm. Ply/ Board : (Make : Century:Sainik/Green :Ecotech/Archidply)				
	Laminate : (Make: Greenlam,Merino,Century,AICA)				
	Hardware: (Make : Godrej/Ozone/Hettich/Hafele/Harison)				
11	Providing and placing the Conference Table (Size : 8'-0"/10'-0"x 24'-0") base made out of premium quality 18mmthk. marine ply as per design/detailed drawing (i.e providing vertical supports at 4'-0"distances and wrapped with18mm . thk. marine ply from both sides) the outer surface shall be clad with additional 6mm flexi ply to attain smooth finish, finally wrapped with teak veneer polished in approved shade.The top of table shall be made with 2 no's 18mm thk. marine ply . The outer exposed side of table top shall be finished with Teak Wood moulding of 3"x 1.5" made to shape.Table top shall have additional 4mm thk. teak veneer in 2 different shades pasted on commercial ply base, fixed with approved adhesives finished with polish.An additional strip of 5mm thk. lacquered glass of size 9"x 10'-0" shall be fixed on top as per design.The entire surface shall be polished as specified in the interior details to the satisfaction of Architect Engineer in charge, complete in all respects.finished with PU Polish.	1.00	Nos		
	Comm. Ply/ Board : (Make : Century:Sainik/Green :Ecotech/Archidply)				
	Laminate : (Make: Greenlam,Merino,Century,AICA)				
	Hardware: (Make : Godrej/Ozone/Hettich/Hafele/Harison)				
14	MDF JALI				
	Making and fixing in position (as per approved sample) Laser Cut Jaali partition to be made out of MDF board of 8mm. thickness and make. All exposed surfaces to be finish with clear gloss Verinlengo paint as per approved shade . All complete as/ design to the entire satisfaction ofArchitect/ Engineer in charge (Elevation area to measure).	6.00	Sq.mt		

[illegible]

