Name of work: INTERNAL PAINTWORK OF SCALE IV / V, FLAT AT SECTOR 42 BANK'S FLATS									
ABSTRACT OF COST									
Sl. No.		Description of items	Unit	Qty	Rate	Amount			
_		OIL BOUND DISTEMPER FOR THE INTERNAL WALLS AND CEILING							
1		Providing and applying 2 or more coats of approved Oil bound distemper not before							
		preparing the surface, scrapping the exisiting paint , repairing the existing worn out							
		plaster with new plaster / mortar as required, applying primer, filling the gaps with white							
		cement putty, scapping smooth and applying two or more coats of approved shade & as							
		per the direction of Bank's Engineer / Architect.							
		Approximate area of OBD Paintwork = 3000 sq.ft	EACH						
			FLAT	1.00					
	а	The work shall further inloude the following:							
	b	Srubbing off the existing paint with sandpaper. Preparation of surface with putty work							
		wherever required for the smooth finish.							
	С	Complete removal of the damaged paint due to dampness and providing two coats of							
	-	cement slurry mixed with waterproofing compound, in addition to the above paintwork.							
		centent starry mixed with waterprooming compound, in addition to the above paintwork.							
	7	Popair of any damaged plactor in the flat with coment mortar 1:2 (1: coment and 2: cand)							
	u	Repair of any damaged plaster in the flat with cement mortar 1:3 (1: cement and 3: sand)							
		as per the direction of the engineer-in-charge.							
-		The cost of work shall be same for all the floors till 5th floor.							
	f	The cost shall include the required ladders, shuttering, scaffolding and required hanging							
ļ		platform etc. or any other material, for the execution of the works.							
		Cleaning the complete area to remove the unwanted stains of paint as per the							
		satisfaction of the EIC.							
	а	Note:							
	b	The vendor shall visit the site and ensure the condition of the existing paintwork and							
		dampness in the areas.							
	С	The vendor may take the exact measurement of paintwork in the flat, however rate must							
		be quoted lumpsum per flat and no increase or decrease in measurement shall be							
		entertained. And, in case the measurement exceeds or decrease from the approximate							
		• • • • • • • • • • • • • • • • • • • •							
		quantity no extra cost shall be paid or deducted respectively.							
		No extra payment of any sort shall be considered for any kind of request of execution of							
		the extra work. The work shall include painting all interiors and balcony as well.							
		MAKE= PAINT: ASIAN, BERGER, NEROLAC/ WATER PROOFING: PIDILITE, FOSROC, SIKA							
2		ENAMEL PAINT FOR THE DOORS AND WINDOWS AND GRILLS							
		Providing & applying Enamel Paints to Doors, Windows, Grills, Metallic Surfaces, walls,							
		fixed almirah, kitchen cabinets/shutters etc. Removing, scrapping & cleaning the							
		existing enamel paint on doors, windows, grills, metallic surfaces, etc. by scrapping,							
		sand papering and scrubbing. Then first coat of primer to be applied. After this necessary							
		leveling shall be done with putty & second primer coat shall be applied. The enamel paint							
		of approved shade shall be applied in minimum 3 coats (finishing paint) (The grills,							
		metallic surfaces, etc. shall be finished with after scrapping, applying red oxide & finish							
		with minimum 2 coats of enamel paint in two different shade).							
		Approximate area of Enamel Paintwork on the doors = 1800 sq.ft							
		Enamel Paint on the doors, windows	EACH						
	1.0		FLAT	1.00					
		The work shall further inlcude the following:							
T	а	The cost shall include the required ladders, shuttering, scaffolding and required hangling							
		platform etc. or any other material, for the execution of the works.							
	b	Cleaning the complete area to remove the unwanted stains of paint as per the							
		satisfaction of the EIC.							
		Note:							
	а	The vendor shall visit the site and ensure the condition of the existing paintwork.							
-		Complete removal of the damaged paint due to dampness and providing two coats of							
	D								
		cement slurry mixed with waterproofing compound, in addition to the above paintwork.							
	С	No extra payment of any sort shall be considered for any kind of request of execution of							
		the extra work. The work shall include everything.							
	d	The approximate area of the Door has been calculated as the flat surface area of the door							
		including the frame.							

е	The approximate area of the Windows has been considered taking the flat portion outer		
	size of the windows. However, the painwork shall include painting of the complete		
	windows(openable and fixed), window shutters both sides, mouldings, grills, Window Jali		
	both sides and frame including for the outer enamel paint of the window frame and		
	shutter. No extra payemnt will be made for painting grills jali shutter etc. rate must be		
	quoted lumpsum per flat for complete paint of door, windws ,jali doors, ventilators , iron		
	grills etc		
	TOTAL AMOUNT		