

**FINANCIAL BID OF CIVIL WORK FOR STATE BANK OF INDIA, M.P.S.T. & H.L.S.T. BRANCH,
FIRST FLOOR, FOUNTAIN CHOWK, CIVL LINES, LUDHIANA.**

SN.	DESCRIPTION OF ITEM	QTY.	UNIT	RATE (Rs.)	AMOUNT (Rs.)
1	VITRIFIED TILES FLOORING:-				
	Providing and laying double charged Vitrified tiles 600mm x600mm (Marble series- Johnson, Kajaria, Nitco) with water absorption less than 0.08% and conforming to IS:15622, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) and 8-12 mm thick tile fixing chemical (Roff, Kajaria, Rachtr, MYK Laticrete) with 5 mm spacer & filling the joint-gaps with jointing with epoxy grout (MYK Laticrete) , as per shade mentioned in drawing. The tiles must be cut with the zero chipping diamond cutter only . Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, leveling system and rubber mallet for placing the tiles gently and easily. tile level will be same as R.A.C.P.C. flooring. (Including dismantling of existing floor tiles if any and disposing of malba from site at appropriate place)	3920	Sq.ft		
2	GRANITE :-				
	Providing and laying 18mm thick Lopatto / Flamed Finish Granite on main entrance steps with 1.5" moulding over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing, nosing and polishing etc. all complete as specified and directed by the Architect. (Including dismantling of existing kotta stone if any and disposing of malba from site at appropriate place)	1410	Sq.ft		
3	S.S. RAILING :-				
	Providing and fixing stainless steel Grade 304 railing (Jindal, Hindalco, Bharat) made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per the drawings provided by the Architect, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc. (Including dismantling of Existing Railing and disposing of malba from site at appropriate place)	140	Rn.ft		
4	PLASTIC EMNULSION PAINT:-				

	Applying three or more coats of Plastic Emulsion Paint (Asian, Nerolac, Berger) of approved shade including making of ground, rubbing, filling of putty base preparation etc. In case where the surface has been white/color washed, the old white/color wash shall be entirely removed and surface broomed/scrapped down before the newPaint is applied. Rates include cleaning of splashes, stains on floor, window panes etc and scaffolding, if required and for all heights.	7400	Sq.ft		
5	PLASTER & FINISHINGS :-				
	Repairs to plaster 1:4 (1 cement : 4 fine sand) of thickness 12 mm to 18 mm in patches of area 2.5 sq.meters including removing the old plaster wherever required and cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With cement mortar 1:4 (1 cement : 4 fine sand)	590	Sq.ft		
6	BRICK WORK :-				
	Providing & laying 4.5" Thick brick wall with brick class designated 75 in cement mortar 1:4 (1 cement: 4 coarse sand), including all types of leads/ lift, scaffolding, pads, racking joints, curing, chipping/ cutting concrete floor before starting work, complete in all respect. In case of half brick wall, MS reinforcement as per CPWD specifications to be provided, i.e. 2 nos. 6mm dia TOR steel bars will be provided at every third course, for which no extra payment will be made.	225	Cu.ft		
7	COLLAPSIBLE/KANCHI GATE :-				
	Providing & fixing in position collapsible steel shutters with vertical channels 20x10x2 mm & braced with flat iron diagonals 20x5 mm size, with top & bottom rail of T-iron 40x40x6 mm, with 40mm dia steel pulleys, complete with bolts, nuts, locking arrangement, stoppers, handles, including applying a priming coat of approved steel primer and 2 or more coats of enamel paint (Asian, Nerolac, Berger) on Collapsible m.s. kanchi gate to give even & uniform surface. (Including dismantling of existing collapsible kanchi gate and disposing of malba from site at appropriate place)	130	Sq.ft		
8	ENAMEL PAINT:-				
	Applying 2 or more coats of enamel paint (Asian, Nerolac, Berger) on m.s.windows to give even & uniform surface.	500	Sq.ft		
	TOTAL				
	G.S.T as applicable will be paid extra by the bank				
	Seal & Signature of Vendor				