

**PRICE BID FOR INTERIOR DECORATION and FURNISHING WORK OF
ATM at MITHILA MINORITY DENTAL COLLEGE & HOSPITAL AT LAHERIASARAI, DARBHANGA**

S.NO.	ITEM	PARTICULARS	QTY.	UNIT	RATE	AMOUNT
1	12 MM THICK TOUGHENED GLASS DOOR ETC	a. 12 MM THICK TOUGHENED GLASS DOOR/PARTITION ETC Providing and fixing / fitting 12 mm thick toughened glass of approved make with all necessary hardware accessories including floor spring etc including cost of labours and materials etc. b.12 MM Thick toughened glass partition with all necessary hardware etc. all complete.	7.9	SQ. MTR.		
4	Frosted Film	Providing and fixing self adhesive Sparkle series Frosted Film and/or one way vision film of 3 M make as per design : The film are to pasted on main glass door & other glasses as directed, cut & fixed as per design including the Bank's logo. Executed area of the film pasted on glasses shall be meas-ured for finished work.	8.5	SQ. MTR.		
5	ACP Panelling and Partitions AND COVER FOR ROLLING SHUTTER	Providing and fixing ACP for panelling and partitions and cover for rolling shutter box: Supplying and fixing aluminium composite cladding with skin material 0.5mm thick aluminium sheet cover material natural polyethylene aluminium cladding panel fixed with extruded aluminium basis frame, angle cleats, weather sealants, rivets, GI brackets all as approved, using suitable fixtures & grooves duly treated with silicon sealant including necessary ccessories complete in all respects including all labour, scaffolding charges etc., complete for finished item of work. ACP Cladding - 4 mm thick. The work is to include all necessary materials, accessories, labour, tools & tackles. Executed covered area shall be measured for finished work	26.85	SQ. MTR.		
12	FALSE CEILING (GYPSUM TILE GRID)	Providing and fixing of Gypsum tile false ceiling tile of size 600mm x 600mm x 12mm with square / tegular edge at all heights laid on Prelude XL Hot dipped galvanized exposed grid with 15 m with T-Section exposed flingers which shall be powder coated white. The framework will comprise of main Runner made from 0.33 mm thick GS sheet and of size 24 mm x 38mm x 3600 mm and spaced at 1200 mm centre securely fixed to the structural soffit by approved hangers at 1200 mm maximum centre. Hangers (GI wire of 4.0 mm diameter) to be fixed by approved Rawl plug, level adjusters and screws etc. All complete work as per drawing, design. Specification and direction of Engineer-in-charge /Bank. The last hanger at the end of each main Runner should not be greater than 450 mm from the adjacent wall. Flush fitting of 1200 mm long cross tee (with double stitching) to be inter-locked between main Runners at 600 mm centre to form 1200 mm x 600 mm modules. Cut cross Tees longer than 600 mm to be supported independent-ly. 600 mm x 600 mm modules top be formed by fitting 600 mm x 600 mm modules to be formed by fitting 600 mm long cross Tee centrally between the 12 mm cross Tee. Perimeter wall Angle shall be of 0.45 thick GS Steel and of size 22 mm and 3000 mm long of white color. The work shall be as per standards and specifications laid down by the manufacturers. Full provision of weight of a/c ducting (if provided) and light fittings, wiring for any use, including co-coordinating with all trades and making any cutouts required for the same, all complete with a minimum of 2 coats of premium quality Acrylic emulsion paint and full finishing for light fittings all complete work as per drawing, design., specification and direction of EIC/BANK	10	SQ. MTR.		
TOTAL in INR						

NOTE:-

- * ABOVE PRICE IS EXCLUDING GST BUT INCLUDING TRANSPORTATION AND OTHER CHARGES
- * GST PAID EXTRA BY THE BANK AS PER RULE.

(SIGNATURE)
AUTHORIZED SIGNATORY