

PRICE BID FOR INTERIOR FURNISHING WORK OF STATE BANK OF INDIA BRANCH AT MAIN BRANCH BARNALA					
S.No.	Item	Qty	Units	Rate	Amount
	<b>PANELING/PARTITON</b>				
	<b>Note: For the Paneling, Full height partitions and low height partitions the work measurement for costing shall be only of the plain visible surface, no extra cost for extrusions or extra frame work required as per drawing will be made. The work done above ceiling, below floor finish level or not directly visible shall not be measured.</b>				
<b>1</b>	<b>WALL PANELING ( 1.0mm Th. Laminate) upto 9'-0" high</b>				
	Providing and fixing paneling over the existing wall made out of framework of 50 mm X 25 mm - 18gauge section un anodised Aluminium ( as per requirement) frame work @ 16" to 24" c/c vertically & horizontally. The frame work to be clad with 8.0 mm thick commercial ply finished in 1 mm Th. laminate of approved shade, design and gloss.and following finishigs as per drawing and instructions. All exposed surfaces to be clad with teakwood moulding of size 30 mm X 12.0 mm made to shape. The work should be complete in all respects including provisions of grooves duly designed & finished. All wood to be treated with wood preservatives of approved ISI quality. All exposed teak wood shall be spirit polished with matching pigment. The rate shall include for providing groves in laminate & wood. Payments shall be made only for exposed surfaces & actual measurement at site, no payment shell be made for paneling behind furniture such as tables, Credenza , storage etc.	153.16	SQ.M		
	<b>Makes :-</b>				
	<b>Commercial ply: Green ply ( Eco- Tech ) / Duro / Century/Amulya</b>				
	<b>Laminate : Merino / Century / Greenlam New Mica / Amulya</b>				
<b>1(b)</b>	<b>WALL PANELING ( 4 mm Th. Veneer )</b>				
	Providing and fixing paneling over the existing wall made out of framework of 50 mm X 25 mm - 18gauge section un anodised Aluminium ( as per requirement) frame work @ 16" to 24" c/c vertically & horizontally. The frame work to be clad with 8.0 mm thick commercial ply finished in 4 mm Th. teak veneer of approved shade, design and gloss.and following finishigs as per drawing and instructions. All exposed surfaces to be clad with teakwood moulding of size 30 mm X 12.0 mm made to shape. The work should be complete in all respects including provisions of grooves duly designed & finished. All wood to be treated with wood preservatives of approved ISI quality. All exposed teak wood shall be spirit polished with matching pigment. The rate shall include for providing groves in laminate & wood. Payments shall be made only for exposed surfaces & actual measurement at site, no payment shell be made for paneling behind furniture such as tables, Credenza , storage etc.(Basic Cost of Veneer @ 100 Rs./sqft)	-	SQ.M		
<b>2</b>	<b>FULL HEIGHT PARTITIONS UPTO 9'-0" HIGH</b>				
	Providing and fixing wooden full height partition with following specifications:	87.83	SQ.M		

THAPAR AND ASSOCIATES  
C.A. No. 2014/2015  
Mobile: +91-951660375

	(a) Supporting system comprising of Dry wall Frame Work Boral/Rondo/Gyp. of 44mm x 44mm (16 Gauge) square section@ max. 600mm c/c both horizontally and vertically. The frame shall be fixed rigidly at floor level and ceiling level wherever possible. The rate should also include necessary strengthening with additional members at doors and other openings.				
	(b) The partition shall have 9mm Plywood fixed on both sides with screws for the entire height of the partition and finished with approved 1.0mm Th. Laminate of desired shade and design on both sides. Wooden molding, lipping etc. as directed by Bank / architect shall be provided wherever required. The partition shall have skirting and intermediate bands finished with metallic laminate of desired shade and design.				
	(c) The full height partition shall be WITH OR WITHOUT 8mm clear float glass with etching fixed as per drawing with 75mm x 12mm Teak wood jamb/chaowkhat around glass opening and 12mm x 12mm teak wood beading for fixing of glass on both sides. As per the direction of Engineer-in-charge and design.				
	(d) The work to include providing and fixing of partly glazed wooden door shutters using 35mm readymade ISI flush door shutter with 1.0mm thick laminate of desired shade and design as per drawing with teak wood frame of 75mm x 40mm. The door shall have 6mm thick teak wood lipping all around the edges. The door shall have vision panels with 8mm thick clear float glass with etching fixed with double 14mmx25mm thick teak wood moulding as per design. The exposed surface of wood shall be deco painted in desired shade. The door shall be complete in all respect with hardware handles, godrej 6-lever lock/night latch lock, door stoppers, 8" tower bolts, hinges, Door closer etc all in brass. (Hettich /Godrej/Dorma/Ozone)				
	<b>Makes :-</b>				
	<b>Commercial ply: Green ply ( Eco- Tech ) / Duro / Century/Amulya</b>				
	<b>Laminate : Merino / Century / Greenlam New Mica / Amulya</b>				
<b>b</b>	<b>FULL HEIGHT PARTITIONS UPTO 9'-0" HIGH (One side laminate &amp; one side veneer)</b>	<b>29.30</b>	<b>SQ.M</b>		
	Providing and fixing wooden full height partition with following specifications:				
	(a) Supporting system comprising of Dry wall Frame Work Boral/Rondo/Gyp. of 44mm x 44mm (16 Gauge) square section@ max. 600mm c/c both horizontally and vertically. The frame shall be fixed rigidly at floor level and ceiling level wherever possible. The rate should also include necessary strengthening with additional members at doors and other openings.				
	(b) The partition shall have 9mm Plywood fixed on both sides with screws for the entire height of the partition and inner side finished with approved 4 mm Thk. veneer of desired shade and design & outer side should be finished with approved 1.0mm Th. Laminate of desired shade and design. Wooden molding, lipping etc. as directed by Bank / architect shall be provided wherever required. The partition shall have skirting and intermediate bands finished with metallic laminate of desired shade and design.				
	(c) The full height partition shall be WITH OR WITHOUT 8mm clear float glass with etching fixed as per drawing with 75mm x 12mm Teak wood jamb/chaowkhat around glass opening and 12mm x 12mm teak wood beading for fixing of glass on both sides. As per the direction of Engineer-in-charge and design.				

	(d) The work to include providing and fixing of partly glazed wooden door shutters using 35mm readymade ISI flush door shutter with approved 4 mm Thk. veneer of desired shade and design & outer side should be finished with approved 1.0mm Th. Laminate of desired shade and design as per drawing with teak wood frame of 75mm x 40mm. The door shall have 6mm thick teak wood lipping all around the edges. The door shall have vision panels with 8mm thick clear float glass with etching fixed with double 14mmx25mm thick teak wood moulding as per design. The exposed surface of wood shall be deco painted in desired shade. The door shall be complete in all respect with hardware handles, godrej 6-lever lock/night latch lock, door stoppers, 8" tower bolts, hinges, Door closer etc all in brass.				
	<b>Makes :-</b>				
	<b>Commercial ply: Green ply ( Eco- Tech ) / Duro / Century/Amulya</b>				
	<b>Laminate : Merino / Century / Greenlam New Mica / Amulya</b>				
<b>3</b>	<b>LOW HEIGHT PARTITIONS:UPTO 4'-6"HT.</b>				
	Providing and fixing wooden low height partition with following specifications:	<b>40.35</b>	<b>SQ.M</b>		
	(a) Supporting system comprising of Dry wall Frame Work Boral/Rondo/Gyp. of 44mm x 44mm (16 Gauge) square section @ max. 600mm c/c both horizontally and vertically. The frame shall be fixed rigidly at floor level and ceiling level wherever possible. The rate should also include necessary strengthening with additional members at doors and other openings.				
	(b) The partition shall have 9mm Plywood fixed on both sides with screws for the entire height of the partition and finished with approved 1.0mm Th. Laminate of desired shade and design on both sides. Wooden molding, lipping etc. as directed by Bank / architect shall be provided wherever required. The partition shall have skirting and intermediate bands finished with metallic laminate of desired shade and design.				
	(c) The low height partition shall have 12 mm thick glass with etching as per design fixed with stainless steel wall cladding profile (WCP) of make at bottom and sides with top surface and other side free. All the edges of the 12mm glass shall be duly grinded/bevelled and polished.				
	<b>Makes :-</b>				
	<b>Commercial ply: Green ply ( Eco- Tech ) / Duro / Century/Amulya</b>				
	<b>Laminate : Merino / Century / Greenlam New Mica / Amulya</b>				
<b>4</b>	<b>12MM THICK TOUGHENED GLASS FIXED PARTITIONS</b>				
	Providing and fixing in position 12mm clear float toughened Glass partition with patch fittings for the full height glass partitions as per the direction of the engineer-in-charge. The work to include making necessary template for all the glasses and then cutting the clear float glass to correct size, making all the necessary holes, cuts etc., then toughen the same. (Saint Gobain/Asahi/Modiguard).	<b>24.65</b>	<b>SQ.M</b>		
	The cost to include all hardware (PATCH FITTINGS etc) required of approved make single corner patch, top and bottom corner patch etc. or as per the direction of the engineer-in-charge. The maximum size of each glass shall be 1200mm to 2000mm x 2400mm to 2700mm as per the site requirement. The rate is for a finished item of work etc., complete as directed. Glass partition will be fixed at bottom and top with patch fittings(as required). SS U-channel of 12mm X 25mm to be grouted with the floor.				

	The cost to include the cost of bevelling and smoothening of the exposed edges of the glass.				
	<b>Makes :-</b>				
	<b>PATCH FITTINGS :- Hettich/ Haffele / Godrej</b>				
	<b>GLASS :- Saint Gobain / TATA / Asahi / Modiguard</b>				
<b>5 (a)</b>	<b>12MM THICK TOUGHENED GLASS DOORS WITH ETCHING:</b>				
	Providing and fixing in position 12mm clear float toughened Glass for naked glass door. The work to include making necessary template for all the glasses and then cutting the clear float glass to correct size, making all the necessary holes, cuts etc., and then toughening the same. The cost to include all hardware required of approved make floor spring with its accessories, top pivot, center lock, 450mm glass door handles etc., along with etching with sand blasting as per design and drawing. The maximum size of each glass shall be as per the drawing or the direction of the Engineer-in-charge. The rate is for a finished item of work etc., complete as directed.	6.51	SQ.M		
	<b>Makes :-</b>				
	<b>PATCH FITTINGS :- Hettich/ Haffele / Godrej</b>				
	<b>GLASS :- Saint Gobain / TATA / Asahi / Modiguard</b>				
<b>6</b>	<b>12mm thick Toughen glass for transaction partition</b>	6.06	SQ.M		
	<b>Makes :-</b>				
	<b>PATCH FITTINGS :- Hettich/ Haffele / Godrej</b>				
	<b>GLASS :- Saint Gobain / TATA / Asahi / Modiguard</b>				
<b>7</b>	<b>12MM TOUGHENED GLASS FOR FRONT :</b>	4.65	SQ.M		
	Providing and fixing 12 mm thick, clear plain toughened glass of approved pattern fixed in vertical position at counter front and as curved glass extension of low height partition as per drawing, fixed on wooden partitions with superior quality stainless steel patch fittings of An opening as per the drawing at the bottom for transaction shall be provided in case of glass in from of the transaction counter. All the edges of the glass shall be grinded/bevelled and polished. The glass shall also be etched as per the design. Glass area with maximum height shall be measured for the purpose of payment. The work shall be carried out as per drawings.				
	<b>Makes :-</b>				
	<b>PATCH FITTINGS :- Hettich/ Haffele / Godrej</b>				
	<b>GLASS :- Saint Gobain / TATA / Asahi / Modiguard</b>				
<b>8</b>	<b>BRANCH MANAGER TABLE WITH SIDE CREDENZA</b>				
	(a) Providing and fixing at site Officer's table made of 18mm thk. commercial ply board with 10 mm plain glass on top with 4mm thick veneer with polish of desired shade, design and gloss on outer visible surfaces; single color on horizontal surface & two color on vertical surfaces. . The front of the table top shall be projected and curved as per drawing. Provision for 3" dia. Round/3" square stainless steel of grade 304 cable manager for computer / electrical cables at appropriate place, will be made in the top surface of the table. Esteem Biege wood lipping will be provided on all the edges of the table, including bottom touching the floor and the drawers.				

	The counter shall have a wooden keyboard rest of size 600mm x 270mm made with 18mm ply fixed with sliding telescopic channels. The work shall also include provision of foot rest made with wooden member of section 3" x 5" along the leg space.				
	(b) There shall be provision of one storage cabinet 1'3" wide. The frame shall be made with <b>18mm thk. commercial ply board</b> The cabinet shall have three lockable drawer running on side mounting drawer slides (channels) & one cupboard with shutter beneath the drawer, made of 18mm thick commercial block board with 4 mm thick veneer with polish of desired shade, design and gloss on front face, handle / knob and magnetic catcher shall be provided on one side of the table as per layout. The sides of the drawer shall be made of 12mm thick plywood, bottom of 6mm thick plywood & front of 18mm thick block board.				
	c) Side credenza made of 19mm thick commercial ply frame and 6mm thick plywood on back side & 4 mm thick veneer on top horizontal surface & one vertical visible side only, polish of desired shade, design and gloss on front face. The credenza will have drawer compartment 16" wide outer to outer, containing three drawers vertically running on side mounting drawer slides(channels). The sides of the drawer shall be made of 12mm thick plywood, bottom of 6mm thick plywood & front of 19mm thick block board. The remaining part of the credenza will have cupboard with Overlapped shutters and one shelf. All the internal surfaces shall be finished with 0.8mm thick mica of desired shade and design and the exposed wood shall be polished in desired shade.				
	All other surfaces i.e. inside / leg space of table, inside of drawer / cupboard shall be provided with 0.8mm thick laminate of desired shade/design and gloss, and wood lipping / beading shall be PU polished with matching pigment/deco painted in desired colour. The table shall have a CPU ledge made of 18mm thick block board on one side, complete as per drawing.				
	<b>Makes :-</b>				
	<b>Commercial ply: Green ply ( Eco- Tech ) / Duro / Century/Amulya</b>				
	<b>Laminate : Merino / Century / Greenlam New Mica / Amulya</b>				
	<b>Telescopic Channels : Hettich/ Hafele / Godrej</b>				
	<b>Drawer locks : Hettich/ Hafele / Godrej</b>				
	<b>Auto lock : Hettich/ Hafele / Godrej</b>				
	<b>BM table (6'-0" x 3'-0" x 2'-6") Side Rack (3'-6" X 1'-6" X 2'-6")</b>	<b>1.00</b>	<b>NOS</b>		
<b>9</b>	<b>OFFICER'S TABLES WITHOUT SIDE CREDENZA</b>				
	(a) Providing and fixing at site Officer's table ( 10 mm thk. glass on table top with foam ) made of 19mm th. commercial block Ply with 1mm thick Laminate of desired shade and design on outer visible surfaces; single color on horizontal surface & two color on vertical surfaces. . The front of the table top shall be projected and curved as per drawing. Provision for 3" dia. Round/3" square stainless steel of grade 304 cable manager for computer / electrical cables at appropriate place, will be made in the top surface of the table. Esteem Biege wood lipping will be provided on all the edges of the table, including bottom touching the floor and the drawers.				
	The counter shall have a wooden keyboard rest of size 600mm x 270mm made with 19mm ply fixed with sliding telescopic channels. The work shall also include provision of foot rest made with wooden member of section 3" x 5" along the leg space.				

	(b) There shall be provision of one storage cabinet 1'3" wide. The frame shall be made with 19mm thick commercial board. The cabinet shall have three lockable drawer running on side mounting drawer slides (channels) & one cupboard with shutter beneath the drawer, made of 19mm thick commercial block board with 1mm thick laminate of desired shade and design on front face, handle / knob and magnetic catcher shall be provided on one side of the table as per layout. The sides of the drawer shall be made of 12mm thick plywood, bottom of 6mm thick plywood & front of 19mm thick block board.				
	All other surfaces i.e. inside / leg space of table, inside of drawer / cupboard shall be provided with 0.8mm thick laminate of desired shade and design, and wood lipping / beading shall be PU polished with matching pigment/deco painted in desired colour. The table shall have a CPU ledge made of 19mm thick block board on one side, complete as per drawing.				
	<b>Makes :-</b>				
	<b>Commercial ply: Green ply ( Eco- Tech ) / Duro / Century/Amulya</b>				
	<b>Laminate : Merino / Century / Greenlam New Mica / Amulya</b>				
	<b>Telescopic Channels : Hettich/ Haffele / Godrej</b>				
	<b>Drawer locks : Hettich/ Haffele / Godrej</b>				
	<b>Auto lock : Hettich/ Haffele / Godrej</b>				
<b>a</b>	<b>Officer Table (1.52 X .0.76 X 0.76)</b>	<b>9.00</b>	<b>no.</b>		
<b>10</b>	<b>GRAHAK MITRA/CRO COUNTER:</b>				
	(a) Providing and fixing at site counters ( 10 mm thk. glass on table top with foam )as per the design and drawings. Table to be made of 19mm thick commercial block board with 1mm thick laminate of desired shade and design on outer visible surfaces; single color on horizontal surface & two colors on vertical surfaces. Provision for 3" dia. Round /3" square stainless steel of grade 304 cable manager for computer / electrical cables at appropriate place, will be made in the top surface of the counter. Teak wood lipping will be provided on all the remaining edges of the counter, including bottom touching the floor and the drawers. The counter shall have wooden keyboard rest of size 600mmx 270mm fixed on sliding telescopic channels. The work shall also include provision of foot rest made with wooden member of section 3" x 5" along the leg space. The table to have writing top of toughened glass at 1200mm level as per drawing.	<b>1.00</b>	<b>NOS</b>		
	(b) The counters shall have three self lockable drawers running on side mounting drawer slides (channels) made of 19mm thick commercial block board with 1mm thick laminate of desired shade and design on front face & 3 nos. self locking drawer locks be provided on one side of the counter as per layout. The sides of the drawers shall be made of 12mm thick plywood, bottom of 6mm thick plywood & front of 19mm thick block board. All other surfaces i.e. inside / legsapce of table, inside of drawer/Cupboard shall be provided with 0.8mm thick laminate of desired shade and design, and wood lipping / beading shall be PU polished with matching pigment/deco painted in desired colour. The drawers shall have partitions for keeping currency notes as per drawing, complete in all respects including the required stainless steel hardware like handles, hinges etc. The counter shall have a CPU ledge made of 19mm thick commercial block board on one side, complete as per drawing.				
	<b>Makes :-</b>				
	<b>Commercial ply: Green ply ( Eco- Tech ) / Duro / Century/Amulya</b>				

**THAPAR AND ASSOCIATES**  
 C.A. No. 1014/2023  
 Mobile: +91 9514660375

	Laminate : Merino / Century / Greenlam New Mica / Amulya				
	Telescopic Channels : Hettich/ Haffele / Godrej				
	Drawer locks : Hettich/ Haffele / Godrej				
	Auto lock : Hettich/ Haffele / Godrej				
	Note: The contractor to get the sample of the counter approved from the Architect/ENGINEER before covering it with laminate without any extra cost.				
11	<b>SWO COUNTERS: (AS PER NEW DESIGN AND SPECIFICATIONS) (4'-6" to 5'-0"X3'-0"X2'-6")</b>				
	(a) Providing and fixing at site SWO counters ( 10 mm thk. glass on table top with foam )as per the new design and drawings. SWO counters to be made of 19mm thick commercial block board with 1mm thick laminate of desired shade and design on outer visible surfaces; single color on horizontal surface & two colors on vertical surfaces. The counter shall have a curved front made with flexible 19mm ply and provision of kobe lighting as per the drawings. . The top with Curvilinear profile shall be made out of 19mm thk. commer block board and finished with 6mm thk. flexi ply as base for acrylic sheet or approved laminate as/design with provision for LED Light in bottom . Provision for 3" dia. Round /3" square stainless steel of grade 304 cable manager for computer / electrical cables at appropriate place, will be made in the top surface of the counter. Teak wood lipping will be provided on all the remaining edges of the counter, including bottom touching the floor and the drawers.The counter shall have wooden keyboard rest of size 600mmx 270mm fixed on sliding telescopic channels. The work shall also include provision of foot rest made with wooden member of section 3" x 5" along the leg space.	6.00	Nos		
	(b) The counters shall have three self lockable drawers running on side mounting drawer slides (channels) made of 19mm thick commercial ply with 1mm thick laminate of desired shade and design on front face & 3 nos. self locking drawer locks be provided on one side of the counter as per layout. The sides of the drawers shall be made of 12mm thick plywood, bottom of 6mm thick plywood & front of 19mm thick block ply. All other surfaces i.e. inside / legsapce of table, inside of drawer/Cupboard shall be provided with 0.8mm thick laminate of desired shade and design, and wood lipping / beading shall be PU polished with matching pigment/deco painted in desired colour. The drawers shall have partitions for keeping currency notes as per drawing, complete in all respects including the required stainless steel hardware like handles, hinges etc.The counter shall have a CPU ledge made of 19mm thick commercial block board on one side, complete as per drawing.				
	Makes :-				
	Commercial ply: Green ply ( Eco- Tech ) / Duro / Century/Amulya				
	Laminate : Merino / Century / Greenlam New Mica / Amulya				
	Telescopic Channels : Hettich/ Haffele / Godrej				
	Drawer locks : Hettich/ Haffele / Godrej				
	Auto lock : Hettich/ Haffele / Godrej				
	Note: The contractor to get the sample of the counter approved from the Architect before covering it with laminate without any extra cost.				
a)	White acrylic stone ( SWO counter top and front )				

	Providing and fixing (12mm thick) white acrylic stone (nonabsorbent, non-porous solid surface composite material, belonging to the solid surface category) as per drawings/design.providing by the Architects complete in all respect including buffing and wastage.	11.15	SQ.M		
	Makes :-				
	Corian : Merino /Dupont/LG				
12	<b>SIDE CREDENZA 0.91 to1.40X 0.46 X 0.76</b>				
	Side credenza made of 19mm thick commercial ply frame and 6mm thick plywood on back side & 1mm thick laminate on top horizontal surface & one vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The credenza will have drawer compartment 16" wide outer to outer, containing three drawers vertically running on side mounting drawer slides(channels). The sides of the drawer shall be made of 12mm thick plywood, bottom of 6mm thick plywood & front of 19mm thick block board. The remaining part of the credenza will have cupboard with Overlapped shutters and one shelf. All the internal surfaces shall be finished with 0.8mm thick mica of desired shade and design and the exposed wood shall be deco painted/malamine polished in desired shade.	10.00	No.		
	Makes :-				
	Commercial ply: Green ply ( Eco- Tech ) / Duro / Century/Amulya				
	Laminate : Merino / Century / Greenlam New Mica / Amulya				
	Telescopic Channels : Hettich/ Hafele / Godrej				
	Drawer locks : Hettich/ Hafele / Godrej				
	Auto lock : Hettich/ Hafele / Godrej				
13	<b>LOW HEIGHT STORAGE CABINETS/BACK STORAGE: (0.76 HIGH)</b>				
	(a) Providing and fixing storage cabinets of size 2'6" (High) x 16" (Deep) along the walls/partitions, as per interior drawings, using 19mm board for carcass, shutters, vertical and horizontal partitions, 6mm ply for the back and 1mm laminate of approved shade on vertical and horizontal visible surfaces. The shutters shall be overlapped on the carcass and shall be provided. The width of the shutter shall be between 12" to 15" as per the site conditions. All the exposed edges of the board shall be provided with wooden lipping 19mm x 3mm, duly PU polished/deco painted in desired shade. The inner surface shall be provided with 0.8mm thick laminate of desired shade and design. The cabinet shall be complete with handles, knobs, locks and magnet catchers etc. to the satisfaction of the Architect/Engineer.	72.41	SQM		
	Makes :-				
	Commercial ply: Green ply ( Eco- Tech ) / Duro / Century/Amulya				
	Laminate : Merino / Century / Greenlam New Mica / Amulya				
	Telescopic Channels : Hettich/ Hafele / Godrej				
	Drawer locks : Hettich/ Hafele / Godrej				
	Auto lock : Hettich/ Hafele / Godrej				
13	<b>GYPSUM BOARD FALSE CEILING WITH STEPS:</b>				

	Providing and fixing suspended false ceiling including steps and provision of cope lighting as per design with 12.5mm tapered edge Gypboard / 12mm thick Elephant Gypsum Board to the grid comprising of cold rolled galvanized metal section to the required line and level. The grid consisting of a perimeter channel fixed round the perimeter. The intermediate channel at 1200mm c/c in the one direction and the ceiling section at 450mm c/c in the other direction to be connected by a connecting clip. The grid to be suspended with an adjustable strap hanger.	191.73	SQ.M		
	The grid to be suspended with an adjustable strap hanger at 1200mm c/c on both ways from the structural soffit using a soffit cleat and expandable bolts/fasteners Nut and bolts to be used to connect strap hangers to soffit cleats and for joining ends of channel sections together. The gypsum board layers to be screwed to the M/F ceiling sections with Gypboard drywall screws. Jointing and screw spotting are then carried out as per manufacturer's standard recommendations. Perimeter Channels to be used around the cut outs for light fittings. A/C ducting etc. The work should be complete as per instructions of Architect or Engineer in charge including 2-3 coats of oil bound distemper , over a coat of primer.				
	<b>Makes :-</b>				
	<b>Gypsum Board :- Saint Gobain / Gypcore/ USG Knauff</b>				
	<b>Ceiling Channel, Angle Screws Etc. :- Gyproc / USG Knauff</b>				
<b>14</b>	<b>GRID FALSE CEILING:</b>				
	Silhouette Grid False Ceiling:- Providing and fixing in true horizontal level false ceiling grid system of Armstrong World Industries. The suspension system shall be the incorporating a 3mm or 6mm central recess color, black or white revealed. Silhouette main runners and cross tees to have mitered ends with "birds mouth " notches to provide mitered cruciform junctions. ).	105.20	SQ.M		
	main runner of size 15 x 42 x 3000 mm spaced at 600 mm centers securely fixed to the structural soffit by approved hangers at 1200 min maximum centers hangers (BUTTERFLY CUP) to be fixed by approved roof plug, level adjusters, screws etc the last hanger at the end of each main runner should not be greater than 450mm from the adjacent wall, 600mm x 600mm modules to be formed by fitting 600mm long flush fitting cross tees of size 15 x 42 x 600mm centrally between the main runners Perimeter wall angle of size 19 x 19 x 3000mm secured to walls at 450mm maximum centers finally dune supreme ml edge rh – 99% 15 mm thick (nrc-0.50,light reffectance > 85%. Can- 34 db, k value = 0.052 to 0.057 w/m k) micro look edge has to be laid on the 600 mm x 600 mm module (the same ceiling shall be fixed by using full size files only & shall be fixed to the gypsum false ceiling.				
	<b>Makes :-</b>				
	<b>Grid Tile :- Armstrong / Knauff</b>				
	<b>Ceiling Channel, Angle Screws Etc. :- Gyproc / USG Knauff</b>				
<b>15</b>	<b>WOODEN CEILING (TEAK PLY)</b>				
	Providing and fixing 4mm thk.teak ply in ceiling over 12 mm thk. commercial ply screwed to GI ceiling sections also incorporating 2" x 2" soft battens sections in framings grids as per drawings (framework to have coating of fire retardant and anti-termite paint) necessary M.S. hangers, screws, clips, PU polishing and polyurethane coating etc.The payment area will be the visible area only The work should be complete as per instructions of Architect or Engineer in charge.	58.46	SQ.M		
	<b>Makes :-</b>				

	<b>Commercial ply: Green ply ( Eco- Tech ) / Duro / Century/Amulya</b>				
	<b>Teak ply : CP Teak</b>				
	<b>Ceiling Channel, Angle Screws Etc. :- Gyproc / USG Knauff</b>				
<b>16</b>	<b>ACP SHEETS AT ENTRANCE</b>				
	Providing and fixing Aluminium Composite Panel wall cladding with the 4mm thick PVDF coated aluminium composite panel (ACP) (0.25 mm coil thick) with frame of aluminium channels (25 x 50 x 1.6mm), cleat angle (8 x 18 x 2mm) necessary hardware, backup material and weather sealant to make the joints leak proof. The spacing for the channel along the length and spacing of cleat on the perpendicular shall not be more than 600mm. The rate includes all required shuttering , scaffolding,labor,material.	<b>39.82</b>	<b>SQ.M</b>		
	<b>Makes :-</b>				
	<b>ACP :- Aluco bond, ALU Décor,Alstrong, Alstone</b>				
<b>17</b>	<b>WOODEN BOXING FOR ELECTRICAL PANEL 7'-6" X 9'-0"X 2'-0"</b>				
	Providing & fixing of Electrical panel cabinete, made of 8mm thick bison panel both side for shutter. External side shall be finished with 1mm thick laminate & internal side shall be finished with backlyte sheet . All accessories like ball catches, ss handle, Fixing MS powder cotted perforated jali shall be provided in shutter top & bottom etc. All internal frames 50mm x 25mm x 1.6mm thick section at maximum 2'-0" c/c. Complete as directed depth of cup board 1'-6". Measurement shall be based on area of front elevation of cupboard. The rate to include all materials, labour, transport, taxes, etc complete as directed. As per approved hardware list.	<b>6.48</b>	<b>SQ.M</b>		
	<b>Makes :-</b>				
	<b>Commercial ply: Green ply ( Eco- Tech ) / Duro / Century/Amulya</b>				
	<b>Laminate : Merino / Century / Greenlam New Mica / Amulya</b>				
<b>18</b>	<b>LOW HT. STORAGE CABINET FOR GENERAL STORAGE-</b>				
	Providing and Fixing of pantry storage cabinet depth 600mm with shutters made in 19 mm thick com. block board and 6mm thick com ply for back side to be fixed on the wall, with 19mm thick com. block board shelves inside placed horizontally with self closing bright finished CP hinges,inside 0.8 mm thk laminate finish and shutters finished with 1 mm thick laminate of approved color and shade .The item includes providing 150mm SS finished handles on front for shutters,including necessary hardware etc. all complete as per drawing and to the instruction of Engineer in charge .	<b>2.67</b>	<b>SQ.M</b>		
	<b>Makes :-</b>				
	<b>Commercial ply: Green ply ( Eco- Tech ) / Duro / Century/Amulya</b>				
	<b>Laminate : Merino / Century / Greenlam New Mica / Amulya</b>				
	<b>Telescopic Channels : Hettich/ Hafele / Godrej</b>				
	<b>Drawer locks : Hettich/ Hafele / Godrej</b>				
	<b>Auto lock : Hettich/ Hafele / Godrej</b>				
<b>19</b>	<b>OVER HEAD STORAGE CABINET FOR PANTRY</b>				

	Providing and Fixing of <b>Pantry over head storage</b> cabinet depth 400mm, height 600mm with shutters made in 19 mm thick commercial block board and 6mm thick com ply for back side to be fixed on the wall, with 19mm thick commercial block board shelves inside placed horizontally and vertically with piano hinges. All inside surfaces to be 0.8 mm thk laminate and outer faces of shutters and sides (excluding outer top and bottom faces which are to be enamel painted) to be finished with 1 mm thick laminate of approved color and shade. The item includes providing 150mm brass handles on front for shutters,magnetic catchers, including necessary hardware etc. all complete as per drawing and as per instruction of Engineer in charge.	2.23	SQ.M		
	<b>Makes :-</b>				
	<b>Commercial ply: Green ply ( Eco- Tech ) / Duro / Century/Amulya</b>				
	<b>Laminate : Merino / Century / Greenlam New Mica / Amulya</b>				
	<b>Telescopic Channels : Hettich/ Hafele / Godrej</b>				
	<b>Drawer locks : Hettich/ Hafele / Godrej</b>				
	<b>Auto lock : Hettich/ Hafele / Godrej</b>				
20	<b>RECTANGULAR WRITING DESK WITH STORAGE FOR CHECK DROP BOX &amp; COMPLAINT BOX AS PER DRGS.</b>				
	Providing & fixing of Rectangular writing desk with provision of complaint and suggestion box , made of 18mm thick commercial plywood finished with 1 mm thick laminate on all sides including inside divisions. 12mm thick toughen glass Shelf shall be fixed of desk with bevelled and polished edges making different divisions by 12mm thick toughen glass for slips or forms as per detail drawing directed complete. The rate to include all materials, labour, transport, taxes, etc complete as directed. (Size: 4'-0" X 1'-0" X 3'-6"ht.)	1.00	NO.		
	<b>Makes :-</b>				
	<b>Commercial ply: Green ply ( Eco- Tech ) / Duro / Century/Amulya</b>				
	<b>Laminate : Merino / Century / Greenlam New Mica / Amulya</b>				
	<b>Telescopic Channels : Hettich/ Hafele / Godrej</b>				
	<b>Drawer locks : Hettich/ Hafele / Godrej</b>				
	<b>Auto lock : Hettich/ Hafele / Godrej</b>				
21	<b>Semi glazed wooden doors with frame :- WIDTH (2'-6" TO 3'-6")</b>				
	Providing & fixing of 35mm thick semi glazed flush type doors. Doors shall be finished with 1mm thick laminate of approved colour & make with 35 x 5mm steam beach wood beading on edges of door. The glass shall be 8mm thick clear float glass with edge polishing & round smoothenend exposed edges All accessories like the door stopper, heavy duty brass hinges, latch, handle, lock etc shall be part of the job. All teak wood members to have melamine spray polish finish. Rate to include cost of conveyance of all materials, labour charges etc. complete as directed. As per approved hardware list.	1.00	NO.		
22	<b>FIRE PROOF DOOR FRAME (3'-0" X 7'-0")</b>				

	Providing and fixing fire resistant door frame of section 143 x 57 mm having built in rebate made out of 16 SWG G.I. Sheet (zinc coating not less than 120 gm/sqm) duly filled with vermiculite based concrete mix, suitable for mounting 60 minutes fire rated door shutters. The frame is fitted with intumescent fire seal strip of size 10x4 mm (minimum) around the frame and fixing with dash fastener of approved size and make, including applying a coat of approved brand fire resistant primer etc. complete as per direction of Engineer-in-charge (including Dash fastener).	1.00	Nos		
<b>b</b>	<b>FIRE PROOF SHUTTER</b>				
	Providing and fixing 50 mm thick glazed fire resistant door shutters conforming to IS:3614 (Part-II), tested and certified as per laboratory approved by Engineer-in-charge, with suitable mounting on door frame, consisting of vertical styles, lock rail, top rail 100 mm wide, bottom rail 200 mm wide, made out of 16 SWG G.I. sheet (zinc coating not less than 120 gm/ m2) duly filled FR insulation material and fixing with necessary stainless steel ball bearing hinges of approved make, including applying a coat of approved fire resistant primer etc. all complete as per direction of Engineer-in-charge (paneling to be paid for separately)				
<b>c</b>	<b>FIRE PROOF GLASS PANEL</b>				
	Providing and fixing glazing in fire resistant door shutters, fixed panels, ventilators and partitions etc., with G.I. beading of appropriate size, made out of 20 SWG G.I. Sheet (zinc coating not less than 120 gm/ m2), fire resistant sealant, including applying a coat of approved fire resistant primer on G.I. beading etc., complete all as per direction of Engineer-in-charge.				
	With clear fire resistant glass panes 6 mm thick of approved brand, having minimum 60 minutes fire resistance				
	<b>Makes :-</b>				
	<b>Fire Door :- SBG/GMP/Kutty's Doors</b>				
<b>22</b>	<b>TROPHY CASE VENEER 9'-0" HIGH FOR BRANCH MANAGER AS PER DRAWING. (10'-0"X1'-6" /2'-0"X 9'-0"</b>				
	Providing and fixing trophy case using 19mm commercial ply finished in 4.0 mm thick VENEER of approved Shade, Max height of the case upto false ceiling bottom , Sides and top and bottom out of commercial ply and Veneer. Internal shelving (3 nos. internal shelves. of the case to be done using 10 mm thk. R polished glass in shelves (The Glass fixed with u brackets). Complete with closing of all joints and accessories complete in all respect as per direction of Engineer-In-Charge.	90.00	SFT		
	Providing and fixing low height storage cabinets of size 2'6" (High) x 16" (Deep) along the walls, as per interior drawings, using 19mm board for carcass, shutters, vertical and horizontal partitions, 6mm ply for the back and 4.0 mm thick VENEER of approved Shade on vertical and horizontal visible surfaces. The shutters shall be overlapped on the carcass and shall be provided with hinges. The width of the shutter shall be between 12" to 15" as per the site conditions. All the exposed edges of the board shall be provided with wooden lipping 19mm x 3mm, duly PU polished/PU polish in desired shade. The inner surface shall be provided with 0.8mm thick laminate of desired shade and design. The cabinet shall be complete with handles, knobs, locks and magnet catchers etc. to the satisfaction of the Architect/Engineer.				
	<b>Makes :-</b>				
	<b>Commercial ply: Green ply ( Eco- Tech ) / Duro / Century/Amulya</b>				
	<b>Laminate : Merino / Century / Greenlam New Mica / Amulya</b>				
	<b>Telescopic Channels : Hettich/ Haffe / Godrej</b>				

	<b>Drawer locks : Hettich/ Hafele / Godrej</b>				
	<b>Auto lock : Hettich/ Hafele / Godrej</b>				
<b>25</b>	<b>Full Height Partitions (Fully Paneled) In 12 mm Thk Gypsum Board:</b>				
	Providing & fixing solid full height partition in frame work in 44mm x 44mm (16 Gauge) square section@ max. 600mm c/c both horizontally and vertically with 6 mm thick plywood on one side finished with 1.0 mm thk. Laminate & other side 12mm.thk. Gypsum Board of approved make. approved make and colour as in drawing Items to include 2"x2" t.w. for door frame. All exposed t.w. surfaces to be finished in melamine polish of matching laminate colour as directed including all necessary stainless steel finish fittings/hardware as approved by the Project Consultant / Bank complete in all respects. <b>(Note- In case of false ceiling, the vertical aluminium section member to be fixed with pucca ceiling but the area of partition payable will be below the false ceiling only) .</b>	16.00	SQM		
<b>23</b>	<b>SBI LIT UP LOGO ( SIZE 2'-0" DIA )</b>				
	Providing and making SBI logo using acrylic signage logo with light . Complete in all respect as per direction of Engineer-In-Charge.	2.00	NO.		
<b>25</b>	<b>WALL PAPER :-</b>				
	Providing and fixing wall paper (Vinyl wall covering) of approved make, Orient/ Muraspec quality on POP/ Gypboard surfaces with suitable adhesive as per manufacturers specification. (BR of the material to be taken as Rs.1400/ sq.m.).	20.00	SQ.M		
<b>26</b>	<b>BEVELED MIRROR</b>				
	Providing and fixing beveled edge decorative mirror 10 mm thk. ( as per architect selection )Superior glass complete with cp brass screws , washers, S.S. studs & clips etc.as	5.00	SQ.M		
<b>27</b>	<b>Vertical garden for reception and waiting area</b>				
	Providing and fixing 40 mm PVC vertical garden as per drgs including making of PVC vertical garden complete with PVC artificial plants, stands, pots fixed with walls/partition/Paneling. complete in all respects as per design given . The rates quoted are inclusive of making of niches,1 mm thk. laminate over the 8 mm thk ply, adhesive etc. labour scaffolding etc. complete in all respects to give the desired look and finish .	5.00	SQ.M		
<b>28</b>	<b>PAINT</b>				
<b>a</b>	<b>TEXTURE PAINT (Madarasi Dana)</b>				
	TEXTURE PAINT (Madarasi Dana) including applying average 12mm to 15mm thick POP Punning over cement plaster in line & plumb finished smooth to receive paint. (Internal surfaces of walls).as per approved.	20.00	SQM		
	<b>Makes :- Nerolac, Asian Paint, Ultratech Paint</b>				
<b>b</b>	<b>Plastic Emulsion paint</b>				
	Providing and applying Plastic Emulsion paint three coats to give an even shade after preparation of surface for painting by scrapping etc. & filling including one primer coat, complete in all respects (Colour to approval) applicable to old or new.	20.00	SQM		
	<b>Makes :- Nerolac, Asian Paint, Ultratech Paint</b>				
<b>c</b>	<b>Enamel paint</b>				
	Providing and applying enamel paint three coats to give an even shade after preparation of surface for painting by scrapping on shutter, doors, windows and grill etc. & filling including one primer coat, complete in all respects (Colour to approval) applicable to old or new.	10.00	SQM		

	<b>Makes :- Nerolac, Asian Paint, Ultratech Paint</b>				
<b>29</b>	<b>OFFICER'S TABLE- Size 1500mm x 750mm x 750mm</b>				
	<p>Supplying and installation of Table as per the following description and as designed by the Architect:</p> <p>Table Top: Providing and fixing 19 mm thick IS 303 BWR grade plywood with 4mm thick veneer with melamine finish with necessary intermediate support. Table top shall be supported by 18 mm thick BWR grade ply wood with plywood framing. The top of the table shall be provided with equal sized 12mm thick toughened glass with polished edges. The top level of the glass shall be 750mm. Apron (Modesty Panel) made from 18mm thick BWR grade plywood finished with 1mm laminate.</p> <p>Table sides, back &amp; intermediate panels (at 500mm from each side) made from 18 mm thick MR plywood finished with 1mm laminate for exposed surfaces (4 faces) and 0.8 mm thick laminate for inner surfaces shall be provided as per drawing.</p> <p>Drawer / Storage cabinet: Box of 400 X 750 X 720 mm shall be provided using 18 mm thick BWR grade plywood. Each Drawer Fascia made out of 18 mm thick plywood and all sides of drawers be made of 12 mm thick plywood &amp; bottom of drawers shall be of 8 mm thick BWR grade plywood. The drawer unit box and individual drawers to be fixed with 1mm laminate on all exposed sides and all the internal surfaces shall be finished with 0.80 mm thick balancing laminate. The drawers to be fitted with Telescopic sliding channel with SS Group locks of approved make and 100 mm long brush finish Stainless Steel handles C-type for each drawer. The front ply of the drawers to be overlapping the frame.</p>	<b>2</b>	<b>no.</b>		
	<p>Computer Keyboard (550 x 375 mm) of metal / PVC of approved make shall be provided. Footrest of 38 x 76 MM T.W members shall be provided. All internal surface will have min. 0.80 mm thick balancing laminate. Table shall have stand of 18 mm ply finish with 1 mm thk. Laminate of size 400 x 375 mm for keeping CPU and PVC cable Manager shall be provided in the cutouts on the tabletop. All edges to be provided &amp; fixed with teak wood lipping patti finished with melamine polish. All the surface without teak veneer / laminate / balancing laminate shall be lacquered polished of approved shade.As per drawing and instruction of Architect/Bank, work to be completed.</p> <p>Plywood Make: Greenply, Century, Duro or equivalent approved by the Bank.</p>				
<b>34</b>	<b>MEETING ROOM TABLE</b>				
	<p>Providing and placing in position Meeting Room tables of approx. size 1200mm in diameter (size to be considered based on site conditions).</p> <p>Providing &amp; Fixing Conference Table of shape as per design made from 50mm X 40mm T. W. Wood framework 450mm center to center both ways for tabletop covered with 12mm thick BWR ply for bottom, 19mm thick BWR ply for top, table stand and base with necessary 50mm X 40mm vertical supports. All exposed surfaces shall be finish with approved color 1 mm thk. laminate. All internal surfaces to be finished with 0.8mm thick laminate. All edges to be provide with TW lipping patti finished with melamine polish. Rate shall be inclusive of Brush Finish Stainless Steel Tray with POP UP Flap for electrical switches including necessary openings for wire manager, mikes carting away unserviceable materials out of the compound,cleaning the site etc. complete as per the detail drawing and instruction of Engineer.</p> <p>Plywood Make: Greenply, Century, Duro or equivalent approved by the Bank.</p>	<b>1</b>	<b>no.</b>		
<b>35</b>	<b>SIDE/ REAR CREDENZA- For officer and clerical staff table</b>				

a	Low Height Cupboard with Laminate Finish: Providing & fixing Low Height Storage Cupboard of 750 height and 450mm deep. Outer exposed structure with to be made with 19mm BWR ply as per IS 303 and back side using 8mm BWR grade ply. All shutters to be made from 25 mm thk BWR Ply and shelves to be made with 19 mm thk.BWR ply.The top portion of the side and rear credenza to be finished with approved veneer and finished with melamine polish. All the other internal and external surfaces to be finished with 1mm laminate of approved shade and All edges to be provide with TW lipping patti finished with melamine polish. Shutters will have concealed handle with wooden groove finished with approved shade of melamine polish as per drawing, magnetic catchers, self-closing SS hinges, locks (Godrej/ Hettich/Hafele), SS towerbolts etc. All shutters to be made overlapping the frame Only front elevation will be considered for area calculation. As per drawing and instruction of Architect/Bank, work to be Completed Plywood Make: Greenply, Century, Duro or equivalent approved by the Bank.	0	no.		
b	Same as above- but finished externally with approved <b>quality veneer with melamine polish</b> complete instead of 1mm laminate to match with design of tables.	2	no.		
36	<b>LOW HEIGHT STORAGE CABINETS/BACK STORAGE: (0.75 HIGH)</b>				
a	(a) Providing and fixing storage cabinets of size 2'6" (High) x 16" (Deep) along the walls/partitions, as per interior drawings, using 19mm board for carcass, shutters, vertical and horizontal partitions, 6mm ply for the back and 1mm laminate of approved shade on vertical and horizontal visible surfaces. The shutters shall be overlapped on the carcass and shall be provided with Hettich /Godrej/Ozonehinges. The width of the shutter shall be between 12" to 15" as per the site conditions. All the exposed edges of the board shall be provided with wooden lipping 19mm x 3mm, duly PU polished/deco painted in desired shade. The inner surface shall be provided with 0.8mm thick laminate of desired shade and design. The cabinet shall be complete with handles, knobs, locks and magnet catchers etc. to the satisfaction of the Architect/Engineer.	-	SQ.M		
b	Same as above- but finished externally with approved <b>quality veneer and PU coating finish over melamine polish</b> complete instead of 1mm laminate.	2.79	SQ.M		

37	<p><b>WALL/ COLUMN PANELING WITH LAMINATE FINISH.</b></p> <p>Wall paneling made from 25 x 25 x 1.00 mm thick hollow aluminum sections, over which BWR grade ply of 10 mm shall be fixed and additional 6-8mm ply in layers to create grooves as per the design in the drawing or as directed by Architect, with decorative molding patty on the edges. Providing and fixing in position wooden paneling to column / walls finished with laminate comprising as under:-</p> <p>(i) Framework:- Made out of 50 mm x 25 mm x 1.2mm thick extruded Aluminium hollow sections, placed not exceeding 600 mm centre to centre, bothways (horizontal and vertical), fixed rigidly on wall / columns in perfect line, level and plumb.</p> <p>(ii) Panel Finishing:- Providing &amp; fixing 9 mm thick approved make BWR plywood and additional 6-8mm ply in layers to create grooves as per the design to Aluminum framework finished with 1.00 mm thick approved quality and shade laminate, using approved adhesive, in approved pattern &amp; design, including providing grooves, decorative moldings etc. as per Architectural drawings and as directed at site by the Engineer-in-charge.</p> <p>(iii) Providing approved quality, seasoned, full length, Teak Wood molding 15 mm thick with adequate width as required at site, to all openings, cutouts etc duly polished with melamine polish complete as directed by the Engineer-in-charge at site.</p> <p>(iv) The rate should include cost of necessary hardware, making cutouts / openings for electrical conduits / cables, Switch boards, AC ducts etc., including providing necessary wooden/aluminum section members support at cutouts, doors/windows openings etc. complete as per drawings and as directed by the Engineer-in-charge at site.</p> <p>(v) Applying 2 or more coats of melamine polish to exposed edges of paneling, moulded beadings etc. including preparation of surface, sealer coats etc. complete including wastage of material, if any, scaffolding for execution of work at all heights and locations etc. Approved make:-</p> <p>(a) Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Bank.</p> <p>(b) Plywood:- Greenply, Century, Duro or equivalent approved by the Bank.</p> <p>(c) Laminate:- Dorby Mica, Greenlam/Century/Archid / Aerolam or equivalent approved by the Bank.</p> <p>(d) Adhesive: Fevicol SH/Vamicol or equivalent approved by the Bank.</p> <p>Mode of measurement:- Though, the aluminium frame may extend above false ceiling level, clear paneling area available below false ceiling shall only be measured after deduction for all openings above 0.50 Sqm.</p>	17.77	SQ.M		
38	<p><b>FULLY GLAZED DOOR</b></p>				
	<p>Providing and fixing position 12 mm fully glazed toughened glass door, single/ double shutter, of approx. size 900/ 1500 x 2100/2400 mm</p> <p>Providing and fixing in position frameless glass door shutter made using 12mm thick toughened glass fixed to the partition (glazed / solid / gypsum partitions) using heavy duty floor spring with pivot of approved make including necessary cutting of floor and making the surface good to its original position including all necessary Patch fittings of approved make and fixtures &amp; hardware.</p> <p>Approved make: DORMA Top Pivot - PT 24, Top Patch Fittings - PT 20, Bottom Patch fittings - PT 10, Floor Spring - BTS 75 V, Corner lock with strike plate and Handle - TG DIH600 - 600mm length) or equivalent brand fittings from Hettich / Hafele / as per sample approved by the Bank. Rate should also include providing film as per design/ instructions of Bank.</p> <p>Mode of Measurement: Door opening size shall be measured.</p>	3.90	SQ.M		

<b>39</b>	<b>FULL HEIGHT FULLY GLAZED PARTITION WITH 12MM TOUGHENED GLASS UPTO 7' LEVEL WITH SOLID PARTITION ABOVE 7' LEVEL</b>				
	<p>Providing &amp; fixing full height glazed partition with 12mm Toughened glass of approved make up to 7' level height with solid partition above 7'-0" level up to false ceiling bottom.</p> <p>The glazed panels shall be fixed to the existing floor and false ceiling with all necessary SS brackets (D, C or U type)</p> <p>Vertical joints between the glass panels shall be sealed with suitable transparent sealant.</p> <p>The solid partition above 7'-0" level shall be made with aluminium framework of size 63mm X38.10mm X1.47 mm (0.780Kg /mtr) box section. The spacing of the Horizontal and Vertical members are approximately 600mm c/c (maximum) and the top of the frame shall be fixed to the RCC slab bottom. The exposed surfaces on both sides of framework are covered with 6mm BWR ply finished with 1.0mm thick laminate as per direction.</p> <p>Providing, placing in position &amp; erecting full height partition in desired shape, framework shall be of 50 x 50 x 1.5 mm thick aluminum square section placed at 500 mm c/c both ways or as directed.</p>	<b>22.65</b>	<b>SQ.M</b>		
<b>40</b>	<b>MDF FLUTED WOODEN PANELLING</b>				
	<p>Wall paneling made from framework of 25 x 25 x 1.20 mm thick hollow aluminum sections spaced 600mm c/c, over which MDF fluted wooden panel of 10mm +/- 2mm shall be fixed as per the design in the drawing or as directed by Architect.</p> <p>(i) Framework:- Made out of 25 mm x 25 mm x 1.2mm thick extruded Aluminium hollow sections, placed not exceeding 600 mm centre to centre, bothways (horizontal and vertical), fixed rigidly on wall / columns in perfect line, level and plumb.</p> <p>(ii) Panel Finishing:- Providing &amp; fixing 10mm +/- 2mm thick approved MDF Wooden Panelling fixed on the aluminum sections with tongue and groove joints in line and level.</p> <p>(iii) The rate should include cost of necessary hardware, making cutouts / openings for electrical conduits / cables, Switch boards, AC ducts etc., including providing necessary wooden/aluminum section members support at cutouts, doors/windows openings etc. complete as per drawings and as directed by the Engineer-in-charge at site.</p> <p>iv) The Duco paint shall be of approved make and shade. The surface to be painted shall be first prepared smooth by applying proper grade of sandpaper/water-paper and then if any pores are noticed the same shall be filled with approved quality synthetic filler agent. The complete surface shall be then applied an even coat of sealer putty and permitted to dry. The surface shall be again grinded smooth and even using appropriate grade of water-paper. When the surface is properly smooth and leveled without any pores or cracks the same shall be spray painted with approved quality Duco paint. The adjoining surfaces which are not to be painted with this application shall be suitably masked using appropriate masking tape. The paint shall be permitted to dry at room temperature and attain smooth lustrous finish.</p>	<b>5.86</b>	<b>SQ.M</b>		

<b>41</b>	<b>FULL HEIGHT SOLID / PARTLY GLAZED WOODEN PARTITION WITH BOTH SIDES LAMINATE</b>				
	<p>Providing &amp; fixing in position 70mm thick +/- 2mm solid / opaque partly glazed full height wooden partitions with 1200 mm high glass middle panels finished with laminate on both sides comprising as under:-</p> <p>(i) Framing- Made out of 50mm x 50mm, 1.2 mm thick hollow aluminium sections not exceeding 600 mm c/c bothways (horizontal and vertical) except in glazed portion of partition, fixed rigidly on floor, wall / column &amp; ceiling. Spacing of frame members may vary to the nearest possible extent as per site conditions.</p> <p>(ii) Plywood skin:- Providing &amp; fixing 12mm thick MDF boards on both sides of the framework.</p> <p>(iii) Finishing:- Providing 1.00 mm thick, approved quality and shade laminate, on both sides of partitions in approved design &amp; pattern including making grooves as per Architectural drawing or as directed by the Engineer-in-charge using approved quality adhesive complete.</p> <p>(iv) Providing and fixing 12mm thick approved make 1200 mm high toughened Glass panels in the middle panels of partitions using second class seasoned teak wood moulding of finished sectional size 75mmx12/15 mm all-round, complete as per drawing and as directed at site. (iv) Making suitable cutouts/openings/channels for Doors, electrical conduits, cables &amp; switch boards, AC ducts etc including providing necessary wooden supports wherever required and directed at site.</p> <p>(v) Providing and making suitable door frame with rebate for door shutters using approved quality seasoned full-length Teak Wood having finished sectional size 75mm x 20mm to the door perimeter complete as per detailed Architectural drawing and as directed at site.</p> <p>(vi) Applying 2 or more coats of approved matching shade and finish, melamine polish to all exposed edges of partitions including those in door openings, cutouts etc. complete.</p> <p>(vii) The rate shall include cost of required hardware, necessary transportation, execution of work at all heights and locations including all lead, lift, wastage, statutory liabilities etc.</p>	<b>10.66</b>	<b>SQ.M</b>		
	<p>Approved make:-</p> <p>(a) Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Bank.</p> <p>(b) MDF Board:- Greenply, Century, Samrat or equivalent approved by the Bank.</p> <p>(c) Laminate:- Greenlam/Century/Archid or equivalent approved by the Bank.</p> <p>(d) Adhesive: Fevicol SH/Vamicol or equivalent approved by the Bank.</p> <p>Mode of measurement:- Though aluminium frame shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sqm.</p>				
<b>42</b>	<b>FALSE CEILING FINISHED WITH LAMINATE</b>				
	<p>Same as Gypsum false ceiling but instead gypsum boards providing, making, and fixing 12 mm thick. BWR Grade ply, and additional 6-8mm ply in layers with molding of approved design shall be fixed as per drawing or as directed by Architect, with decorative molding patty.</p> <p>The plywood should be finished with 1 mm thick. Laminate of approved colour(wooden finish) and quality.</p>	<b>1.49</b>	<b>SQ.M</b>		
<b>43</b>	<b>Center Table (3'-0" X 2'-0" Oval / Rectangular)</b>				
	<p>Providing and supplying in position oval or rectangular centre table to be made out of 2" X 2" teakwood frame including 12mm thk clear glass top with bevelled edges including bottom glass shelf with etching etc complete. The rate shall also include SS lining design to the teakwood frames including all the necessary hardware, fittings, fixtures as per manufacturers specifications complete.</p>	<b>1</b>	<b>NOS</b>		

44	BACK PAINTED GLASS + LOGO				
a.	<p><b>Back painted glass (Lacquer Glass) paneling:</b>  Providing and fixing in position wooden paneling to column / walls finished with Back painted (Lacquer Glass) comprising as under:-  (i) Framework:- Made out of 50 mm x 25 mm x 1.2mm thick extruded Aluminium hollow sections, placed upto 600 mm centre to centre, bothways (horizontal and vertical), fixed rigidly on wall / columns in perfect line, level and plumb.  (ii) Panel Finishing:- Providing &amp; fixing 9 mm thick approved make BWR plywood to Aluminum framework finished with 8 mm thick approved quality and make back painted Lacquer Glass panels of required size, rigidly fixed using 3M adhesive / double side self-adhesive tape complete as directed by the Engineer-in-charge.  (iii) The rate should include cost of necessary hardware, making cutouts / openings for electrical conduits / cables, Switch boards etc., including providing necessary wooden/aluminum section members support at cutouts, providing scaffolding for execution of work at all heights, complete as per drawings and as directed by the Engineer-in-charge at site.</p>	4.46	SQM		
b.	<p><b>Logo:-</b> Providing and fixing in position with SS studs or as directed laser cut Logo as per design made from 18 mm MDF board (exterior grade) and and 10 inch -12 inch high and finished with PU metallic paint as directed complete with acrylic</p>	1	NOS		
45	WOODEN FLOORING + SKIRTING				
	<p>Providing and placing in position wooden laminate flooring with planks of size not less than 1200 mm X 190 mm (with unlink panels / tongue-groove locking arrangement) having a 0.2 mm thick top abrasive layer followed by decorative layer upon HDF (high density fiberboard) substrate core over raisin saturated backing layer installed using tongue-groove system over 2 mm thick underlayer of polyurethane foam on 250-micron polythene sheet over a smooth, flat, hard and free from moisture floor surface complete in all respect with required accessories like end profile, transition profile, reducer 'T' profile etc. and preparation of base including all other incidental works as per direction &amp; satisfaction of Architect in charge. Cost of Laminate Floor Accessories, Skirting, End edge, T- molding, Reducer shall have to be added in the cost, wherever required. <b>Grade :- AC4</b></p>	28.02	SQ.M		
46	<p><b>Polyester Film over glazed partitions:</b>  Providing and fixing in position high impact resistant Polyester Films of approved design &amp; pattern which once installed on glass, give additional strength to glass, reduce glare &amp; prevent glass from splintering on impact. <b>thickness not less than 4 Mil (100 mic.) or 7 Mil (175 mic.)</b></p>	20.66	SQ.M		
47	<p><b>BUY BACK</b> ( All the old grid/false ceiling, Alumunium partition, wooden partition, tables and low height/full height storage are to be included in Buy back except for the material in good condition and that can be reused. Also , if the existing material in good condition is to be included in buy back , prior approval from Branch Manage is recommended.</p>	-1	NOS		
<b>Total Value of Works</b>					
<b>NOTE: GST SHALL BE PAID EXTRA</b>					

THAPAR AND ASSOCIATES  
C.A. No. 2014/2015  
Mobile: +91 9514660375