

PRICE-BID

SUPPLY, INSTALLATION, TESTING & COMMISSIONING OF 3 NO. ELEVATORS AT SBI, ZONAL OFFICE, LUDHIANA & 1 NO. LIFT AT RACC, JALANDHAR

S.NO.	SPECIFICATIONS	QNTY.	UNITS	RATE	AMOUNT
1	Supply, Installation, Testing & commissioning of machine room less (MRL) elevator with following general specifications, complete in all respects.	3	Job		
a)	Capacity: 8 passengers (544kg)				
b)	No. of stops :				
	Lift -1 & 2	4 (G+3)			
	Lift -3	4 (Basement+ GF+2)			
c)	Available well size				
	Lift -1 & 2	1850 x 1860mm			
	Lift -3	1915 x 2390 mm			
d)	Pit depth: to be customized as per requirement				
	Available: Lift -1 & 2	1665 mm			
	Available for Lift -3	1795 mm			
e)	Approx. Vertical travel: 14m appx.				
f)	Cabin & door finish – SS Hairline 441 with handrail				
g)	Minimum speed (1 m/s)				
h)	Door type - automatic doors with infrared security curtain				
i)	Flooring - Silver brushed stainless steel finishing (with space for fixing Granite floor)				
j)	Diffused lighting, concealed blowers				
k)	Mirror on 1 cabin wall (half height)				
l)	Automatic Rescue Device (ARD)				
m)	Floor announcement system				
n)	Three-way Intercom				
o)	Machine Type: Machine Room Less - Gearless				
p)	Drive System: Micro Processor Based VVVF				
q)	1 year Warranty included				

	<i>MAKES: SCHINDLER / OTIS / KONE / FUJITECH / HYUNDAI / JOHNSON / MITSUBISHI/HITACHI</i>				
2	LIFT WITH GLASS DOORS & ONE SIDE GLASS WALL (RACC, JALANDHAR)				
	Supply, Installation, Testing & commissioning of machine room less (MRL) elevator with following general specifications, complete in all respects.	1	Job		
a)	Capacity: 8 passengers (544kg)				
b)	No. of stops :				
	Lift -4	4 (G+3)			
c)	Available well size				
	Lift -4	1465 x 2084mm			
d)	Pit depth: to be customized as per requirement				
	Available for Lift -4	1985 mm			
e)	Approx. Vertical travel: 14m apprx.				
f)	Cabin & door finish – SS Hairline 441 with handrail. <ul style="list-style-type: none"> One wall (Outer side): SS frame with glass Doors: SS Frame with glass 				
g)	Minimum speed (1 m/s)				
h)	Door type - automatic doors with infrared security curtain				
i)	Flooring - Silver brushed stainless steel finishing (with space for fixing Granite floor)				
j)	Diffused lighting, concealed blowers				
k)	Mirror on 1 cabin wall (half height)				
l)	Automatic Rescue Device (ARD)				
m)	Floor announcement system				
n)	Three-way Intercom				
o)	Machine Type: Machine Room Less - Gearless				
p)	Drive System: Micro Processor Based VVVF				
q)	1 year Warranty included				
	<i>MAKES: SCHINDLER / OTIS / KONE / FUJITECH / HYUNDAI / JOHNSON / MITSUBISHI/HITACHI</i>				
	TOTAL OF ITEM (1+2)				
3	CREDIT OF OLD MATERIAL:				
	Disconnecting, Dismantling and removal of old existing lifts including the cabins, doors, machines, pulleys, cables including controllers etc.	4	Lot		
	TOTAL AMOUNT (3)				
4	TOTAL AFTER BUY BACK (1+2-3)				

COMPREHENSIVE ANNUAL MAINTENANCE:					
5	Providing annual maintenance inclusive of parts & labor for additional period after 1 year of included warranty			Rate (Rs.)	Amount (Rs.)
a)	1 st Year	4	Lot		
b)	2 nd Year	4	Lot		
c)	3 rd Year	4	Lot		
d)	4 th Year	4	Lot		
<i>TOTAL (a+b+c+d)</i>					
GRAND TOTAL (4+5)					

Note: ***GST as applicable will be paid extra***

SIGNATURES OF BIDDER WITH SEAL