

**SCHEDULE OF WORKS : CIVIL /STRUCTURAL WORKS**  
**PROJECT : REPAIRING/STRENGTHENING OF EXISTING BITUMINOUS ROAD-LANE 2, A BLOCK AT SBI STAFF QUARTER**  
**COMPLEX,DAVID HARE ROAD DURGA PUR**  
**DAVID HARE STAFF QUARTER DURGA PUR**

| Sl. No. | Item Description   | Unit | Quantity | Rate (Rs./Unit) | Amount(Rs) |
|---------|--|------|----------|-----------------|------------|
| 1       | Box cutting in road embankment in all sorts of soil<br>Depth up to 200 mm  | Sqm  | 110      |                 |            |
| 2       | Water bound Machadam Base Course: Providing, laying and spreading and compacting stone aggregate of specific sizes, rolling with vibratory roller 8-10 tonne capacity in stages to proper grade.....<br>Grading -II Aggregate (53mm to 22.4mm) using stone screening Type B(11.2m) | Cum  | 18       |                 |            |
| 3       | Cleaning of old road surfaces with wire brush  | sqm  | 110      |                 |            |
| 4       | Providing & laying tack coat with bituminous emulsion  | sqm  | 470      |                 |            |
| 5       | Providing and laying bituminous machadam with Mobile Hot Mix plant (Light Duty) with power roller including cost and carriage of stone materials and bitumen all complete (35-50mm)- rate is inclusive of hire charges of machinery  | sqm  | 470      |                 |            |
| 6       | Providing and laying 25mm premixed Carpet with mixing of 20mm and 12mm grade including heating and mixing with bitumen, followed by rolling with power roller including cost of all materials, labours all complete  | sqm  | 470      |                 |            |
| 7       | Providing and laying 6mm premixed Carpet with mixing of 6 mm grade including heating and mixing with bitumen, followed by rolling with power roller including cost of all materials, labours all complete  | sqm  | 470      |                 |            |
| 8       | Sand spreading and bituminous tack coat over seal coat area  | sqm  | 470      |                 |            |
| 9       | Dressing and chiselling road flanks including cutting and filling with earth up to 150 mm  | sqm  | 110      |                 |            |
| 10      | Providing and erecting Brickwork with good quality 1st class brick in mix proportion of mortar = 1 : 4 or 1 : 6  | Cum  | 10       |                 |            |
| 11      | Plastering (avg. 15 mm thick) with cement : medium sand mortar = 1 : 4 to walls, ceiling, columns, beams, etc., at any floor level   | sqm  | 40       |                 |            |
| 12      | Pouring and placing in position Plain Cement Concrete (PCC) in all sorts of structural members at any level as directed with mix proportion of either 1 : 1.5 : 3, or, 1 : 2 : 4, as directed, for nominal mix with a water-cement ratio of 0.45                                   | Cum  | 4        |                 |            |
| 13      | Stone dust filling in box cutting required as per the site conditions  | cum  | 6        |                 |            |
| 14      | Carriage of excavated earth and dumping the same out of the quarter complex without any risk and liability to the Bank   | cum  | 15       |                 |            |
| 15      | Protection of base of light posts with cement plaster and painting of edges/kerb stones throughout the length and breadth of the road  | Ls   | 1        |                 |            |
|         | TOTAL  |      |          |                 |            |
|         | TOTAL AMOUNT IN WORDS  |      |          |                 |            |

**Signature of the Contractor with official seal**

**# Bank reserves the right to select any material out of the specified make.**

TER