

BOQ FOR CIVIL WORK OF					
SBI, SAMANNAY AWARD STAFF QUARTER, RUKMINIGAON, GUWAHATI (REPAIRING WORK)					
Sl.No	Description of items	Unit	Qty	Rate (Rs.)	Amount (Rs.)
1	PAINTING ON STEEL AND OTHER METAL SURFACE: Synthetic enamel paint, aluminium paint / bituminous paint on steel and other metal surfaces. i).Removing old paint from steel and other metal surface and making the surface even.	Sqm	11		
2	Exterior Painting: Finishing walls with ready mixed Premium acrylic emulsion paint of green pro eco labelled products of Asian paint, Burger or equivalent brand of required shade as per instruction of Engineer in Charge having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives after thoroughly brooming the surfaces to remove all dirt and remains of loose powdered materials as specified and directed by the department. Repairing work (Two or more coats applied @ 1.43 litre/ 10 sqm. Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm. The rate is inclusive of scaffolding and staging if required, removal of unwanted plants from walls & application of suitable chemicals for prevention of growth of plants, plastering of damaged portions of wall and chajjaas (with application of fibre reinforced concrete, wall putty and water proofing materials for finishing) whenever required as per instruction of Engineer in charge.	Sqm	10995		
3	Supplying,fitting and fixing PVC pipes of 6kg/cm2 (Supreme/Prince) or other ISI approved including joining,fitting and fixing with clamps etc as necessary complete at all levels including below G.L as directed as specified a) In exposed surfaces or trenches 75mm/110 mm dia (as per instruction of Engineer in Charge)	RM	51.2		
4	Removal of scrap materials, soil, plants from the roof top of each block, cleaning the floors, removal of unwanted plants and disposal/dumping of unserviceable items as per instruction of Engineer in charge or by following the GMC Guidelines. The nos in BOQ denotes the numbers of blocks in the complex.	Nos	7		
5	Removal of scrap materials, dead trees from the premises of Quarter complex and cleaning the premises & disposal/dumping of unserviceable items as per instruction of Engineer in charge or by following the GMC Guidelines.	Lumpsum	1		
6	Septic tank cleaning: Cleaning of existing rectangular septic tanks and outlets with the help of local body/Municipality and private sanitation agencies, if any, to equipped with appropriate technology, machinery etc. (mechanised solution) and ensure that only trained professionals are allowed to enter the sewer/septic tanks. Septic tanks for block C, B in the Samannay SBI Award staff quarter complex as per instruction of Engineeer in charge.	Each	2		
			TOTAL		