

COVER-II PRICE BID					
	1. Rate must be quoted for every item.				
	2. Rate to be quoted both in figures and in words clearly and legibly. In case of discrepancy rate in words will be considered.				
	3. No cutting , over writing , corrections will be allowed.				
	4. Each page of the Price Bid must be signed by the bidder before submission.				
	5. Price bid must be sealed in a separate envelop clearly marking COVER-II on top of the envelop , otherwise the same will not be considered .				
S.N	DESCRIPTION	UNIT	QTY.	RATE (INR)	AMOUNT (INR)
1	<b>Dismantling Work</b> Dismantling, cleaning and stacking reusable material on Ground floor (space has to be specified by bank). Item includes disposal of waste material outside of municipal limit by truck /tempo. Stacking and disposal as per Banks instruction. Contractor must visit the site and refer drawings to take first hand information.	Job	1.00		
2	<b>VITRIFIED TILES FLOORING</b>				
	Providing and laying Vitrified tiles in floor in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @3.3 kg/sqm including grouting the joints with white cement and matching pigments etc. The tiles must be cut with the zero chipping diamond cutter only . Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, leveling system and rubber mallet for placing the tiles gently and easily.				
	Double charge vitrified tile polished finish of size				
a	Size of Tile 600 x 600 mm. ( base rate of tile 70 /sqft)	Sqm	20.00		
3	making door opening in existing brick wall. Item includes placing required props/ support to structure.	No	1.00		
4	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centring, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	Cum	0.25		

S.N	DESCRIPTION	UNIT	QTY.	RATE (INR)	AMOUNT (INR)
5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete up to plinth level. 5.22.6 Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	15.00		
6	<b>PLASTERING</b>				
a	12 mm cement plaster of mix : 1:4	Sqm	25.00		
7	<b>FULL HT SOLID PARTITION - WITH BOTH SIDE LAMINATE</b>	Sqm	43.00		
	Providing and fixing partition framing shall consist of Aluminum Section 50 mm x 50 mm ( Wall Thickness 2 mm) @ 2'0" C/C Both ways Horizontally and Vertically. The framing shall be finished with 8 mm thk. BWR ply on both side 1.00 mm thk. approved shade Laminate shall be fixed from both sides of ply. Provide 4" high skirting in 1.00 mm thk. approved laminate to fixed as per drawing and direction. Rate shall be inclusive of necessary hardware items, etc. Complete.				
a	Item same as above but glazed partition. Glass shall be 6mm thick toughen glass and with 3M film in desired pattern.	Sqm	13.00		
b	Item same as 1 (a) but with 8 mm bison board (or approved cement board) on both side in place of 8 mm WP ply.	Sqm	25.00		
8	<b>SEMI HT. PARTITION IN LAMINATE</b>				
	Specification same above but of low ht with 8 mm thk. ply on both sides finished in 1.0 mm. thk laminate as per the drg. A 3" x 1" steam beach wooden molding with champhered edge is to be provided on all external edges & finished in melamine / zinc as per details. Providing and Fixing inserted Soft board / White boards maintaining the vertical surface lines and no extra measurements would be taken for the soft boards / white boards.	Sqm	10.00		
9	<b>PANELLING ON WALLS IN LAMINATE FINISH</b>	Sqm	25.00		
	Providing and fixing paneling on wall. Framing shall consist of Aluminum Section 50 mm x 25 mm (Wall Thickness 2 mm) @ 2'0" C/C. Both ways horizontally and vertically on the wall. This framing would be covered by 8 mm thk. Ply finished in approved 1.0 mm. Thk. Laminate. Wooden moulding, lipping etc. as directed by architect shall be provided wherever required				

S.N	DESCRIPTION	UNIT	QTY.	RATE (INR)	AMOUNT (INR)
a	<b>BISON BOARD WALL PANEL IN LAMINATE FINISH</b>	Sqm	20.00		
	Providing and fixing paneling on wall. Framing shall consist of Aluminum Section 50 mm x 25 mm (Wall Thickness 2 mm) @ 2'0" C/C. Both ways horizontally and vertically on the wall. This framing would be covered by 8 mm thk. bison board finished in approved 1.0 mm. Thk. Laminate. Wooden moulding, lipping etc. as directed by architect shall be provided wherever required.				
10	<b>ENTRANCE DOORS - WITH TOUGHENED GLASS (PATCH FITTINGS) (DORMA FITTINGS)</b>				
a.	FULLY GLAZED (12MM THK TOUGHENED GLASS)	Sqm	5.00		
	Providing and fixing frameless fully glazed 12mm thk toughened float glass fixed with necessary patch fittings(Dorma make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jams including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 12" long S. S. (C Shape) Handles of approved make, floor springs, and any necessary hardware items.(DORMA MAKE Top Pivot - PT 24, Top Patch Fittings - PT 20, Bottom Patch fittings - PT 10, Floor Spring - BTS 75 V, Corner lock with strike plate and Euro Profile Cylinder - US 10, Handle - TG 9300 EQ - S 25mm dia X 300mm length)				
11	<b>P/F DOORS IN LAMINATE FINISH WITH / WITHOUT FRAMES</b>				
	Providing and fixing solid doors of sizes as shown in the drawing. The door shutter shall of 35 mm thick flush shutter of approved make and finished with 1mm thick approved laminate on both sides. The edges finished with steam beach lipping. A door frame of 3.5" x 2" teak wood section shall be provided finished in melamine. Rate shall include Dead lock ( Godrej Make), floor springs / door closure ( as the case may be), door stopper, a pair of handles 12" SS Brushed finished, 5" hinges 4 Nos., buffers, tower bolts, etc. with necessary hardware items and with or without door frames / withdoor frame as mentioned below.				
a	Door shutter with frame specification same as above.	Sqm	2.00		
b	Door shutter without frame specification same as above.	Sqm	5.75		

S.N	DESCRIPTION	UNIT	QTY.	RATE (INR)	AMOUNT (INR)
12	<b>FALSE CEILING - GYP BOARD</b>				
	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate	Sqm	20.00		
	G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter				
	channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound ,				
	jointing tapes , finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charge but excluding the cost of painting with : 12.45.1 12.5 mm thick tapered edge gypsum plain board conforming to IS: 2095- (Part I) :2011 (Board with BIS certification marks)				

S.N	DESCRIPTION	UNIT	QTY.	RATE (INR)	AMOUNT (INR)
13	<b>MODULAR FALSE CEILING</b>				
	Providing and fixing mineral fibre false ceiling tiles at all heights of size 595X595mm of approved texture, design and pattern. The tiles should have Humidity Resistance (RH) of 99%, Light Reflectance ? 85%, Thermal Conductivity k = 0.052 - 0.057 w/m K, Fire Performance as per (BS 476 pt - 6 &7)in true horizontal level suspended on interlocking T-Grid of hot dipped all round galvanized iron section of 0.33 mm thick (galvanized @120 gsm) comprising of main T runners of 15x32 mm of length 3000 mm, cross T of size 15x32mm of length 1200 mm and secondary intermediate cross T of size 15x32 mm of length 600 mm to form grid module of size 600x600 mm suspended from ceiling using galvanized mild steel item (galvanised@80gsm) 50 mm long 8mm outer diameter M-6 dash fasteners, 6 mm diameter fully threaded hanger rod up to 1000 mm length and L-shape level adjuster of size 85x25x2 mm, spaced at 1200 mm centre to centre along main 'T'.	Sqm	10.00		
	The system should rest on periphery walls /partitions with the help of GI perimeter wall angle of size24x24X3000 mm made of 0.40 mm thick sheet, to be fixed to the wall with help of plastic rawl plug at 450 mm centre to centre & 40 mm long dry wall S.S. screws. The exposed bottom portion of all T-sections used in false ceiling support system shall be pre-painted with polyester baked paint, for all heights. The work shall be carried out as per specifications, drawings and as per directions of the engineer-in-charge.With 16 mm thick beveled tegular mineral fibre false ceiling tile (NRC 0.55 to 0.6				
	Flush fitting 1200mm long cross tees to be interlocked between main runners at 600mm to form 1200 x 600 mm module. Cut cross tees longer than 600mm require independent support. 600 x 600mm module to be formed by fitting 600mm long flush fitting cross tees centrally between the 1200 mm cross tees. Perimeter trim to be Armstrong wall angles of size 3000x19x19mm, secured to walls at 450 mm maximum. Installation to be carried out by Armstrong Trained Installation team & Installation should be carried out as per Armstrong recommended procedure. ARMSTRONG SUSPENSION SYSTEM - Armstrong make Anchor Fastener, Hanger Wire 2.5mm dia, Hook Clip with J Wire assembly. APPROVED MAKE – Armstrong/ Knauf/ Hunter Douglas/ Tranquill. <b>(DSR-2021 ITEM NO-26.27.1)</b>				

S.N	DESCRIPTION	UNIT	QTY.	RATE (INR)	AMOUNT (INR)
14	<b>Furniture Work</b>				
	Providing and laying tables / counters/ desk/ of overall size of top as mentioned in item. It shall consist of 25 mm thk BWR Ply top as per design sides and modesty panel of on 19 mm thk. BWR Suitable (as per Architects design). This shall be finished with 1.0 mm laminate of approved color and make. All inner sides shall be finished with 0.75 mm thick. All edges shall be finished with 2 mm thick edge binding tape . Item includes all accessories and hardware of approved quality. (telescopic channels, pop-ups, SS handles, locks etc.				
	<b>AGM / OFFICER TABLE</b>				
	Providing and laying a desk of overall size of top as mentioned. It shall consist of 19mm thk. BWR. Ply top as per design shall be double edged 38 mm thick and it will be supported on 19 mm thk. Comm. Ply verticals. 38 x 38 mm Steam beach (as per Architects design) wooden moulding with melamine shall be provided to the edge of the top.				
	A 19 mm thk. BWR Ply apron shall be provided as per Architects design with necessary pattern. The Table top should be finished with 1.0 mm Laminate (suede finish) of approved make and all other external to be finished in 1.0 mm. thk. Laminate (suede finish). Each top should be provided with 75 mm dia PVC wire manager of approved quality near the CPU / Monitor position as shown in drawing. 1 no. ready made, sheet metal CPU trolley with lockable wheel (as approved) finished in black colour powder coating.				
	Computer ready made, white powder coated, metal key board tray -1no. as approved with telescopic / double (ebco make sliders). A drawer unit as shown in the drg shall be provided. 3 nos of drawers and 1 no. of tray with 1.0 mm. Thk. Laminate shall be provided. Height of drawers shall be 3", 4" and 11". Drawer shall consist of ½" thk. BWR Ply sides, back and 6mm thk. BWR Ply base. Facia of drawers shall be of 19 mm thk. BWR Ply finished in 1.0 mm. Thk. Laminate (suede finish) and with a wooden moulding on top/bottom edge for handle. 25 mm gap to be maintained between each drawer. Each drawer shall slide on a pair of telescopic drawer sliders(ebco/beck) and individually lockable. 12 mm beveled edge glass top has to be provided on table top. Glass shall have wire manager according to CPU position All inner side surfaces including shutters shall be finished with 0.75 mm thick balancing laminate of matching colour.Rate shall be inclusive of all necessary approved fittings like locks(Godrej make) for drawers and any miscellaneous hardware items. Complete work including seperate inclined footrest.				

# SBI

S.N	DESCRIPTION	UNIT	QTY.	RATE (INR)	AMOUNT (INR)
a	AGM TABLE (2100 x 900 mm) with Side credenza size 1100 mm x 700 mmx 450mm deep x 900 mm.	Each	1.00		
b	OFFICER TABLE 1500 x 750 mm Table and Side credenza upto size 1000 mm x 700 mmx 450 mm deep x 900 mm.(Analysis)	Each	4.00		
15	Repair / renovation / resizing of existing tables (as per specifications given above) by changing defective ply, accessories (locks, hinges, sliding rails and handles) , changing laminates ( as per above specifications, design and new color scheme ) . Item includes complete work including paint and polish.				
a	CM / OFFICER / TABLE 1500 x 750 mm Table	Each	7.00		

SIGNATURE OF BIDDER AND SEAL

S.N	DESCRIPTION	UNIT	QTY.	RATE (INR)	AMOUNT (INR)
16	<b>SIDE CABINETS</b>				
	Providing & fixing in position Side Cabinets having side partition drawers,shelves, shutters fabricated out of 19mm thick BWR board with 6mm thick BWR ply wood backing, all exposed surfaces, side side & front finished with 1mm thick laminate, top with high gloss laminate as per approved sample complete colour with shelves, drawers,shutters. Item includes providing and fixing necessary hardware,hinges,locking arrangement with lock, telescopic steel channel runners ,handles, stainless steel wire manager as per approved sample. Providing and fixing 0.8mm thick laminate fixed over on all visible & invisible internal surfaces of shutters, drawers internal side of back ply, side and both sides of vertical, horizontal members with 2mm thick edge binding tape fixed with adhesive on edges of BWR board/ply as required etc. complete to the satisfaction of Architect / Bank's Engineer.				
a	Cabinet Size : 900X450X750mm (3'X1'4"X2'6").	Each	2.00		
17	<b>FULL/ Low HT. Storages (450 mm DEPTH X2100 mm HT.) IN LAMINATE FINISH.</b>	Sqm	18.00		
	Providing and laying Full / low ht. Storage units of sizes as mentioned above. They shall consist of a top of 25 mm thk. BWR. Ply, 19 mm thk. BWR. Ply sides and base, 6 mm thk. Comm. ply back, 19mm thk. BWR. Ply shutter/ glass shutter with self closing hinges of ebco make (full oval open) . All external surfaces to be finished in 1.0 mm laminate (suede finish) and hidden (internal surface ) 0.8 mm laminate of approved make.				
	Division of shutters shall be made equally according to the length of the storage. A 19 mm thk. Fixed Ply shelf on battens shall be provided at 400 mm / specified intervals from the base.				
	1 mm thick PVC Lipping (edge binding) with matching to laminate colour shall be provided to the edge of the storage top . All inner surfaces including shutters, rear side, shall be finished with 0.75 mm thick balancing laminate of matching colour.				
	Rate shall be inclusive of all necessary approved fittings like hinges(ebco make), locks, 4" long brushed finish handles, tower bolts, 100 mm high SS legs (as required) and any miscellaneous hardware items.				



S.N	DESCRIPTION	UNIT	QTY.	RATE (INR)	AMOUNT (INR)
18	<b>PLASTIC EMULSION PAINT</b>				
	Providing & applying plastic emulsion paint on walls, columns & ceilings. The rate shall include scrapping, levelling & preparing the surface. Primer coat + (minimum) 3 coats to get evenly spread quality finish (roller finish) of approved make , quality & finish shall be provided. NOTE : Rate shall also include - Filling up the cracks in walls & ceiling, making good surface.	Sqm	210.00		
19	<b>ENAMEL PAINT</b>				
	Providing & applying 1 <sup>st</sup> quality oil paint of approved make, quality & shade. The rate shall include scrapping, levelling & preparing the surface / base and primer coat.	Sqm	30.00		
				<b>TOTAL</b>	
					<b>GST EXTRA</b>
	<b>SIGNATURE OF BIDDER WITH SEAL</b>				