

BOQ for wooden wall panelling work for State Bank of India, on 6th floor lobby area at LHO, Sector - 17, Chandigarh					
S.No	ITEM	QTY	UNIT	RATE	AMOUNT
A	INTERIORS / FURNISHING				
1	Dismantalling of existing all required furniture, partitions, ceiling, electrical work, all kind of doors & windows, AC Units, AC duct required cutting & closed the void / vent of duct matching with existing material, hanging tight the remaining & Repairing. All old material hand over to the bank authorities.	1.00	Job		
	All existing under woodwork which is infected by termite, shall be treated by spraying at the point of contact with adjoining masonry wall with suitable chemical treatment as per IS Code 6313				
2	Wall Paneling: Providing and fixing paneling over the existing wall made out of framework of 50 mm X 25 mm - 18 gauge section un anodised Aluminium (as per requirement) frame work @ 16" to 24" c/c vertically & horizontally. Frame work for bands - 3" / 6" / 9" /12" & 15" as required paid in sq. feet. The frame work to be clad with 8.0 mm thick commercial ply and following finishings as per drawing and instructions. All exposed surfaces to be clad with teakwood moulding of size 30 mm X 12.0 mm made to shape. The work should be complete in all respects including provisions of grooves duly designed & finished. All wood to be treated with wood preservatives of approved ISI quality. All exposed teak wood shall be Malamine polished with matching pigment. The rate shall include for antitermite treatment on the wall as well as on the back side of ply and providing grooves in laminate & wood. Payments shall be made only for exposed surfaces & actual measurement at site. Note - Panelling for AC duct covering - Aluminium frame work / section shall be supported to wall & soffit of RCC slab / beam etc. under False ceiling & payments shall be made only for exposed surfaces of teak ply / laminate.				
	Panelling finished with 1.0 mm thk. Approved shade & colour -suede / glossy / wood grains / veneer texture laminates.	300.00	Sft.		

S.No	ITEM	QTY	UNIT	RATE	AMOUNT
3	Painting Work – Plastic Emulsion: Applying three or more coats of plastic emulsion (Asian / Nerolac) including making of surfaces with oil based putty and rubbing, etc. in case where the surface has been white / colour washed, the old white / colour wash shall be entirely removed and surface broomed / scrapped down before the new paint is applied. Rates include Scaffolding for all heights, cleaning splashes from glass panes, floor, furniture , etc. The work shall be completed in all respects to the entire satisfaction of the Architect.	300.00	Sft.		
	Repair of exisitng gypsum board flase ceiling with complete painting and finsing up to satatisfaction of bank.				
4	Painting Work – Enamel Paint: Applying two or more coats of enamel paint (Asian / Nerolac) on wooden / steel surfaces including filling and making of surfaces smooth with oil based putty required to give even and smooth surface. Rates include Scaffolding for all heights, cleaning splashes from glass panes, floor, furniture etc.	150.00	Sft.		
	Total quoted amount				
	GST Extra as / applicable				

Seal & Signature of contractor