

BOQ FOR INTERIOR AND FURNISHING WORKS OF SBI SME DAMOH BRANCH UNDER RBO-4, KATNI, JABALPUR					
S.No.	DESCRIPTION OF ITEM	Unit	Qty	Rate	Amount
A	<b>PART A: INTERIOR WORKS:</b>				
	<b>Mode of Measurements: Area of exposed and finished surfaces will be measured</b>				
1	<b>False Ceilings :</b>				
	Note : i) Rate to be included for all kinds of profiles and cut outs required for light fixtures, Speakers, Smoke detector, trap doors and AC grill in the ceiling. Provision for light fittings, AC grills and diffusers have to be made at no extra cost supported with tees, Angles, etc. suitably fixed all complete as per drawing and direction.				
1.1	<b>Gypsum Board False Ceiling :</b>	Sqmt	60.00		
	Providing, making and fixing Gypsum Board False Ceiling straight or curve any profile of reputed make which includes				
1.2	<b>Cove in ceiling :</b>	Rmt	50.00		
	Same as above but providing, making and fixing Gypsum cove (inside height 150 - 200 mm and border 75 mm) to hide strip/cove light in ceiling or to act as pelmet for roller blinds on windows or for projector screen, etc.				
1.3	<b>Mineral Fibre Grid Tile Ceiling :</b>	Sqmt	100.00		
	Mineral Fibre Acoustic Ceiling Tiles : Providing, making & Fixing at all heights & in spirit level, Acoustical Ceiling System @ Office areas with Armstrong make mineral fibre acoustical suspended ceiling system as per Manufacturer's specification				
2	<b>PARTITIONS:</b>				
	Rate to be included of all kinds of planes/levels, profiles and cut outs, etc. required for light fixtures,				
2.1	<b>Full Height Partly Glazed Partly Wooden Double Skin Plywood Partitions :</b>	Sqmt	20.00		
2.2	<b>Low Height partitions With/Without Glass :</b>	Sqmt	20.00		
2.3	<b>Full Height Laminated Double Skin Plywood Partitions Wth Both Sides Laminations :</b>	Sqmt	3.00		
3	<b>Panelling Works (Walls, Columns etc):</b>				
3.1	<b>Wall/Column Panelling - Type I :</b>	Sqmt	110.00		

	Providing, making and fixing single skin paneling ( <b>type I</b> using 6mm thick exterior grade MR commercial plywood of approved make : Century / Archid / Kitply ) on walls, front facia, boxing for rolling shutter, and/or columns and/or glazing soffits at various parts of the premises,				
3.2	<b>Cabinet for Electric Panel :</b>	Sqmt	3.00		
	Providing, making and placing in position cabinet with openable shutter around the electric panel. Cabinet and shutter made of 18mm thick exterior grade MR commercial plywood (Make:Century/Archid/Kitply).				
3.3	<b>ACP Panelling Works :</b>	Sqmt	10.00		
	ACP Panelling in ATM room & exteriors and Shutter boxing with trap door : Providing and fixing in position Aluminium Composite Panel (ACP) on wall, boxing, shutter panelling with framing of M.S. Tube sections of				
	<b>MDF Work:</b>				
3.4	<b>6 mm :</b> Providing and fixing 6 mm Thick Plain MDF sheet in required design/pattern/ shape/size, etc. for application of texture paint/finishes.	Sqmt	32.00		
4	<b>Doors:</b>				
4.1	<b>Main Door- Toughened Glass:</b> Providing, making and fixing 12mm thick single/double shutter toughened glass of make: (Saint Gobain/ Modi / Asahi)/doors, at entrance, etc. (each door shutter counted individually) of size 2.10 m x 0.85 m (approx. as per site requirement)	Sqmt	6.00		
	<b>SUB TOTAL : PART A ( INTERIOR WORKS)</b>			<b>Rs.</b>	
<b>B</b>	<b>PART B : FURNISHING WORKS</b>				
5	<b>FURNITURES:</b>				
5.2	<b>TABLES:</b>				
5.2 1	Providing and supplying Officer's table and other tables as detailed below :				
5.2 2	<b>Executives Branch Manager Table :</b>	Nos.	1.00		
	... same as item no. 7.2.1 but providing and supplying Executives Branch Manager of size 2.1 - 1.80 m x 0.90 m x 0.75 m ht.				
5.2 3	<b>Officer / Relationship Manager/ Auditor Tables :</b>	Nos.	4.00		
	...same as item no. 7.2.1 but providing and supplying Office Relationship Manager/ Auditor Tables of size 1.6 - 1.50m x 0.75m x 0.75m ht.				

5.2.4	<b>Single Window Operator Counters :</b>	Rmt	3.00		
	... same as item no. 7.2.1 but providing, making and placing in position Single Window Operators Counters fitted to necessary partitions as per item 2.2 above (The partitions will be measured and paid separately as per item 2.2 i.e. Half Height Partition) with the following specification and per dimensions specified. The overall size of each Single Window				
5.2.5	<b>Wall Mounted Writing desk :</b>	Nos.	1.00		
	Providing and fixing half round / rectangular customer voucher holders writing counter of width 900 mm and maximum depth 450 mm				
5.3	<b>Storages / Credenza :</b>	Sqmt	6.00		
5.3.1	<b>Officer Storage/Side Credenza :</b>				
5.3.2	<b>Back Credenza/Runner :</b>	Sqmt	8.00		
5.4	<b>Corian Surfaces on Furniture / Partitions :</b>				
	Note:- Work done including labour, material wastage, time limits, required hardware etc. Note: Corian Sheet use in - Salt(Translucent series), Azure & Diamond Blue, preferably on BM's table, SWO counter, as directed. The basic rate of the corian shall be Rs. 900/- per sqft.) (Make: Dupont or equivalent as approved.	Sqmt	7.00		
5.4.2	<b>Deduction</b> for lamination work wherever Corian is been used (area same as Corian).	Sqmt	-7.00		
6	<b>Glass Works:</b>				
6.1	<b>Toughened Glass Dividers For Single Window Counters and Front Partition Glazing/ATM.</b> Make: Saint Gobain/Modi/Asahi	Sqmt	5.00		
6.2	<b>Partition Glass / Glass on Transaction side of Single Window Operator Counters : 12 mm glass work :</b>	Sqmt	5.00		
6.3	<b>Partly Glazed Door :</b> (Partly Glazed Door on Floor Spring)	Sqmt	2.1		
6.40	<b>Etching Glass/Film:</b>	Sqmt	20.00		
7	<b>Hardwares:</b>				
	The following hardwares may be provided as per make specified as directed:(to be provided if not mentioned in item & required at site)				
7.1	Providing and fixing Doorset / Sterling / Ozone or as approved heavy duty <b>floor spring</b> , upper patch, bottom patch, etc. complete.	Nos.	2.00		

7.2	Providing and fixing lock keeper plate, <b>euro profile cylinder (EPC)</b> etc. complete.	Nos.	2.00		
7.3	Providing and fixing <b>night latch</b> with three keys at doors, etc.	Nos.	2.00		
7.4	Providing and fixing two lever <b>mortise lock</b> of Godrej Make with brass handle	Nos.	2.00		
7.5	Providing and fixing <b>Door closers</b> on doors of make Everite/Ozone/ Hardwyn/ Dorma or equivalent upon approval including all packing, levelling, etc. as required.	Nos.	2.00		
7.6	Providing and fixing <b>floor mounting</b> 6 lever lock for main entrance door	No.	2.00		
8	Misc. Works:				
8.1	<b>NOTICE BOARD:</b>	Nos.	1.00		
8.2	<b>Vertical Blinds</b>	Sqmt	4.00		
8.3	<b>Drop &amp; Complaint Box :</b>	Nos.	1.00		
	Providing & fixing at site drop & complaint box of size 300 mm x 400 mm to be made up of 1st class steam beach wood frame of size 25 mm x 25 mm wooden section, front 6 mm thk plain glass. The boxes shall have 12 mm py with approved shade of laminate and lockable shutter as per design 7 drawing, etc. complete.				
8.4	Providing and fixing of <b>green channel box</b> on the column made out of 18 mm thick commercial block board and green coloured 1mm thick laminate as per design and as directed by the Engineer Incharge.	Nos.	2.00		
9	<b>SUB TOTAL: PART B ( FURNISHING WORKS)</b>			<b>Rs.</b>	
<b>C</b>	<b>PART C: MISCELLANEOUS WORKS:</b>				
10	<b>Painting Works:</b>				
10.2	<b>Plastic Emulsion Paint :</b>	Sqmt	200.00		
	Providing & applying Plastic emulsion paint on walls, ceiling, etc. Removing,				
10.3	<b>Enamel Paints to Doors, Windows, Grills, Metallic Surfaces, Walls :</b>	Sqmt	20.00		
	Providing & applying Enamel Paints to Doors, Windows, Grills, Metallic Surfaces, walls, etc.				
10.4	<b>COLLAPSIBLE STEEL GATE :</b>				
10.5	Providing and fixing in position collapsible steel shutter with vertical channels	Sqmt	6		
6.8	<b>ROLLING SHUTTER :</b>				

	Providing and fixing manually operated rolling shutter of approved make and type fabricated with 18 gauge section M.S Flats	Sqmt	8		
11	<b>SUB TOTAL: PART C (Miscellaneous Works)</b>			<b>Rs.</b>	
<b>D</b>	<b><u>Part D : BOUGHT OUT ITEMS:</u></b>				
12	<b>Sofa set :</b>				
	Providing, making and fixing in position sofa set with side arms made for best quality badam/hillock wood framework and legs	Nos	3		
	Measurement : no. of seats				
13	<b>SUB TOTAL: PART D (Bought out items)</b>			<b>Rs.</b>	
	<b>(A) Total of Interior Works</b>			<b>Rs.</b>	
	<b>(B) Total of Furnishing works</b>			<b>Rs.</b>	
	<b>(C) Total of Miscellaneous works</b>			<b>Rs.</b>	
	<b>(D) Total of Bought out items</b>			<b>Rs.</b>	
	<b>TOTAL ( A+ B+C+D) excluding GST</b>			<b>Rs.</b>	