

PRICEBID FOR INTERIOR WORK OF STATE BANK OF INDIA SME BRANCH (NEW PREMISES) AT ABW TOWER,GURUGRAM, HARYANA

				Date:- 26.05.2025	
S.No.	Description of work	Unit	Qty	Rate (In Rs.)	Amount (In Rs.)
PRICE BID INTERIOR WORK					
1.0	PARTITIONS AND DOORS				
	Measurement of height shall be taken from finished floor level up to the level of false ceiling, in case of varying heights on either side of partition, average height shall considered. The rates include provision of extra frame work as necessary for skirting and making cutouts for electrical switch plates, switch boxes, light fittings light etc. making provision for laying conduits as per drawings & directions. All wood framework to be applied with 2 coats of fire retardant paint and 1 coat of wood preservative with anti termite treatment properties.				
a	Providing & fixing Solid Full Height Partition 75mm thick with 25x50mm aluminium sections (1.5 mm thk.) of Indal or jindal @ 450 mm c/c in both directions, (vertical member to be in one piece) 11mm thk. MDF board to be fixed on both sides and 1.0mm thick laminate pasted on both sides as per design & including provision of grooves as per drawing. Partition to have 100mm high band at skirting in laminate 1mm thick as per specified color/shade in level with partition on both sides of partition. Rest of specifications same as main specifications of partitions, complete to the satisfaction of the Architect / Bank's Engineer.	Sq.Mt.	95.00		
b	Providing and Fixing Partition For Server Room/UPS and Pantry, Same as above item no. 1 (a) but Providing both sides 10mm thick Hilux board over aluminium framing with two coats of birla putty and final two coats of plastic paint of approved make & specifications etc complete to the satisfaction of Architect/ Bank's Engineer.	Sq.Mt.	46.00		
c	Providing & fixing 12mm thick clear toughened glass in wooden partition as per drawing fixed with steam beech wood beading on both sides out of size 40x15mm with required headless nails secured to partition frame finished in lacquer polish natural color on the wood surfaces complete to the satisfaction of Architect/ Bank's Engineer. (Note :- Steam beach Included)	Sq.Mt.	33.00		
d	Providing and fixing front Frameless Patch Fitting Door with 12mm thick toughened glass with frame less glass fittings & double action floor springs as per design. The item includes providing and fixing wooden handle not less than 600 mm long on both side of glass, center lock and fittings as per the manufacturer's specifications etc. complete to the satisfaction of Architect/ Bank's Engineer.				
	Door Size:- 1000 x 2300 mm (BM Cabin & Lounge)	Nos.	2.00		

S.No.	Description of work	Unit	Qty	Rate (In Rs.)	Amount (In Rs.)
e	Providing & fixing Low Height Partition 75mm thick with same specifications as item no. 1(a) above but with 1.0mm thick hi-gloss laminate fixed on both sides with wooden top (steem beech wood) of size 85x15mm thick having 12mm thick toughened glass in between as per design and drawing fixed in partition with steem beech wood beading on both sides secured by headless nails all wood properly sanded & finished in natural lacquer polish color as per design/ drawing, height of partition to be 1220mm high complete to the satisfaction of the Architect / Bank's Engineer.	Sq.Mt.	53.00		
f	Modifying existing Doors and Chaukhats , existing door to be removed and refixed after providing it with 1.0mm thk. decorative texture laminate. Item also includes polish on all wooden surfaces etc, complete to the satisfaction of Architect/Bank's Engineer. (Items Include both side of laminate. Measurement will be considered for one side)	Sq.Mt.	12.50		
	SUB TOTAL : 1.0 : PARTITIONS AND DOORS			RS.	
2.0	PANELLING				
a	Providing & fixing Panelling with frame work with 50 x 25 x 1.5 mm aluminium tube sections @ 450 mm c/c in both directions, with 11mm thk.mdf board finished with 1.0mm thk.(texture / matt)laminate in two or more colour, provision of extra frame work as necessary for skirting and making cutouts for electrical switch plates, switch boxes, light fittings light etc. making provision for laying conduits as per drawings & directions etc. complete to the satisfaction of the Architect /Bank's Engineer. Note: Vendor to furnish picture of framing and put on record.	Sq.Mt.	324.00		
b	Providing & fixing Panelling on columns with lacquer glass same as item no 2 (a) with aluminium frame work having raised mdf panels of required thickness pasted on base of panelling board with mdf fluted panels and glossy laminate in design pattern leaving space in between for led light making provision for laying electrical conduit etc.as per design/drawing as per drawings & directions etc.complete to the satisfaction of Architect/Bank's Engineer.	Sq.Mt.	93.00		
c	Providing & fixing additional box panelling (around digital glass) finished in 1mm thick laminate as per drawing behind Branch Mgr. as per design with specifications same as item 2(a) having depth 150 /180 mm as per design/details with extra frame work as necessary for making cutouts for electrical switch plates, switch boxes, light fittings light etc. making provision for laying conduits as per drawings & directions etc.complete to the satisfaction of Architect/Bank's Engineer.	Sq.Mt.	6.00		
d	Providing & fixing Digital printing glass 6mm thick as per design on wall panelling as per design, pasted with silicone on base . Digital glass shall be as per design theme which shall be specified and design shall be given by contractor before execution complete to the satisfaction of the Architect /Bank's Engineer.	Sq.Mt.	12.00		

S.No.	Description of work	Unit	Qty	Rate (In Rs.)	Amount (In Rs.)
SUB TOTAL : 2.0 : PANELLING				RS.	
3.0	FALSE CEILING				
	Item includes providing False Ceiling in plane, curve shape and design .Suspending system and frame work shall match layout of A.C. ducts / grills, electrical /fire protection wiring / fixtures, return air grills etc. Rate to include provision of extra frame work for trap door , necessary scaffolding for double height needed due to layout of other utilities refered above and fixtures etc. Including finished with a top coat of paint. (Measurement shall be taken of the plan area only, coves to be paid separately)				
a	Providing and fixing Gypsum Board False Ceiling with INDIA GYPSUM ULTRA main g.i. ceiling sections at 1200 c/c and cross members at 450 c/c of INDIAN GYPSUM. The grid work to be suspended from ceiling with hangers at every 1200 c/c in both directions. The Frame work to be as per manufacturer's specifications. 12.5 mm thk. GYPBOARD to be screwd to the frame. The board to be finished with filling the tapered edges of the board with jointing compound and finishing with paper tape of INDIA GYPSUM. The ceiling to be finished with a top coat of royale touch paint as per manufacturer's specification along with provision of all necessary cut outs for electrical / air conditioning grills and necessary frame work including cove and curve designs etc. complete to the satisfaction of Architect/ Bank's Engineer.	Sq.Mt.	315.00		
b	Providing coves in false ceilings as per design/drawings of patta size 75/100mm high , 150mm deep with 12mm gypsum board on base(to keep LED light strip) and cove wall(vertical) again of gypsum board 100mm high. <i>(Item shall be painted in specified color and counted in running meter for measurement one time only.)</i>	R Mt	96.00		
c	Providing and fixing False Ceiling with Mineral Fibre Acoustic Ceiling Tiles Fine Fissured 600x600mm x15 mm (thk.) of Armstrong with MICROLOOK edges and having noise reduction properties laid on exposed grid system with 16mm wide Silhouette(black) type T-section flanges of white colour, main runners spaced at 1200 mm c/c securely fixed to the soffit of structure with approved hangers at 1200 mm maximum c/c. Flush fitting 1200 mm crossed tees to be interlocked between main runners at 600 mm c/c to form 1200 x 600 modules. 1200 mm cross tees to be crimped. 600 x 600 module to be formed by fixing 600 mm long flush fitting cross tees centrally between the 1200 cross tees. Rate to include making necessary cut-outs or openings for light fixtures, air conditioning grills/diffusers/speaker and other utilities etc. complete to the satisfaction of Architect/ Bank's Engineer.	Sq.Mt.	43.00		
d	Fabricating & fixing in position Wooden False Ceiling with Laminate 1mm thick over 6mm mdf panels as per specified size pasted & screwed to base of 12mm thick Comm ply suspended & secured to G.I. frame of false ceiling at 400 x 400 c/c sections with hangers in both directions secured to available metal frame . Laminate pasting in design as per detail drawings. (BM Cabin)	Sq.Mt.	7.00		

S.No.	Description of work	Unit	Qty	Rate (In Rs.)	Amount (In Rs.)
e	Supply and fixing of false ceiling system (waiting area) with panel sizes of 300mm x 3850mm in Polymer based material with thermal printing as per desired color and shade selected by architect/bank's engineer. Panel Specifications: Panel Sizes: 300mm x 3850mm Characteristics: Durable, moisture-resistant, water-resistant, and resistant to borer-fungus-termite attacks. Installation Requirements: Panels to be installed using GI sections (0.55mm / 0.8mm thick) Gauge and size of sections : 1. Perimeter channel for Fixing J trim 1.5" parameter 2. Furring Channel for Fixing Soffit. Fixed perpendicular to soffit panels every 450mm 3. Main Channel for Beam support. Fixed every 1000mm 4. Wall angle / channel for frame weight bearing Fixed ceiling to frame every 1000mm 5. Self Tapping screw - Philip pan head screw – 1" for GI channels	Sq.Mt.	8.00		
	Accessories SV 15 with dimensions 40x19x22x12x3050 (all in mm) for edge profiles SV 18 with dimensions 67x3050 mm with T head of 42mm for Connecting profiles.				
	Ceiling panels (wooden printed) make: Vox / Soulwood / Euro Pratik.				
f	Providing & fixing of baffle metal GI ceiling systems as per drawing at given spacing not less than 50/60mm gap in between with proper steel wire hanging systems as per manufacturers specification from nearest available support/roof above . Size of baffle tube 50x100mm in any powdercoated color /texture/grains and length. Make: Metacil/Unidus or equivalent	Sq.Mt.	35.00		
g	Providing and Fixing 8mm thk Hilux board of approved make on metallic grid conforming to IS:2095:1982. The metallic grid shall consist of the following components: GI Perimeter of size 27 mm and 0.5 mm thk having one flange of 20 mm and another flange of 30 mm. GI Intermediate channel of size 45 mm and 0.5 mm thk with two flange of 15 mm each at 1200 mm centre to centre. GI Hanger of size 25 mm, 0.8 mm to 0.9 mm thk at 1200 mm centre to centre distance. GI Cleat and Steel Expansion Fasteners Ceiling section of 0.5 mm thickness having curled wedge of 51.5 mm and two flanges of 26 mm each with lips of 10.5 mm at 600 mm centre to centre. Connecting clips & 12.5 mm drywall screws at 230 mm centre to centre. The metallic grid shall be installed as follows : The perimeter channel along the perimeter ceiling with screw fixed to brick wall partition with the help of rawl plugs and screws. The intermediate channels shall be suspended from the ceiling with steel GI cleat and steel expansion fasteners. The intermediate channels shall be at 1200 mm centre to centre distance. The ceiling section placed in a direction perpendicular to the Intermediate channels shall be at 600 mm centre to centre distance including 50 mm thk x 150 mm wide Recessed, etc. complete as per detail drawing, as specified and as directed by Designer. complete to the satisfaction of Architect/ Bank's Engineer. <i>The ceiling to be finished with a top coat of paint as per manufacturer's specification along with provision of all necessary cut outs for electrical work.</i>	Sq.Mt.	40.00		
	SUB TOTAL : 3.0 : FALSE CEILING			RS.	

S.No.	Description of work	Unit	Qty	Rate (In Rs.)	Amount (In Rs.)
4.0	COUNTER/ TABLES/ WORKSTATIONS				
	All Tables/ Counters/Work stations to have 18mm thk. BWR ply top and sides and 1.0 mm thk. laminate (Decorative/Texture/Metallic/High Gloss) finish on exposed surfaces along with 0.8 mm thk. white laminate on inside surface, drawer units to be made from 12 mm thk. BWR ply with 18mm thk. BWR ply FASCIA with 1.0 mm thk. laminate finish (as per individual item).The drawers to run on telescopic drawer channels. Drawer units shall have two smaller and one bigger drawer and auto locking arrangement as per specified hardware in make of materials. Footrest 75x50mm made of 2nd class teakwood member to be fixed in each table. The rate shall include providing all hardware such as drawer channels, S.S. handles,lock, aluminium cable manager flap type 80x160mm etc. complete. The item also includes a tray for keyboard running on telescopic channel, finished with laminate on top and rounded front of size 560x450mm, wooden platforms finished in laminate 1mm thick for CPU under tables etc. complete to the satisfaction of Architect/ Bank's Engineer.				
a	Providing and placing Branch Manager Table made of 12mm thk. BWR ply finished with approved 6mm thk. white solid acrylic surface on top & side edges on table and sides made with 19mm thk. commercial ply finished with 1.0mm thk. high gloss decorative laminate. Modesty panel to be made of 12mm thk. frosted toughened glass. Table top edges to be approx. 50mm thk. with solid acrylic surface finish as per design & details. Rest of the specifications for drawer units etc. shall be as per main specifications mentioned above etc. complete as per design/ drawing. The table size shall be 2400mm x 850 x 760(H)mm.	Nos.	1.00		
b	Providing and placing in position Officer Table made of 18mm thk. commercial ply top and sides finished with 1.0mm thk. laminate. Front modesty panel to be as per given design/ drawings made of 18mm thk. commercial ply finished with 1.0mm thk laminate. Rest of the specifications for drawer units etc. shall be as per main specifications mentioned above etc. complete as per design/ drawing. <i>Note: Apron of tables as per design with texture/higloss laminate basic rate of laminate Rs. 1600 per sheet.</i>				
	(i) 1530x760x760 (H)mm.	Nos.	13.00		
	(ii) 1230x760x760 (H)mm.	Nos.	4.00		
c	Providing and fixing Side Table of Officer Tables made of 18mm thick commercial ply and finished with laminate 1mm thick as per color & shade. The side table to have shuttered storage below with one shelf. The inside of side table to be finished with 0.8mm thk. white laminate. The rate shall include providing all hardware such as auto hinges, S.S. handles and locks etc. complete as per design/drawing. The side table size shall be 1000x450x760(H)mm.	Nos.	13.00		

S.No.	Description of work	Unit	Qty	Rate (In Rs.)	Amount (In Rs.)
d	Providing and placing in position Workstation Table 760mm wide (with drawer unit) made of 18mm thk. commercial ply top resting on wooden battens 18x70mm on three sides of available partition as per design drawing all exposed surface finished with 1.0mm thk. laminate. Edge of table 36mm thick finished in 2mm thick edge banding tape. Rest of the specifications shall be as per main specifications mentioned above etc. complete as per design/ drawing.	Rmt.	4.50		
e	Providing and placing in position Banking Counters (Operations) in straight/curved shapes 750 mm high made of 18 mm thk. exterior grade ply duly rounded with 6mm thk. flexi ply covering in 750mm wide working top, finished with 6mm thk. high density solid acrylic surface(any color)on top & side edges as per specified make in curved shape and rest of the structure made from 19mm thk. BWR ply finished with 1.0 mm thk. high gloss laminate in frosty white color ,design as per SBI specified standards, rest of the specifications for drawer units etc. shall be as per main specifications mentioned above but with divisions for currency as per Bank's instructions. The drawer units shall be provided with autolocking system for drawers etc. complete as per design/ drawing. <i>Note: Basic rate of 6mm thick acrylic solid surface any color Rs. 650 per sq ft.(without application)</i> (Measurement will be taken from top plan).	R.Mt.	5.00		
f	Providing and fixing Side Rack or Back Storage Unit for Banking Counters & Branch Mgr. Cabin made of 18 mm thk. BWR ply board having 450mm wide top provided with 6mm thk. high density solid acrylic surface (any color) on top & side edges as per specified make and sides with shutters design as per drawing/detail finished with 1mm thk. laminate in specified color & shade. The side table to have shuttered storage below with one shelf. The inside of side table to be finished with 0.8mm thk. white laminate. The rate shall include providing all hardware such as auto hinges, S.S. handles and auto locking locks for drawers etc. complete as per design/drawing. <i>Note: Basic rate of 6mm thick acrylic solid surface any color Rs. 650 per sq ft.(without application)</i>	Sq Mt	10.0		
g	Providing and fixing 12mm thk. Toughened Glass in front portion of single window counters with s/s brackets including cutouts for passing currency and communication as per drawing. The edges of the glass to be machine polished complete to the satisfaction of Architect/ Bank's Engineer.	Sq.Mt.	5.50		
SUB TOTAL : 4.0 : COUNTER/TABLES/WORKSTATIONS				RS.	

S.No.	Description of work	Unit	Qty	Rate (In Rs.)	Amount (In Rs.)
5.0	STORAGE CUPBOARDS				
a	Providing & fixing Low Height Box Storage cabinet 450mm deep & upto 1500mm height having <i>open book shelves in between as per design/drawing made up of 18mm thick rubber wood board integrated in storage cabinets complete with lacquer polish.</i> Cabinet box, shelves, shutters to be made with 18 mm thk. BWR ply and 6mm thk. BWR ply fixed at the back the shutters to be made without handles having recessed design /taper shutter finished with 1.0 mm thk. laminate on all exposed surfaces & 0.8mm laminate on inside surface of box cabinet. Cabinet top edge made of 36mm thick as per drawing finished with 2mm thk. edge binding tapes , all shutters to have 1mm thk. edge binding tapes(rehau) as per details including S.S. handles, self closing hinges, locks, etc. complete to the satisfaction of Architect / Bank's Engineer. (Only front elevation will be considered for area calculation)	Sq.Mt.	57.00		
	SUB TOTAL : 5.0 : STORAGE CUPBOARDS			RS.	
6.0	MISCELLANEOUS				
a	Providing & applying the walls, ceiling and elsewhere with Plastic Emulsion Paint (roller finish) after preparing the base by applying 2 coats of birla white putty for making the surface plane & smooth and then applying 2 or more coats of plastic emulsion paint with final coat done with rollers as per manufacturer's specifications etc. complete to the satisfaction of Architect/Bank's Engineer. (Removal of existing paint included)	Sq.Mt	222.00		
b	Providing & applying Texture Paint (Berger/ Dulux/ Asian) in two or more shades as approved by Bank with roller & spray, after preparing the base for the same as per manufacturer's specifications etc. complete to the satisfaction of Architect/Bank's Engineer.	Sq.Mt	43.00		
c	Providing and applying approx. 12mm thk. POP Punning on walls , ceiling and elsewhere to give a clean smooth and plumb surface as per the instructions of Architect/Bank's Engineer.	Sq.Mt	43.00		
d	Providing and fixing Louvered Shutter Cabinet Box for main Electrical panel fabricated out of 19 mm thick Bwr block board and finished with 1 mm thick laminate on outside & 0.8mm laminate on inside of approved make,having aluminium louvers in powder coated white finish. Coating of fire retardent and anti-termite paint inside. complete as per instructions of Architect/ Bank's Engineer.	Sq.Mt	4.70		
e	Providing & fixing in position 4mm thick Lacquered glass (color as specified) on facia of SWO counters duly fixed with adhesive/ s/s screw wherever required in desired pattern etc. complete as per instructions of Architect/ Bank's Engineer.	Sq.Mt	3.50		
f	Providing & fixing on fixed glass Frosting film 3M wherever required as per design & drawing in desired pattern etc. complete as per instructions of Architect/ Bank's Engineer.	Sq.Mt	10.00		

S.No.	Description of work	Unit	Qty	Rate (In Rs.)	Amount (In Rs.)
g	Providing and fixing wooden wicket gates of apprx. Size 800mm X 1220 mm made of 36 mm thk. BWR block board & both sides laminate 1mm thick of approved make and color complete with godrej premium night latch lock hinges etc. complete as per instructions of Architect/ Bank's Engineer.	No.	1.00		
h	Providing and fixing of pelmets L- shape near glass windows as per drawing made up of 36mm comm. Ply having the two dimentions 200mm each or more finished in laminate 1mm thick of desired color on exposed surface and 0.8mm white color on inside surface with teak margin 6mm thick on edge polished in natural color.	R.Mt.	5.00		
i	Providing and fixing Roller Blinds (Vista Levelor/ MAC/ DACK) of approved shade, texture and fabric including all associated accesories etc. complete to the satisfaction of Architect/Bank's Engineer. Base rate: Rs. 1900 per sq ft	Sq.Mt	15		
j	Providing and fixing of wooden planter boxes made up of 18mmthick ply on four sides with base as per design and drawing laminated with desired color of laminate 1mm thick on both sides. Lipping on edges with teak wood 6mm thick margin polished in melamine natural color complete to the satisfaction of Architect/Bank's Engineer.				
	Size : 600 x500x450mm	Nos	5.00		
k	Providing & fixing wooden battens 30mmx25mm made up of Steem Beach wood fixed on panelling (item no 2a) in a design pattern with headless nails countersunk proper sanded made smooth finish with lacquer natural polish as per drawing complete with lacquer natural polish as per design/ drawings & directions etc. complete to the satisfaction of the Architect /Bank's Engineer.	R.Mt.	200.00		
l	Providing & pasting wallpaper on MDF Panel as per design/ drawings & directions etc. with undercoat of putty and paint complete to the satisfaction of the Architect /Bank's Engineer. Note : Base rate of wall paper Rs. 7000/- per roll	Sq Mt	5.00		
m	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineerin- charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. Complete as per the directions of Bank's Engineer/ Architect. Basic rate GI sheet Rs 210/- per sqft	Sq Mt	45.00		

S.No.	Description of work	Unit	Qty	Rate (In Rs.)	Amount (In Rs.)
n	Providing & fixing of MS pipe over cabins/waiting lounge in double height hall resting over partition wall frame & suitable for framing /supporting of G.I.sheet roofing size of ms pipe at specified spacing as per drawing finished in enamel black .				
(i)	50x75x2.6mm (Weight of pipe per meter length 3.73kg Pre mt length) x 85 Mt. = 202 Kg	Kg.	317.00		
(ii)	30x30x2mm (Weight of pipe per meter length 1.70kg Pre mt length) x 50 Mt. = 80 Kg	Kg.	85.00		
o	Providing , laying & removing floor protection sheets size 4x6' or roll complete with taping of joints to protect the floor tiles from damage.	Sq Mt	150.00		
p	Scaffolding & Protection				
	To be erected in one go to the entire Site and for duration as long as all works are not completed. No member of scaffolding can be removed after erection without prior permission of the consultant				
	Providing, Erecting, maintaining for the entire contract period and including dismantling after completion of work, theNew uniformly painted Cuplock framed scaffoldwith bracing, shoring, horizontal pipes, jacks, U heads etc around the building having additional length adjustable steel pipes for horizontal and diagonal braces & shoring properly coupled with steel couplers to the main frames, without touching the building as required for the use of the workmen. The cuplock shall be made of 40 MB pipe having OD of 48.3. The height of the scaffold to be erected shall be ranging on an average of 6mt.to7 mt. The scaffolding shall have a provision of a working wooden or steel platforms properly resting on pipes and anchored.				
	These platforms can be of cantilever or long supported spans using horizontal steel props properly clamped with braces and Ties to the main scaffold, connecting two framed ends, properly anchored and back supported diagonally/or horizontally to prevent from buckling under the weight of machines, men and materials, at all comfort levels, max 1.5 to 2.00 mtr for the men and artisans to work. The scaffold shall be 150mm to 230mm away from the building or any place of work as required for different agencies & for inspection, including removal of the same after completion of works and contract period. The scaffold shall be for the use by of all the contractors and agencies appointed for the work. The contractor/executing agency shall provide extra labourers for adjusting and shifting planks as required for proper working etc within this scope of work.				

S.No.	Description of work	Unit	Qty	Rate (In Rs.)	Amount (In Rs.)
	No dismantling or removing of parts or pipes can be done without prior permissions. The Quoted Rates shall include for providing of ready made Aluminium ladder with landing one on each facade for the full length of the building for consultant and others to inspect the site. Refer attach Drg and photograph of the module. Including providing and supplying New, standard anti skid perforated galvanised working platforms (2mt x 0.3 mt) for the use by all agencies. Its Tying and Shifting shall be done free of cost whenever required & new silver oak / Bellapine scaffolding planks 35 mm thick 300mm wide in lengths of 3 mt for the use on works the ends of the planks to have GI strapping to be done with gun to prevent splitting of planks. Tying, Shifting, carting and removal of the same shall be done free of cost whenever required & providing and fixing New transparent Nylon white hessian cloth stitched together horizontally on any scaffolding of external facade to prevent debris from falling out as required for different agencies and also internally to cordon working area. Kindly note that this cloth can not be removed until the completion of the work for which it is intended for the area of works & providing and fixing wherever directed with suitable fixing arrangement, high strength nylon net (standard construction net used across the road ie two type, yellow high strength and blue small gaps net) to catch the falling plaster debris for entire duration of work. This is to be erected as directed inclusive of cantilever pipe etc.				
	Main Cup-lock frames not less than 1200 (width) x 1800mm (Length) x 1000 (high) with adjustable jacks if required for leveling and with horizontal members bracing in all the joint for safety and for cantilever platforms. & Providing and fixing NEW corrugated 22 gauge GI sheets at the convenient heights using the existing scaffold frame with additional frame supports as directed for the entire duration of external works to cover some areas and protect the area below in use while the work is in progress and to protect from falling debris or paint. Dismantling the same after the all works are completed. (Note :- Nothing extra will be paid for working in double height in case of project delay.)	Nos.	1		
q	Providing & fixing metal (SS) Tee profile (rose gold color) inserts on panelling at required distance as per drawing of size 18mm wide . Metal Tee inserts to be fixed after cutting of groove in mdf board of required size pasted with Fevicol (nail free ultra adhesive) as per drawing complete to the satisfaction of the Architect / Bank's Engineer. Basic cost of Tee insert @ Rs. 450/- per length 2.4M	R Mt	286.00		
r	Disposal of rubbish/ mulba after dismantling/ demolition including clearing building waste of all types, rank vegetation etc. all complete as per the directions of Bank's Engineer/ Architect.	No.	1.00		
	SUB TOTAL : 6.0 : MISCELLANEOUS			RS.	
	SUBTOTAL INTERIOR WORKS RS.			RS.	
Note:- The rates quoted includes all other taxes, duties, loading, unloading, transportation, other expenses etc to site. only GST will be paid Extra.					