

OFFICERS TRANSIT CAMP AT JOYSAGAR
BOQ for Electrical and allied Works

SL No	DESCRIPTION	UOM	QTY	Rate (Rs.) (Exclusive of GST on work contract)	Amount (Rs.) (Exclusive of GST on work contract)
1	Sub-main line:- Wiring in PVC conduit of IS specification of Proper size with core PVC insulated stranded copper wire 11KV grade (Finolex/Havells/Polycab/ RR Kabel/ Richa/KEI or equivalent) and with supply ,installation, commissioning of all the materials required including proper termination,connection in complete as required from main DB to various DBs:-				
i)	with 2nos 4sq.mm + 1 nos 2.5 sq.mm(1ECC)(AC & Gyser line)	RM	80		
ii)	with 3nos 6sq.mm (1ECC)	RM	30		
2	Supply ,installation ,testing and commissioning of distribution board manufactures made sheet steel enclosure With the following MCBs (DB,MCB and MCCB Make- Legrands/ Havells/ L&T/ SIEMENS or equivalent) and connecting the same to the system.				
i)	4- way VTPN Double Door Distribution Board with 63 A 4 Pole MCCB (36kA) as incomer and 10 Nos. 32A SP MCB's at outgoing	Set	1		
ii)	Light DB SPN double door with 40A (30mA)DP RCCB as incomer & 5 nos 10A SP MCB as outgoing.	Set	2		
3	Supplying, installing and commissioning of PVC Armored cable complete with proper cable glands and two nos. of 8SWG GI wire (Havell's/Richa/RR kebel/KEI or equivalent) alongwith all the other materials required including proper connection in complete as required from main Panel,Power Distribution Board to various DBs .				
i)	With 3.5 core x 25 sq. mm cable	RM	40		
4	Power point wiring in MS conduit of IS specification of proper size with 3nos 2.5sq.mm single core PVC insulated stranded copper wire 1.1KV grade(Finolex/Havells/Polycab/ RR Kabel/ Richa/KEI or equivalent) and with all material supply installation and commissioning complete from /PDB(Raw) .The wiring shall be carried out on surface above false ceiling by chiseling the existing surface and plastering the same with cement etc. after fixing the MS conduit with all accessories like saddles screws, bends T-joint etc. 2 coats of painting Matching to the surface including supply installing, testing, commissioning of modular plate type switch and socket (Legrands / MK or equivalent) for TV,power socket etc terminal on sheet steel enclosure (cadmium plated),duly fitted with screw to the steel conduit and fixed to the wall partition furniture with all interconnection and proper earthing .All the opening shall be covered with blank plate and be sealed to make the box vermin proof.B48(maximum 2 points in single circuit)				
i)	With 2 nos 6A socket with single 16A switch and cable outlet 8mm for TV unit.	No.s	3		
ii)	With 3 nos 6A socket with single switch power socket.	No.s	6		
iii)	With 2 nos A 16/6A socket with individual switch power socket.	No.s	4		
iv)	With 1nos 16A socket with individual switch	No.s	2		
5	Supply, installation and testing of Roud recessed mounted 12/15 W LED edge lit slim down light with die-cast aluminium housing finished in premium white powder coating. efficacy: 120lm/W (12/15 W LED). Make :- /Havels/Phillips/Wipro/ Crompton or equivalent. (Model to be approved by Bank's Engineer)	Nos	22		
6	Supply, installation and testing of metallic chrome with fabric white shade decorative bed side wall lamp with additional full glow 9 W warm white LED bulb. Bed side wall lamp Make Philips Model No. 581876 or identical desgine approved by Bank's Engineer.	Nos	4		
7	Supply, installation and testing of decorative wall mounting, brushed nickel finish fixture with Opal Glass diffuser suitable with 9 W LED lamp B22 base.(Make Havells Model No. LHFOAJE1TZ11060 oror similar design and specification approved by Bank's Engineer.)	Nos	6		
8	Supply installation testing and commissioning of LED batten Single Tube light fittings with 20W (Model: Havells LUMILINEBS20WLED865SPCWH or equivalent Specification) with glare free light distribution wall mounted at ceiling/false ceiling level/. Make :- Bajaj/ Havels/ Phillips/ Wipro/ Crompton or equivalent	Nos	8		
9	Supply installation testing and commissioning of foot lamp LED light fittings of 3W (3 module Make :- Bajaj/ Havels/ Phillips/ Wipro/ Crompton oror similar design and specification approved by Bank's Engineer.)	Nos	2		
10	Supply installation testing and commissioning of 20 W LED Mirror round wall light fittings with MS poly carbonate diffuser IP 44, 600mm and 2000lm/(WW) make philips (Model:Meraki-582106 or similar design and specification approved by Bank's Engineer.)	Nos	2		

Sl No	DESCRIPTION	UOM	QTY	Rate (Rs.) (Exclusive of GST on work contract)	Amount (Rs.) (Exclusive of GST on work contract)
11	Supply, installation, testing & commissioning of ceiling mounted LED strip ower Saving Led, Flexible And Long Lasting With 50000 Burning Hours.Light Bulbs And Wires Are Completely Wrapped In Flexible Plastic, With Features Of Insulation, with adopter ,Waterproof And Safety Luminaries manufacture shall provide LM79 report from NABL accredited lab & LM80 report issued by LED manufacturer.	RM	40		
12	Supply installation testing and commissioning of 10 W fixed track LED light with modern design, compact size with high power COB LED to provide focussed light. Make: Havells(Model:UNECOTRACKLIGHTS 10WLED830S15WHT/BLK or similar design and specification approved by Bank's Engineer.)	Nos	2		
13	Supply, Installation, Testing and Commissioning of decorative smart BLDC 1200 mm sweep, BEE 5 star rated, ceiling fan class of insulation: B, 3 nos. blades, 30 cm long down rod, 2 nos. canopies, shackle kit, safety rope, copper winding, Power Factor not less than 0.9, Service Value (CMM/W) minimum 6.85, Air delivery minimum 215 CMM, 350 RPM (tolerance as per IS : 374-2019), THD less than 10%, remote or electronic regulator unit for speed control and all remaining accessories including safety pin, nut bolts, washers, temperature rise=75 degree C (max.), insulation resistance more than 2 mega ohm, suitable for 230 V, 50 Hz, single phase AC Supply, earthing etc. complete as required.. Rates shall be inclusive of providing and fixing of M.S. fastner hooks for fixing the fan from the ceiling .(Make Crompton Model :Stylus or similar design and specification approved by Bank's engineer)		3		
15	Supply and installation of heavy duty Exhaust Fan 300 mm crompton/ bajaj/ usha/ havells make	No.s	3		
16	Wiring for light/fan/exhaust fan points using 3 X 1.5 1.1 kV grade PVC insulated stranded copper conductor wire (Finolex/ Havell's/ Richa/ RR kebel/ KEI or equivalent) for phase, neutral and earth in 25 mm dia heavy duty MS conduit along with associated accessories like MS junction boxes, bends, saddles, screws et. concealed in wall, floor, under flooring, below false ceiling or on surface as well as suspended from ceiling with 25mm X 3 mm MS flat suspenders duly painted above false ceiling from individual light/Fan/Exhaust Fan point outlet. etc. to individual modular type switch boards, 10 Amp modular plate type switches etc.(MK/Legrand's/Havell's or equivalent), as required complete including circuit wiring with 3 X 2.5 sqmm. 1.1 kV grade PVC insulated stranded copper conductor wire and as per site requirement and as instructed by SBI Engineer.				
a	Light point one switch control one light/ fan	Nos	15		
b	Light point one switch control two light	Nos	10		
c	Two way point in bedroom(2 nos each room) for light and fan	Nos	2		
d	Ceiling Fan point with regulator(2M)360 degree rotation	Nos	3		
e	Exhaust fan point with Ceiling rose.	Nos	3		
f	Call bell point 6A bell push 1 Module with Electronic chime(ding dong 230v-2 module)	Nos	3		
g	combine twin USB 3.1A Euro Socket typeA & type C-2 Module with switch	Nos	2		
h	same Board 6 Amps with switch and socket.	Nos.	5		
17	16 A modular MCB for Gayser point and 16A socket	Nos.	2		
18	Supply and fixing of modular 25A AC starter 2M to be provided separately with switch board.	Nos.	3		
19	Supplying and drawing co-axial TV cable RG-6 grade, 0.7 mm solid copper conductor PE insulated, shielded with fine tinned copper braid and protected with PVC sheath in the existing surface/ recessed steel/ PVC conduit as required.	RM	40		
20	Supply, erection, testing and commissioning of 3-way splitter of aluminium die cast body in suitable size of G.I. Box.	Nos.	1		
21	S.I.T.C. of 32A Mechanical key tags to be connected with all Bedroom switchboards.	Nos.	2		

Sl No	DESCRIPTION	UOM	QTY	Rate (Rs.) (Exclusive of GST on work contract)	Amount (Rs.) (Exclusive of GST on work contract)
22	supply, Installation, testing and commissioning of 15 litre capacity closed and storage type BEE 5 star rated Geyser having ABS body with stainless steel/Titanium steel tank. The geyser must have temperature adjustable knob and automatic thermal cut off protection. Working pressure of geyser should be not less than 8bar or 60N/sq.cm. The heating element of geyser must be glass coated. The temperature range of geyser should be 25 degree celsius to 80 degree celsius. Rated power of the geyser should not be more than 2000 Watt and operating voltage should be 230 Volt Single phase. The geyser should be vertical mounting type. The geyser should have red and Green indication for heating mode and non heating mode respectively. The geyser should aesthetically look good along with all the accessories like anchor fastener, cold & hot inlet pipes. The approved model of geyser of different make are Racold Andris (AN 15 LUX PLUS 2KW)/USHA Aquerra DG/Crompton Solarium Care/Jaquar Alena/Bajaj Compagno/ Havells Bianca. Model other than models mentioned for different make will not be accepted in any case.	Nos.	2		
23	Installation charges of the 1.5 TR Hi-Wall Split AC including outdoor frame / stands to withstand the full load of outdoor units and making good all the damage.	No	3		
24	Supply and Installation of 4 KVA Stabilizer with ABS body for 1.5 TR Cassette type Acs (Make/Model: V-guard : VDI 400 or equivalent)	No	3		
25	supply, Installation, testing and commissioning of 32 INCH(80 cm) LED Television Smart HD TV(1,366 x 768 minimum Resolution)Picture Engine:Hyper Real, PQI (Picture Quality Index):900, HDR (High Dynamic Range), Mega Contrast, PurColor, Contrast Enhancer, Dolby Digital Plus, Sound Output (RMS), 20W(L:10W, R:10W), SmartThings App Support Make/Model:(Samsung: 32T4360AK, LG:32LQ643bpta/ equivalent of reputed company) with wall mounting accessories.	Nos.	2		
26	supply, Installation, testing and commissioning of 185 Liter, 5 Star smart inverter Compressor, single door refrigerator Make: LG:GL-D201ABEU/ Godrej:RD EDGE 185 CW or Equivalent)	Nos.	1		
27	Supply of 1.5 TR Capacity Hi Wall mounting 5-star rated Inverter Split AC with cordless remote and Copper Condensor Coil. AC Make, Voltas/Bluestar /Carrier/Daikin /LG/Godrej(INCLUDING 3 M COPPER PIPES)	Nos.	3		
	Total				