

STATE BANK OF INDIA					
ADMINISTRATIVE OFFICE, DHANBAD					
BILL OF QUANTITY OF AIR CONDITIONING WORKS OF JHARIA BRANCH					
SNo	Item Description	Unit	Qty.	Rate(Rs)	Amount(Rs)
1	Supply and Installation, testing and commissioning of 2.0 TR Inverter Cassette Air conditioners(5 star) fitted with rotary /scroll/swing compressor with standard installation kit (Excluding cost of copper piping) with all fixing accessories, Ready made powder coated MS stand/angle heavy duty support for outdoor units , first fill of eco-friendly refrigerant (R32 or R410a) complete. Piping to be laid through nitrile rubber sleeve with white taping and to be clamped neatly. Wall openings are to be sealed and finished using cement plastering-Banking Hall	Nos.	4		
2	Supply, Installation, testing and commissioning of 2.0 TR Window conditioners (5 star) fitted with rotary/scroll/swing compressor with standard installation kit, Fabricated primered & painted MS Grill/stand for mounting ACs , first fill of eco-friendly refrigerant (R32 or R410A) complete. Wall openings are to be sealed and finished using cement plastering-	Nos.	2		
3	Refrigerant copper piping of suitable size including protective covering with foam tubes b/w indoor and outdoor units, with all necessary fittings and leak proof arrangements as required for 2.0 TR Cassette AC 's.	Mtr.	100		
4	Electrical wiring between indoor and out door units with all necessary fittings as required for Cassette AC 's for 2.0 TR (4core 4 sqmm Cu wire to be laid inside MS conduit pipe Indoor unit to Outddoor Unit)	Mtr.	100		
5	Drain piping with UPVC pipe of suitable size from the indoor unit to the drain point in Ground floor location decided by the Bank with all necessary fittings and leak proof arrangements as required for Cassette AC's	Mtr.	100		
6	Supplying, laying, testing & commissioning of PVC insulated aluminium armoured 1.1 KV grade 4.0 core 35 sqmm cable with making proper trench/support as per IS specification and complete with all respect From Main Panel to ACDBs.	Mtr.	10		
7	ACDB : Consumer unit TPN MCB DB (Double Door) complete with busbar and the following MCBs. INCOMING : 1 No. 415V 63A 10KA TPN MCB OUTGOING : 12 Nos. 240V 32A 10 KA SP MCB	No.	1		
8	AC With 2 Nos. 4 Sq.mm. + 1 No. 2.5 Sq.mm. PVC insulated copper wire to be laid inside MS conduit pipe from ACDB to AC power point.	Mtr.	80		
9	Supply & fixing of Company made approved modular type AC socket & Top with 32A SP MCB for Window AC supply.	No.	2		
10	Dismantelling of False celing and making proper after installation of Cassette ACs in the ceiling	L.S.	1		
		Total			
	# GST EXTRA AS APPLICABLE				

AC Make: Hitachi, Daikin, OGeneral, Carrier, Voltas, LG, Blue Star (5 Star)