

SHIFTING OF SBI SAORI BIDKAR BRANCH UNDER RBO CHANDRAPUR
BOQ

Sl. No.	Item Description	Qty	Unit	ESTIMATE	
				Rate	Amount
1	Supply and erection of 25mm dia PVC drain water piping (4kg/sq.cm.) upto just above ground level for all ACs including Split ACs and its insulation using 4 mm thick nitrile rubber sleeve insulation.	25	m		
2	Supply and Installation of 1.5 Tonne Capacity Hi Wall mounting 5 Star rated Inverter Split AC with cordless remote and Copper Condensor Coil. (with copper piping & cabling upto 3metre) (High Wall Split AC). Insulation using nitrile rubber insulation with Teflon taping. (1-BM & 2-ATM)	4	No.		
3	Supply and Installation of 1.0 Tonne Capacity Hi Wall mounting 5 Star rated Inverter Split AC with cordless remote and Copper Condensor Coil. (with copper piping & cabling upto 3metre) (High Wall Split AC). Insulation using nitrile rubber insulation with Teflon taping. (1-BM & 2-ATM)	1	No.		
4	Supply and laying of additional copper refrigerant piping (double circuit) for Split Airconditioners (additional length beyond 3 Metre)	50	Mtr.		
5	Control Cabling between Indoor & Outdoor Units for Non VRF Split Acs	30	Mtr.		
6	Supply and installation of powder coated ready made metallic stand for mounting ODU of Split Airconditioners.	5	Nos.		
7	Supply and Installation of 4 kVA V-Guard Stabiliser with metallic enclosure.	5	Nos.		
7	AMC for 5 years	35	Nos.		
	TOTAL AMOUNT FOR THE AC WORKS				