

**PRICE BID OF PROPOSED AC WORK
FOR DIGITAL BANKING UNIT BRANCH AT GANDHINAGAR**

Sr.No.	Description	QTY	UNIT	RATE	AMOUNT
[I] MACHINE PART					
	AC EQUIPMENT WITH - INVERTER COMPRESSOR				
1	Supply & providing of 4 way Inverter Cassette Type AC ceiling mounted cassette unit with indoor and out door having eco friendly refrigerant. Including indoor unit outdoor unit. decorative grille and cordless remote Machine shall have copper condensor Unit, Make: Daikin/ Mitsubishi Heavy Industries / Toshiba/Hitachi				
1.a	Inverter 4-way Cassette of 2.00 TR (BEE 5 Star rating)	4	NOS		
	TOTAL FOR PART- I				
[II] LOW SIDE WORK					
2	Installation of IDU & ODU of 4.00 TR / 3.00 TR / 2.00 TR ceiling mounted cassatte unit with first oil & gas charge & commissioning etc. Rate including ceiling mounted suspension Kit etc complete	4	NOS		
3	Referigerant piping - insulated 0.80mm wall thicknees copper tube of Mandav/ Totalline make between indoor to out door unit of 4.00/3.00/2.00 TR ceiling mounted cassette unit with 4 Sqmm 4 Core copper flexible cable of Finolex / R R Kable/Havells/CEI make. The copper piping shall be insulated with 13mm thick Nitrite rubber insulated of 'O' Class of K Flax/Armaflex/ Superlon Make	38	RMT		
4	25/32 mm Dia UPVC drain pipe with insulation of Dutron / Supreme / Astral make - schedule 40 pipe, white in colour, joint properly glued with UPVC adhesive for water outlet from indoor unit. (drain pipe concealled in inside wall)	29	RMT		
5	Providing and Fixing M.S Powder coated stand for keeping outdoor unit of Split A/C and cassatte AC. (Redy made)	4	NOS		
6	Misc. civil wok for entire AC work of branch (including jari in wall and jari filling, hole filling with cement mortar and finishing with core cutting putty. This also include removing of flooring tiles and providing drain pipe during shifting of AC and refixing of same color tiles ptopeprly) This work is for entire branch air conditioning system.	1	Job		
	TOTAL FOR PART- II				
	TOTAL (I + II)				