

PRICE BID FOR INTERIOR FURNISHING WORK OF STATE BANK OF INDIA ATM AT Dau Majra & Phase -10, Mohali

S.No.	Item	Qty	Units	Rate	Amount
	PANELING/PARTITION				
	Note: For the Paneling, Full height partitions and low height partitions the work measurement for costing shall be only of the plain visible surface, no extra cost for extrusions or extra frame work required as per drawing will be made. The work done above ceiling, below floor finish level or not directly visible shall not be measured.				
1	12MM THICK TOUGHENED GLASS FIXED PARTITIONS				
	Providing and fixing in position 12mm clear float toughened Glass partition with patch fittings for the full height glass partitions as per the direction of the engineer-in-charge. The work to include making necessary template for all the glasses and then cutting the clear float glass to correct size, making all the necessary holes, cuts etc., then toughen the same. (Saint Gobain/Asahi/Modiguard).	9.50	SQ.M		
	The cost to include all hardware (PATCH FITTINGS etc) required of approved make single corner patch, top and bottom corner patch etc. or as per the direction of the engineer-in-charge. The maximum size of each glass shall be 1200mm to 2000mm x 2400mm to 2700mm as per the site requirement. The rate is for a finished item of work etc., complete as directed. Glass partition will be fixed at bottom and top with patch fittings(as required). SS U-channel of 12mm X 25mm to be grouted with the floor.				
	The cost to include the cost of bevelling and smoothening of the exposed edges of the glass.				
	Makes :-				
	PATCH FITTINGS :- Hettich/ Haffele / Godrej				
	GLASS :- Saint Gobain / TATA / Asahi / Modiguard				
2	12MM THICK TOUGHENED GLASS DOORS WITH ETCHING:				
	Providing and fixing in position 12mm clear float toughened Glass for naked glass door. The work to include making necessary template for all the glasses and then cutting the clear float glass to correct size, making all the necessary holes, cuts etc., and then toughening the same. The cost to include all hardware required of approved make floor spring with its accessories, top pivot, center lock, 450mm glass door handles etc., along with etching with sand blasting as per design and drawing. The maximum size of each glass shall be as per the drawing or the direction of the Engineer-in-charge. The rate is for a finished item of work etc., complete as directed.	4.30	SQ.M		
	Makes :-				
	PATCH FITTINGS :- Hettich/ Haffele / Godrej				
	GLASS :- Saint Gobain / TATA / Asahi / Modiguard				
3	12mm thick Toughen glass for transaction partition	7.80	SQ.M		
	Makes :-				
	PATCH FITTINGS :- Hettich/ Haffele / Godrej				
	GLASS :- Saint Gobain / TATA / Asahi / Modiguard				
4	GYPSUM BOARD FALSE CEILING WITH STEPS:				
	Providing and fixing suspended false ceiling including steps and provision of cope lighting as per design with 12.5mm tapered edge Gypboard / 12mm thick Elephant Gypsum Board to the grid comprising of cold rolled galvanized metal section to the required line and level. The grid consisting of a perimeter channel fixed round the perimeter. The intermediate channel at 1200mm c/c in the one direction and the ceiling section at 450mm c/c in the other direction to be connected by a connecting clip. The grid to be suspended with an adjustable strap hanger.	14.20	SQ.M		
	The grid to be suspended with an adjustable strap hanger at 1200mm c/c on both ways from the structural soffit using a soffit cleat and expandable bolts/fasteners Nut and bolts to be used to connect strap hangers to soffit cleats and for joining ends of channel sections together. The gypsum board layers to be screwed to the M/F ceiling sections with Gypboard drywall screws. Jointing and screw spotting are then carried out as per manufacturer's standard recommendations. Perimeter Channels to be used around the cut outs for light fittings. A/C ducting etc. The work should be complete as per instructions of Architect or Engineer in charge including 2-3 coats of oil bound distemper , over a coat of primer.				
	Makes :-				
	Gypsum Board :- Saint Gobain / Gypcore/ USG Knauff				
	Ceiling Channel, Angle Screws Etc. :- Gyproc / USG Knauff				
5	GRID FALSE CEILING:				
	Silhouette Grid False Ceiling:- Providing and fixing in true horizontal level false ceiling grid system of Armstrong World Industries. The suspension system shall be the incorporating a 3mm or 6mm central recess color, black or white revealed. Silhouette main runners and cross tees to have mitered ends with "birds mouth " notches to provide mitered cruciform junctions.).	8.84	SQ.M		
	main runner of size 15 x 42 x 3000 mm spaced at 600 mm centers securely fixed to the structural soffit by approved hangers at 1200 min maximum centers hangers (BUTTERFLY CUP) to be fixed by approved roof plug, level adjusters, screws etc the last hanger at the end of each main runner should not be greater than 450mm from the adjacent wall, 600mm x 600mm modules to be formed by fitting 600mm long flush fitting cross tees of size 15 x 42 x 600mm centrally between the main runners Penmeter wall angle of size 19 x 19 x 3000mm secured to walls at 450mm maximum centers finally dune supreme ml edge rh – 99% 15 mm thick (nrc-0.50,light reflectance > 85%. Can- 34 db, k value = 0.052 to 0.057 w/m k) micro look edge has to be laid on the 600 mm x 600 mm i full size files only & shall be fixed to the gypsum false ceiling by using				

THAPAR AND ASSOCIATES
C.A. No. 100/2023/14
Mobile: +91-9516880375

	Makes :-				
	Grid Tile :- Armstrong / Knauff				
	Ceiling Channel, Angle Screws Etc. :- Gyproc / USG Knauff				
6	ACP SHEETS AT ENTRANCE				
	Providing and fixing Aluminium Composite Panel wall cladding with the 4mm thick PVDF coated aluminium composite panel (ACP) (0.25 mm coil thick) with frame of aluminium channels (25 x 50 x 1.6mm), cleat angle (8 x 18 x 2mm) necessary hardware, backup material and weather sealant to make the joints leak proof. The spacing for the channel along the length and spacing of cleat on the perpendicular shall not be more than 600mm. The rate includes all required shuttering , scaffolding, labor, material.	93.50	SQ.M		
	Makes :-				
	ACP :- Aluco bond, ALU Décor, Alstrong, Alstone				
7	SBI LIT UP LOGO (SIZE 2'-0" DIA)				
	Providing and making SBI logo using acrylic signage logo with light . Complete in all respect as per direction of Engineer-In-Charge.	4.00	NO.		
	TOTAL VALUE OF WORKS				
	NOTE: GST SHALL BE PAID EXTRA				