

PRICE BID FOR ROOF TRUSS WORK AT 3rd FLOOR ANNEXE, LHO, POOJAPPURA

No	Description of work	Unit	Qty	Rate (excl. GST)	Amount Rs.)
1	Sheet Roofing	Sq.M.	850		
	The scope of work includes dismantling the existing pvc pathy, screws , clamps, and all associated components. wherever required and fixing new GI sheet of 0.45 mm thickness above the existing sheet including necessary overlapping of sheets etc complete. Roofing sheet of 0.45 mm GI trafford sheet with matt finish and of approved make shall be fixed to the existing purlins with hot dipped galvanized self drilling fastners with integral EPDM washers and silicone sealant as necessary. Rate shall also include cost of necessary scaffolding, handling, and conveyance of materials, disposal of debris, all labour charges etc completed as per specifications. Measurement shall be taken along the sloped length of the roofing. The work is to be caried out at Thrid floor level, on the roof of a functioning office. Hence all necessary precautions shall be taken to ensure the safety of personnel, prevent disruptions to ongoing office activities and avoid any damage to the premises.				
2	GI Ridge Sheet	RM	85		
	Providing and fixing GI ridge sheet, matt finish and of approved make and shade of 0.50 mm thickness and 500-600 mm wide including necessary scaffolding cost, conveyance of all materials and labour charges etc complete				
3	GI Sheet for valleys	RM	40		
	Providing and fixing GI sheet, matt finish and of approved make and shade of 0.50 mm thickness and 1000 mm wide including necessary scaffolding cost, conveyance of all materials and labour charges etc complete				
4	PVC Pathy	RM	75		
	Supplying, laying and jointing 160 mm dia unplasticised Rigid PVC rain water pathy 15 gauge of approved quality and ISI marks and specials such as tees, bends, elbows, checknuts etc with clamps including cutting and making good the walls, floors, scaffolding etc complete as per the direction of Engineer-in-charge				
5	PVC Rain water pipe	RM	80		
	Supplying, laying and jointing 110 mm dia unplasticised Rigid PVC rain water pipes 15 gauge of approved quality and ISI marks and specials such as tees, bends, elbows, checknuts etc with clamps including cutting and making good the walls, floors, scaffolding etc complete as per the direction of Engineer-in-charge				
	TOTAL				
	GST extra				