

BOQ for INTERIOR FURNISHING WORK AT STATE BANK OF INDIA, RBO -1, GREATER NOIDA ,U.P.					
S.NO.	DESCRIPTION	UNIT	QTY.	RATE (RS.)	AMOUNT (RS.)
	FURNISHING WORK				
1.0	FALSE CEILING				
1.1	Providing and fixing suspended false ceiling in Glass Fiber Reinforced Gypsum board. Gypsum board suspended ceiling shall comprise of providing and fixing G.I. perimeter channel (MF-6A) of size 0.50mm thick having one flange of 19.6mm and another flange shall be of size 29.6mm and a web of 26.6mm along with perimeter of ceiling, screw fixed to the beam for the required curvature with nylon sleeves and screws are not exceeding 610mm centers. Then suspending G.I. intermediate channel (MF-7) of size 45mm, 0.9mm thick with two flanges of 15mm each bent to the required curvature by cutting both of its flanges. Suitable bracing to be provided where ever the flanges are cut with 0.9mm G.I. Flat and nuts and bolts at specific positions and thereafter at 1220mm centers with ceiling angle of width 25mm x 10mm x 0.50mm thick fixed to the soffit with G.I. cleats and steel expansion fasteners. Ceiling section (MF-5) of 0.50mm thickness having knurled web of 51.5mm and two flanges of 25.6mm each with lips of 10.5mm bent to the required profile by cutting both its flanges. Suitable bracing to be provided wherever the flanges are cut with 0.50mm flats.				
	Steel screws, are then fixed to the intermediate channel with the help of connecting clip and in direction perpendicular to the intermediate channel at 457mm centres. 12.5mm tapered edge Glass Fiber Reinforced Gypsum board (conforming to IS-2095-1982) is then screw fixed to ceiling section with 25mm drywall screws at 230mm centres. Screw fixing is done mechanically either with screw driver or drilling machine with suitable attachment. The boards are to be jointed and finished which includes filling and finishing the tapered and square edges of the boards with jointing compound and fiber tape suitable for Gypsum board. A layer up to of 3.00mm thickness of Veneer Plaster is applied followed by two coats of topcoat (primer) at the face of board to give smooth seamless finish. 2 or more coats of plastic emulsion paint (roller finish) of approved shade and make shall be applied. The item includes making all necessary cut outs & frame work for electrical fixtures / air conditioning work coves etc. Shall have edge groove details and cove lighting provisions as per drawings.				
	Rectifying all defects and cracks formed during the construction period before handing over the work complete. The rates shall include for necessary supports, scaffolding and labor. All as per drawing, approval and instructions of the architect / employer. Note: - Horizontal surface shall be measured for the purpose of payment.	Sq.Mtr.	258.00		0
1.2	Providing and fixing false ceiling system manufactured by M/s. Armstrong World Industries using hot dipped galvanized steel section, rotary stitched main tee of size 15mm x 42 mm web height, having 0.36 mm gauge at every 600 mm centre to centre maximum				

S.NO.	DESCRIPTION	UNIT	QTY.	RATE (RS.)	AMOUNT (RS.)
	and rotary stitched cross tee of size 15 mm x 42 mm, having 0.33 mm gauge at every 600 mm. c/c. and wallangle of size 19 x 19 mm., having 0.35 mm gauge fixed to the periphery of the wall. The above grid is suspended at every 600mm c/c. in both directions using Butterfly clip & adjustable rod hanger laying. FINE FISSURED MICROLOOK WITH SILHOUETTE GRID ceiling tiles manufactured by M/s. Armstrong World Industries, of size 600mmx600mmx15mm having NRC 0.55, Light reflectance of >84% (WT), thermal conductivity k = 0.052-0.057 W/m0K, Humidity Resistance of 99% , having Fire Performance CLASS O / CLASS 1 (BS 476), surface having 3 coats of white paint with Fine Fissured,back of the tile duly sanded and finished with a coat of protective paint over the formed grid complete. All complete as per manufacturer's specification. Rectifying all defects and cracks formed during the construction period before handing over the work complete. The rates shall include for necessary supports, scaffolding, labour. All complete as per drawing, approval and instructions of the Architect/ employer.	Sq.Mtr.	136.00		0
1.3	Providing and fixing Wooden False ceiling made of GI framework with specification same as Item No. 1.1 hanged from RCC ceiling with proper MS hangers. 12mm thick EDHMR (Exterior grade) ply is then fixed to ceiling section clad with 12mm thick fluted MDF board (Basic Rate Rs. 2000/- Sq.m) of approved design finished with two or more coats of duco paint over one coat of sealer (GLO make) on to the framework finished with high gloss paint of approved shade. Screw fixing shall be done mechanically either with screw driver or drilling machine with suitable attachment. All exposed woodwork / veneer to be melamine polished. All complete as per approval of the Architect / Engineer.	Sq.Mtr.	7.00		0
1.4	Providing and fixing printed / plain white Stretch ceiling (Basic Rate Rs. 5500/- Sq.m) of Euroceil or approved equivalent make of white colour comprising aluminium channels and PVC translucent membrane with PVC gripper, the stretch ceiling having back lighting with LED modules of OSRAM or approved equivalent make of mutiple strips with compatible drivers including supporting wooden box and frames, cutouts etc. all complete as per drawings, specifications and directions of EIC/ Architect.	Sq.Mtr.	21.00		0
	NOTE:- • False ceiling design can be stepped / curved / architectural design etc however only plan / horizontal surface shall be measured for the purpose of payment.				
	• Ceiling shall be hung from the existing slab through hanger's. Rate quoted in the tender shall be applicable for all floor levels/ all floor height including scaffolding, etc complete. The rate of falseceiling items also includes 6 mm ply backing for supporting light fixtures in the false ceiling.				
	FALSE CEILING TOTAL	:			0.00

S.NO.	DESCRIPTION	UNIT	QTY.	RATE (RS.)	AMOUNT (RS.)
II	PARTITIONS & PANELLING WORK				
2.1	Providing and fixing fully glazed partition including door made 12mm thick toughened glass fixed to the floor / wall / false ceiling with patch fittings. Exposed edges of glass shall be machine cut & polished. Door shall have 1" dia. 2'-0" long SS brushed finish handle (Hettich Make 9250424) on both sides including heavy duty double action floor-spring HETTICH Make Cat. No. 9227856 with steel cover plate, all accessories complete including lock etc. Cost includes cutting and making good the floor, walls, ceiling etc. for fixing floor spring and patch fittings. All glass to glass , glass to ceiling , glass to wooden partition & glass to floor joints shall be sealed with transparent silicon. All complete as per approval of the Architect / Engineer-in-Charge.				
a	FIXED PARTITION	Sq.Mtr.	26.00		0
b	DOOR	Sq.Mtr.	12.00		0
2.2	FULL HEIGHT SOLID PARTITION : Providing and fixing in position full height partition having overall thickness of 75mm thick approx. including 38mm thick door shutter finished with 1.0mm thick laminate on both side with steam beech wood chowkhat of size 76mm x 65mm approx. Partition made out of aluminum hollow section of 50mm x 50mm size 1.50 thick (Section no. 14525) of JINDAL / INDAL as internal frame structure placed horizontally & vertically in 600mm x 600mm center to center. Fixing 12mm thick EDHMR (Exterior grade) ply on both sides finished as mentioned below with 1.0 mm thick laminate/ 3.5mm thick veneer on top in approved shade with groove pattern as per architect instructions.				
	Item includes Heavy-duty SS ball bearing butt hinges 100 x 5.5 mm (4 Nos. per shutter) with screws, door closer, cylindrical door locks, door stopper, melamine polishing all necessary hardware etc. All exposed woodwork to be melamine polished. All complete as per approval of the Architect.				
a	One Side Finished with 3.5mm thick veneer & one side finished with 1.0mm thick laminate.	Sq.Mtr.	93.00		0
b	Both side of partition finished with 1.0mm thick laminate	Sq.Mtr.	54.00		0
2.3	LOW HEIGHT PARTITION				
	Providing and fixing in position low height partition of 2100mm / 1200 mm high with 12mm thick toughened glass with 3M glass film as per design including 38mm thick Flap door shutter finished with 1.0mm thick laminate on both side with steam beech wood chowkhat of size 76mm x 65mm approx. made out of aluminum hollow section of 50mm x 50mm size 1.50 thick (Section no. 14525) of JINDAL/ INDAL as internal frame structure placed horizontally & vertically at max distance of 600mm approx c /c both ways. Fixing 12mm thick EDHMR (Exterior grade) ply on both sides finished with High gloss PU paint / 1.0mm thick ultra gloss laminate of Blue & White / approved shade as per Architect instructions. 12mm thick toughened glass (blue shade) as per design fixed with teak wood beading of finished size 1½" x 1" all along the edge.	Sq.Mtr.	42.00		0

S.NO.	DESCRIPTION	UNIT	QTY.	RATE (RS.)	AMOUNT (RS.)
	Item includes teak wood edging of size 3" x 1 1/2" at the exposed edges of the partition. All exposed woodwork to be high gloss PU polished. Shutter hung on 3 nos. heavy-duty SS butt ball bearing hinges of size 100 x 5.5mm with screws etc. The item inclusive Night Latch locks of Godrej make (ULTRA C2) with both side key, s tower bolt etc. complete in all respect. All complete as per approval of the Architect / employer.				
2.4	Providing and fixing frosted / striped / designer glass film of 3M, Avery Dennison or equivalent (basic rate of film Rs. 600/ Sq.m.) on existing glass as per manufacturer's specification. All as per drawing, approval and instructions of the Architect / Eingneer-in-charge.	Sq.Mrt.	19.00		0
2.5	Providing and fixing in position paneling on existing wall including making niches, cove, design as per drawing shall be made out of aluminum hollow section of 50.80mm x 25.40mm size 2.03 thick (Section No. 14003) of JINDAL / INDAL as internal frame structure placed horizontally & vertically in 600mm x 600mm center to center. Frame work clad with 12mm thick EDHMR (Exterior grade) ply finished with high gloss PU paint / 1.00mm thick edge laminate in approved shade with groove pattern as per Architect instructions. The item also includes 32mmx 25mm steam beech wood moulding finished with melamine polish, scaffolding etc. All complete as per approval of Architect / Engineer.				
a	Finished with 1.0 mm thick laminate premium range (Basic rate Rs. 550/- Sq.m. including transportation)	Sq.Mrt.	100.00		0
b	Finished with 3.5mm thick veneer (Basic rate Rs. 1200/- Sq.m. including transportation)	Sq.Mrt.	54.00		0
c	Panelling finished with pre finished flutes (Basic Rate Rs. 2000/- Sq.m)	Sq.Mrt.	14.00		0
2.6	Providing and fixing hollow box of size 6" x 3" fixed at floor and ceiling level at a distance of 230mm aprox. with planter boxes as per design . All made of 18mm thick EDHMR board finished with 3.5mm thick veneer (Basic Rate Rs. 1200/- Sq.m) of approved shade. All wood work / veneer to be finished with PU polish as per instructions of Architect / Engineer-in-Charge. Item includes providing white pebbles of size 50mm-75mm approx in floor.	Sq.m	13.00		0
	Note For Item No. 2.1, 2.2,2.3, 2.4, 2.5 & 2.6 : - For the purpose of payment partition shall be measured including the area of door / door frames up to false ceiling height.				
a)	Framework shall be rigidly secured to floor, bottom of slab & existing walls at 600mm c/c with dash fasteners.				
b)	For All Full height partitions (Toughned Glass, Solid, Partly Glazed) framework and ply shall be provided up to the bottom of slab. The item also includes scaffolding for maximum height upto 4000 mm from floor etc complete				
c)	Center to center spacing may vary to make provision for fixing dado rail / to adjust the level of glass or for fixing counter / storage units or otherwise as per site requirement.				

S.NO.	DESCRIPTION	UNIT	QTY.	RATE (RS.)	AMOUNT (RS.)
d)	No extra payment shall be made for reduction in framework, opening as indicated in the drawing or as instructed by the Engineer-in-charge. Framework shall be rigidly secured to floor, walls and ceiling by dash fasteners etc. at maximum 600mm c/c.				
e)	For full height solid / partly glazed partitions rate also includes providing and fixing steam beach chowkhat, doors with laminate / veneer as per the specification of the items including handles, locks, door closer, door stopper, Hinges / patch fittings, accessories etc of approved make. Ref. HETTICH Cat. 1) FOR door closer Article no. : 9227817 (2) Handle Article no. 922768 (3) Mortise cylinder lockcase Article no. 9228136 (4) Europrofile Clynder Lock Article No. 9228171 (5) Ball bearing butt hinges 102 x 76 x 3 mm article No.9287297(6) Door stooper: 9228709 (7) Cylindrical door lock 9228335				
f)	For all full height partitions (solid / partly glazed / toughend glass) rate also includes providing and doing infill of 50mm glass wool insulation having density of 24kg/ cu.m. with polybag covering on either sides in partition framework.				
2.0	PARTITION WORK	TOTAL:			0.00
3.0	WORKING COUNTERS / TABLES				
3.1	Providing and placing the tables as per drawing and the following specification : Table top made out of 18mm thick EDHMR (Exterior grade) board (Double Layer 18+18mm). Top finished with 3.5mm thick veneer /1.0mm thick laminate of approved shade as mentioned below. Item includes 10mm thick clear float Glass on the table top with all beveled edges machine cut & polished. Bracing panel, sides made of 18mm thick EDHMR (Exterior grade) board (double layer 18+18mm) finished with 1.0mm thick laminate & 12mm thick flutes (Basic Rate Rs. 2000/- Sq.m). All exposed edge of board shall be finished with the steam beech wood edging. Top supported on side credenza and drawer unit as per detail drawing. Each table shall be provided with 1 No. grommet, 1 No. CPU Trolley, 1 No. footrest, 1 No. prefabricated computer key board tray including drawer slides 12.5" x 22" tray with 14" telescopic slides including L-brackets for securing to the table top. Side credenza made out of 18mm thick EDHMR (Exterior grade) board and finished with 1.0mm thick laminate of approved shade.				
	Drawers Base, Back & sides @ 12mm thick EDHMR (Exterior grade) ply. Front @ double layer, inside of 12mm thick ply, outside 18mm thick EDHMR (Exterior grade) board. All external surfaces shall be finished with 1.0mm thick laminate of approved shade and all internal surfaces shall be finished with 0.8 mm thick laminate. All drawers shall run on drawer slides.				
	All exposed edge finished with the edges steam beech wood edging. All veneer & woodwork to be melamine polish and all non laminated surfaces to be finished with two or more coats of spirit polish. All complete including lock, auto- closing hinges, 6" long S.S. handles, studs for adjustable shelving etc.				

S.NO.	DESCRIPTION	UNIT	QTY.	RATE (RS.)	AMOUNT (RS.)
a)	T1 2400mm x 1000mm x 750mm high with side credenza 1650mm x 450mm x 712mm & drawer unit 450mm x 600mm. Finished with 3.5mm thick veneer & laminate	Nos.	1.00		0.00
b)	T2 1800mm x 900mm x 750mm high with side credenza 1450mm x 450mm x 712mm & drawer unit 450mm x 600mm. Finished with laminate	Nos.	3.00		0.00
c)	T3 1500mm x 750mm x 750mm high with side credenza 1350mm x 450mm x 712mm & drawer unit 450mm x 600mm. Finished with laminate	Nos.	3.00		0.00
d)	T4 1200mm x 600mm x 750mm high with side credenza 1350mm x 450mm x 712mm. Finished with laminate	Nos.	1.00		0.00
3.2	Providing and fixing 600mm wide working counter as per following size and specification. Working top made out of made out of 18mm thick EDHMR board (double layer 18+18mm) top side finished with 1.0mm thick laminate (basic rate of laminate Rs. 1100/- per sheet) of approved shade & counter side with 0.8mm thick laminate. Front edge of the counter finished with 2mm thick PVC edge banding tape of matching colour of laminate. Top fixed to the solid partition / wall with MS brackets. Vertical support of 18mm thick EDHMR board finished with 0.8mm thick laminate shall be provided at every 1200mm approx. distance below counter. All non laminate surface to be enamel painted. Item includes readymade metal powder coated CPU trolley, grommet for every 8 sq.ft area, Keyboard pull out tray made of 0.7 mm thick CRCA steel duly powder coated, of minimum thickness 45micron, with metallic roller slides (Telscopic channels Ref Hettich Article No. 9193319) on both sides and shall be fixed to the bottom of worktop surface with the help of screws. Drawer unit made out of 18mm thick EDHMR board having 2No's drawers at top and one no. openable shutter below.				
	Drawers Base, Back & sides @ 12mm thick EDHMR ply Front @ double layer, 12mm thick EDHMR ply. All drawers shall run on hydraulic drawer slides. Top drawer shall have partitions as per requirement made of 6mm thick EDHMR ply. Item Includes auto closing hinges, lock, 150mm long S.S. brush finish handles. All exposed edge finished with 2mm thick PVC edge bandinbg tape. All surfaces exposed to view shall be finished with 1.0mm thick laminate (Basic rate of laminate Rs. 1100/- per sheet). All internal surfaces, under counter top shall be finished with 0.8mm thick laminate. All complete as per drawing, approval and instructions of the Architect / Employer.				
a)	L-Shape workstation Size 1500mm x 2000mm x 750mm with 2 No's pedestals (Drawer units).	No's	3		0.00
b)	L-Shape workstation Size 1500mm x 1500mm x 750mm with 2 No's pedestals (Drawer units).	No's	23		0.00
c)	600 wide linear workstation with 2 No's pedestals (Drawer units).	Sq.M	5		0.00

S.NO.	DESCRIPTION	UNIT	QTY.	RATE (RS.)	AMOUNT (RS.)
3.3	Providing and placing Meeting Table of size 11000 x 1800 x 750 with following specification :- Top made of 18mm thick EDHMR board (double layer 18+18mm) over frame work finished with 3.5 mm thick veneer (basic rate of veneer Rs. 1200/ Sq.m) of approved shade. All exposed edges sealed with steam beech wood moulding of size 2 ½" x 1 ½". Leg supports @ 1000-1200mm c/c spacing made of 18mm thick EDHMR ply board (double layer) finished with 3.5mm thick veneer. Bracing panel made of 18mm thick EDHMR board (double layer) cut to shape finished with 1.0mm thick laminate of approved shade. All exposed edges of board shall be finished with steam beech wood edging. All wood work / veneer to be protected with PU polish. All complete as per drawing and approval of Employer/ Architect. Top area at the centre of the table shall be measured for the purpose of payment.	Sq.M	20.00		0.00
3.4	Providing and placing side table of size 530 x 530 x 530mm as per following specification:- Top having 12mm thick Clear float glass with machine cut and polished edges. Base made of hard wood framework clad with 6mm thick EDHMR (Exterior grade) ply finished with 1.0mm thick laminate. Edges sealed with 6mm thick steam beech wood lipping. All wood work to be protected with melamine polish. All complete as per drawing, approval and instructions of the architect /employer.	Each	2.00		0.00
3.5	Providing and placing Centre table of size 1200 x 600 x 530mm as per following specification:- All made of 18mm thick EDHMR board double layer(18+18mm) finished partly in veneer (basic rate of Veneer Rs. 1200 per Sq. M) and partly in 1.0mm thick laminate (basic rate of laminate Rs. 2200 per sheet) of approved shade. Edges sealed with 6mm thick steam beech wood lipping. Base fixed on 75mm high SS leg supports as per design. All wood work and veneer to be protected with melamine polish. All complete as per drawing, approval and instructions of the architect /employer.	Each	2.00		0.00
3.6	Providing and fixing notice board size 900mm x 1200mm approx. or as required / directed with open able shutter on the front. Made out of 18mm thick EDHMR (Exterior grade) board frame and outer frame in 65 x 37mm Steam beech wood section, concealed hinges, locking arrangement, glass of (5.5mm thick) with rear panel of SITATEX board, covered with fabric of approved shade. (Basic rate Rs. 150/- per mtr, 48" width) fixed to back ply 6mm thick. All complete including melamine polish in stain of required shade. All complete as per design and approval of the Architect / employer.	Each	1.00		0.00
3.0	WORKING COUNTERS/ TABLES TOTAL :				0.00
4.0	STORAGE				
4.1	Providing and fixing 400mm deep low ht. Storage with following specification: - Outer framework i.e. top, sides, shutters, shelving of 18mm thick EDHMR (Exterior grade) board. Back shall be of 8mm thick EDHMR (Exterior grade) ply.				

S.NO.	DESCRIPTION	UNIT	QTY.	RATE (RS.)	AMOUNT (RS.)
	Storage top shall be finished as mentioned below. All other surfaces exposed to view to be finished with 1.0mm thick Ultra high gloss laminate/ High gloss PU paint. All internal surfaces shall be finished with 0.8mm thick laminate. Skirting shall be finished with 1.0mm thick metallic laminate. All edges of the EDHMR (Exterior grade) board shall have Steam beech wood edging of 6mm x 19mm . All shutters shall be provided with lock (1 no. for two shutters), auto closing hydraulic hinges (2 nos. per shutter), brass catchers, 150mm long S.S. brush finish handles, 1 no. Intermediate shelf shall rest on studs for adjustable shelving etc. Woodwork protected with melamine polish. Entire surfaces left without lamination to be finished with two or more coats of spirit polish. All complete as per drawing, approval and instructions of the Architect / employer.				
a	Storage top shall be finished with 3.5mm thick veneer of approved shade finished with PU Polish .	Sq.Mtr	5.00		0.00
b	Storage top shall be finished with 1.0mm thick laminate of approved shade.	Sq.Mtr	42.00		0.00
4.2	Providing and fixing full height storage 400mm deep, height & length as per site and following specifications:- Framework, Shutter, Shelving, skirting made of 18mm thick EDHMR (Exterior grade) board. Back shall be of 8mm thick EDHMR (Exterior grade) ply. Vertical partitions at 3'-0" approx. c/c. All exposed surfaces finished with 1.0mm thick laminate. All internal surfaces shall be finished with 0.8mm thick laminate. All edges of EDHMR (Exterior grade) board shall be sealed with steam beech wood lipping of 6mm x 19mm . Shutters shall be provided with aluminium louvers, lock (1 no. for two shutters) , auto closing Hydraulic hinges (4 nos. per shutter), 6" long S.S. brush finish handles, S.S. studs for adjustable shelving etc. Woodwork protected with melamine polish. Entire surfaces left without lamination to be finished with two or more coats of spirit polish. All complete as per drawing, approval and instructions of the Architect/ employer.				
a	5 No's. intermediate shelf @ 400 height (Approx.).	Sq.Mt.	15.00		0.00
4.3	Providing and fixing Louvered Shutter Cabinet for main panel fabricated out of 18 mm thick Fire Retardant MDF (FRMDF) (conform to BS 476 : Part 7 Class 1) finished with putty and fire retardant paint from inside and 1 mm thick laminate of approved make & shade from outside.				
	The item to include powder coated MS louvers in both the shutters of the door of size - 300 mm x 1.2 m				
	The door is to be provided with 12 x 200 mm SS Aldrop, 150 mm SS handles (2 nos), auto closer hinges (3 Nos. per shutter) with necessary screws, harwares. All complete as per approval & instructions of the architect/ employer.				

S.NO.	DESCRIPTION	UNIT	QTY.	RATE (RS.)	AMOUNT (RS.)
	Front facia shall be measured for payment. Measurement of height shall be taken from finished floor level up to the finished edge of the cabinet and width shall be from outer edge to outer edge of cabinet. In case of varying heights on either side of partition, average height shall be considered. Measurement shall be taken of the visible front surface (elevation - 2D surface) only.	Sq.Mt.	4.00		0.00
4.4	Providing and fixing storage below pantry with following specification : Providing and fixing shutters made of 18mm thick BOILO (Action Teesa) board with wooden frame all-round of size 75mm x 37mm. Vertical partition, Shelving (3No's. max.), skirting made of BOILO (Action Teesa). All exposed surfaces finished with 1.0mm thick laminate. All internal surfaces shall be finished with 0.8mm thick laminate. All edges of BOILO Board shall be sealed with steam beech wood lipping of 6mm x 19mm. Shutters shall be provided with lock (1 No. for two shutters), auto closing hinges (4 No's. per shutter), 150mm long S.S. brush finish handles, tower bolt 150mm long, wooden batten 19mm x 19mm shelving etc. Woodwork protected with melamine polish. Entire surfaces left without lamination to be finished with two or more coats of spirit polish. All complete as per drawing, approval and instructions of the Architect.	Sq.Mtr.	2.00		0.00
4.5	Providing and fixing full height display unit 400mm deep as per design. Outer framework made of 18mm thick EDHMR board and back shall be of 8mm thick ply. All surfaces internal & external finished with 3.5mm thick veneer ply. Shutter shall be partly glazed having 6mm thick clear float glass. All edges of the EDHMR board shall have Steam beech wood edging of 6mm x 18mm. All shutters shall be provided with lock (1 No. for two shutters), auto closing hydraulic hinges (2 Nos. per shutter), 150mm long S.S. brush finish handles, 5 No. Intermediate shelf shall rest on studs for adjustable shelving etc. All veneer and woodwork protected with PU polish. All complete as per drawing, approval and instructions of the Architect / employer.	Sq.Mt.	4.00		0.00
	NOTE:- For Item no.. 5.1, 5.2 , 5.3 & 5.4 Front area shall be measured for the purpose of measurment. For hardware (Ref Hettich (1) Autoclosing hinges Artical No. 9281432 & 9281434				
4.0	STORAGES TOTAL :				0.00
5.0	MISCELLANOUS WORK				
5.1	Providing, fixing and installation of roller blinds (Basic rate Rs. 2000/- per Sq.m) of Vista make or equivalent in approved finish of required shade complete in all respect. All complete as per approval and instructions of Engineer-in-Charge / Architect	Sq.m	51.00		0.00
5.2	Providing plaster of pairs punning 2mm to 5mm approx. thick (nominal) on walls, leveling and smooth finishing the surface including sand papering the old surface etc. The rates are inclusive of scaffolding staging etc. for any height and for plane as well as for architectural surface. All complete as per directions and approval of the Architect / employer.	Sq.M.	141.00		0.00

S.NO.	DESCRIPTION	UNIT	QTY.	RATE (RS.)	AMOUNT (RS.)
5.3	Providing and applying two or more coats of plastic emulsion paint (roller finish) of approved make and shade as per the manufacturer's specifications to give a smooth surface including priming coat, scaffolding, cleaning, curing etc. complete as specification and as directed by the Architect / employer.	Sq.M.	268.00		0.00
5.4	Providing and fixing wall paper on wall, gypsum board ceiling , partition or anywhere else as required with approved adhesive (basic rate of wall paper Rs. 1200/- Sq.m.). All complete as per approval and instructions of the Architect / Engineer-in- charge.	Sq.M	10.00		0.00
5.5	Providing and placing aluminium dust buster mat for entrance door of 19 mm thickness of Euronics/approved make all complete as per the the directions of the Architect/Employer.	Sq.M.	1.00		0.00
5.6	Providing and placing SS perforated dustbin with square holes of Euronics/ approved make (Cat No.- AFBR 3FP) of size 200 x 300mm all complete as per directions of Architect / Engineer-in-charge.	Each	40.00		0.00
5.7	Providing and placing in position planter box of size 600mm wide & 450mm high made of 18mm thick EDHMR (Exterior grade) board. Inside finished with 1.0mm thick laminate and outside finished with 3.5mmthick veneer. Exposed edges of board finished with 6mm thick steam bech wood lipping. All wood work and veneer shall be finished with two or more coats of PU polish over one coat of sealer.All complete as per approval of Architect / Employer.	Each	5.00		0.00
5.8	Providing and fixing SS LOGO of 450 mm dia. Made of 304 grade stainless steel complete as per approval of Client / Architect	Each	1.00		0.00
5.0	MISCLLANEOUS TOTAL	:			0.00
	SUB TOTAL 1.0 TO 5.0 (Excluding GST)			Rs	0.00
	(RUPEES)				