

PRICE BID FOR RENOVATION & STRUCTURAL ADDITION/ ALTERATION WORK FOR STATE BANK OF INDIA BRANCH AT 'A1' BLOCK, PASCHIM VIHAR, DELHI					
CIVIL WORK					
				Date:- 20.06.2025	
S.No.	Description of work	Unit	Qty	Rate (In Rs.)	Amount (In Rs.)
A	DISMANTLING & DEMOLITION WORKS				
1	Making the opening in brick masonry including dismantling in floor or walls by cutting masonry and making good the damages to walls, flooring and jambs complete, to match existing surface i/c disposal of mulba/ rubbish to the nearest municipal dumping ground, all complete as per direction of Engineer-in-Charge.				
	For door/ window/ clerestory window	Cu.m	12		
	TOTAL			RS.	
B	RCC & Reinforcement				
1	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	Cu.m	1		
2	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level	Kg	50		
	TOTAL			RS.	
C	BRICK WORKS				
1	Brick work with common burnt clay modular bricks of class designation 7.5 in foundation and plinth in:				
	Cement Mortar 1:6 (1 cement : 6 coarse sand).	Cu.m	4.5		
	TOTAL			RS.	
D	FLOORING				
1	Providing and laying large format Vitrified tiles in given size (thickness 9mm) of approved make, in all colours & shade, gloss or satin matt in flooring,skirting, with layer of adhesive (latiocrete 335 Maxi)of required thickness over 15 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand) having gap of 4mm with help of pvc spacers and grouting the gap joint with epoxy (latiocrete SP 100 DUO) matching pigments etc. complete to the satisfaction of Architect/bank engineer. Dismantling existing flooring tiles including. Note:- Base cement motar 1:3 in level before tiles included.				
	Size of Tile 600x1200 mm (For Counter Area & Pantry Flooring) Basic Rate of Tile Rs. 60 Per Sqft.	Sq.m	239		
2	Granite in Flooring, Counters Tops, Risers & Treads : Providing and fixing 18mm thick gang saw cut mirror polished (pre moulded and pre polished) machine cut ' Tan Brown/ Black' Granite for Flooring, stairs & Toilet, kitchen platforms, vanity counters, window sills , risers and similar locations as per drawing of required size and of approved shade, color and texture laid over 20mm thick base cement mortar 1:4 (1 cement : 4 coarse sand) with joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edge to give high gloss finish etc. complete at all levels as per the directions of the Architect/ Bank's Engineer. Dismantling of existing flooring included. Basic Rate of Granite @ Rs. 150 per sq.ft	sq.mt	4		
	TOTAL			RS.	
E	FINISHING WORKS				

S.No.	Description of work	Unit	Qty	Rate (In Rs.)	Amount (In Rs.)
1	Providing Internal cement plaster 12mm/15mm thick of mix 1: 6 (1cement, 6 coarse sand) incl. curing for 7days etc. complete as per directions of Architect/ Bank's Engineer	Sq.m	75		
2	Painting of MS windows /grills with synthetic enamel paint of two or more coats on work over an under coat of suitable shade with ordinary paint of approved brand and manufacture of required color to give an even shade. Cleaning of widow glass panes both sides included in this item. Asian- Enamel paint in Black Color. complete to the satisfaction of Architect/ Bank's Engineer.				
	Old Work	Sq.mt	37		
	TOTAL			RS.	
F	MISCLLENOUS WORK				
1	Providing and fixing in position collapsible steel shutters with verticalchannels 20x10x2 mm and braced with flat iron diagonals 20x5 mm size, with top and bottom rail of T-iron 40x40x6 mm, with 40 mm diasteel pulleys, complete with bolts, nuts, locking arrangement, stoppers, handles, including applying a priming coat of approved steel primer	Sq.m	5.5		
2	Supplying and fixing rolling shutters of approved make, made of required size M.S. laths, interlocked together through their entire length and jointed together at the end by end locks, mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with push and pull operation complete, including the cost of providing and fixing necessary 27.5 cm long wire springs manufactured from high tensile steel wire of adequate strength conforming to IS: 4454 - part 1 and M.S. top cover of required thickness for rolling shutters.				
	80x1.20 mm M.S. laths with 1.20 mm thick top cover : Opening Size: 2.0x2.75M	Sq.m	7.9		
3	Providing and fixing ms channel 50x100mm in existing brick wall above door level as per drawing after cheese cutting manually from both side of brick work complete with fixing lifting transportation of all related items. The ms channel should rest on 75mm thick Cement concrete block (Mix 1:2:4). complete to the satisfaction of Architect/ Bank's Engineer.	Nos.	1		
	TOTAL			RS.	
G	SANITARY INSTALLATION				
1	Providing & Fixing Floor mounted S-trap WC & cistern in toilets with of specified make having connection to inlet pipe angle valve and floor drain PVC connection complete as per manufacturers specification and to be given in running condition. Note: Hindware WC -white, Aspiro S- trap Single body closet. Make:- Hindware or equivalent.	Nos.	2		
2	Providing & Fixing of Health Faucet ABS body with 1 meter long pvc tube & wall hook .Basic Cost Rs.800/-	Nos.	2		
3	Providing & fixing Long body Bibcock with flange cat. No. F730011 in bath with overhead shower cat. No. F160148 with arm with stop cock in wall for operating shower. Note: 3 items namely-wall tap,stop cock,shower. Make :- Hindware or equivalent.	Nos.	1		
4	Providing and fixing Mirror of superior glass of approved quality and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board backing. The mirror shall be ofrectangular shape and 450 x 600 mm size.	Nos.	2		

S.No.	Description of work	Unit	Qty	Rate (In Rs.)	Amount (In Rs.)
5	Providing and fixing Stainless Steel kitchen sink as per IS 13983 with C.I. brackets and stainless steel plug 40 mm including painting of fittings and brackets, cutting and making good the walls wherever required :Kitchen sink without drain board. 400x400 mm bowl depth 200mm with hindware contessa sink swivel tap wall mounted chrome.	Nos.	1		
6	Providing and fixing C.P. brass Towel Rail near washbasin & W.C.	Nos.	2		
7	Providing liquid soap dispensers in S/steel body 500 ml capacity fixed on wall near washbasin. Basic cost : Rs.800/-	Nos.	2		
	TOTAL			RS.	
	SUBTOTAL CIVIL WORKS RS.			RS.	
INTERIOR WORK					
1.0	PARTITIONS AND DOORS				
	Measurement of height shall be taken from finished floor level up to the level of false ceiling, in case of varying heights on either side of partition, average height shall considered. The rates include provision of extra frame work as necessary for skirting and making cutouts for electrical switch plates, switch boxes, light fittings light etc. making provision for laying conduits as per drawings & directions. All wood framework to be applied with 2 coats of fire retardant paint and 1 coat of wood preservative with anti termite treatment properties.				
a	Providing & fixing Solid Full Height Partition 75mm thick with 25x50mm aluminium sections (1.5mm thk.) of Indal or equivalent @ 600 mm c/c in both directions, (vertical member to be in one piece) 11mm thk. MDF board to be fixed on both sides and 1.0mm thick laminate pasted on both sides as per design & including provision of grooves as per drawing. Partition to have 100mm high band at skirting in laminate 1mm thick as per specified color/shade in level with partition on both sides of partition. Item includes fixed toughened glass in between as per drawing of 10mm thick fixed with steem beech wood beading on both sides out of size 40x12mm with required headless nails secured to partition frame finished in lacquer polish natural color on the wood surfaces and finishing of grooves with polish etc. as per detail drgs. Rest of specifications same as main specifications of partitions, complete to the satisfaction of the Architect / Bank's Engineer.	Sq.Mt.	38.00		
b	Providing and Fixing Partition For Server Room/UPS and Pantry, Same as above item no. 1 (a) but Providing 8mm thick Hilux board over aluminium framing with one side laminate & other side plastic paint of approved make & specifications etc complete to the satisfaction of Architect/ Bank's Engineer.	Sq.Mt.	37.50		
c	Providing & fixing 12mm thick clear toughend Fixed Glass for Cabins fixed in place in aluminium frame profile (black powder coated) section size 25 x 45mm having one side removable beading as per detail drgs. all four sides of frame to be fixed with screws in pvc gutty held in place to partition and flooring complete to the satisfaction of Architect/ Bank's Engineer.	Sq.Mt.	22.50		
d	Providing and fixing front Frameless Patch Fitting Door with 12mm thick toughened glass with frame less glass fittings & double action floor springs as per design. The item includes providing and fixing S.S. handle not less than 450mm long on both side of glass, center lock and fittings as per the manufacturer's specifications etc. complete to the satisfaction of Architect/ Bank's Engineer.				

S.No.	Description of work	Unit	Qty	Rate (In Rs.)	Amount (In Rs.)
	(a) Door Size:- 1100 x 2300 mm (Bank Entry)	Nos.	1.00		
	(b) Door Size: 1000 x 2300 mm (Branch Mgr.)	Nos.	1.00		
e	Providing & fixing Low Height Partition (SWO Counters) 75mm thick with same specifications as item no. 1(a) above but with 1.0mm thick hi-gloss (white) laminate fixed on both sides with wooden top (steem beech wood) of size 85x15mm thick having 12mm thick toughened glass in between as per design and drawing fixed in partition with steem beech wood beading on both sides secured by headless nails all wood finished in lacquer polish natural color as per design/ drawing, height of partition to be 1220mm high complete to the satisfaction of the Architect / Bank's Engineer.	Sq.Mt.	18.50		
f	Modifying existing Doors and Chaukhats , existing door to be removed and refixed after providing it with 1.0mm thk. decorative texture laminate. Item also includes polish on all wooden surfaces etc, complete to the satisfaction of Architect/Bank's Engineer. (Items Include both side of laminate. Measurement will be considered for one side)	Sq.Mt.	6.67		
	SUB TOTAL : 1.0 : PARTITIONS AND DOORS			RS.	
2.0	PANELLING				
a	Providing & fixing Panelling (Laminate) with frame work with 50 x 25 x 1.5mm aluminium tube sections @ 600 mm c/c in both directions, with 11mm thk.mdf board finished with 1.0mm thk. laminate in two or more colour, provision of extra frame work as necessary for skirting and making cutouts for electrical switch plates, switch boxes, light fittings light etc. making provision for laying conduits as per drawings & directions etc. complete to the satisfaction of the Architect /Bank's Engineer.	Sq.Mt.	128.00		
b	Providing & fixing Panelling on columns with lacquer glass same as item no 2 (a) with frame work having raised mdf panels 6mm thick pasted on base of panelling board in design pattern leaving space in between for 4mm thick lacquer glass pasted with silicone, all exposed surfaces finished with 1mm thick laminate. as per drawings & directions etc.complete to the satisfaction of Architect/Bank's Engineer.	Sq.Mt.	16.50		
c	Providing & fixing additional box panelling (around digital glass) finished in 1mm thick laminate as per drawing behind SWO counters as per design with specifications same as item 2(a) having depth 150 /180 mm as per design/details with extra frame work as necessary for making cutouts for electrical switch plates, switch boxes, light fittings light etc. making provision for laying conduits as per drawings & directions etc.complete to the satisfaction of Architect/Bank's Engineer.	Sq.Mt.	3.50		
d	Providing & fixing Digital printing glass 6mm thick as per design on wall panelling as per design, pasted with silicone on base. Digital glass shall be as per design theme which shall be specified and design shall be given by contractor before execution complete to the satisfaction of the Architect /Bank's Engineer.	Sq.Mt.	7.00		
	SUB TOTAL : 2.0 : PANELLING			RS.	
3.0	FALSE CEILING				

S.No.	Description of work	Unit	Qty	Rate (In Rs.)	Amount (In Rs.)
	Item includes providing False Ceiling in plane, curve shape and design .Suspending system and frame work shall match layout of A.C. ducts / grills, electrical /fire protection wiring / fixtures, return air grills etc. Rate to include provision of extra frame work for trap door , necessary scaffolding for double height needed due to layout of other utilities refered above and fixtures etc. Including finished with a top coat of paint. (Measurement shall be taken of the plan area only, coves to be paid separately)				
a	Providing and fixing Gypsum Board False Ceiling with INDIA GYPSUM ULTRA main g.i. ceiling sections at 1200 c/c and cross members at 450 c/c of INDIAN GYPSUM. The grid work to be suspended from ceiling with hangers at every 1200 c/c in both directions. The Frame work to be as per manufacturer's specifications. 12.5 mm thk. GYPBOARD to be screwd to the frame. The board to be finished with filling the tapered edges of the board with jointing compound and finishing with paper tape of INDIA GYPSUM. The ceiling to be finished with a top coat of paint as per manufacturer's specification along with provision of all necessary cut outs for electrical / air conditioning grills and necessary frame work including cove and curve designs etc. complete to the satisfaction of Architect/ Bank's Engineer.	Sq.Mt.	178.00		
b	Providing coves in false ceilings as per design/drawings of patta size 75/100mm high , 150mm deep with 12mm gypsum board on base(to keep LED light strip) and cove wall(vertical) again of gypsum board 100mm high. <i>(Item shall be painted in specified color and counted in running meter for measurement one time only.)</i>	R Mt	80.00		
c	Providing and fixing False Ceiling with Mineral Fibre Acoustic Ceiling Tiles Fine Fissured 600x600mm x15 mm (thk.) of Armstrong with MICROLOOK edges and having noise reduction properties laid on exposed grid system with 16mm wide Silhouette(black) type T-section flanges of white colour, main runners spaced at 1200 mm c/c securely fixed to the soffit of structure with approved hangers at 1200 mm maximum c/c. Flush fitting 1200 mm crossed tees to be interlocked between main runners at 600 mm c/c to form 1200 x 600 modules. 1200 mm cross tees to be crimped. 600 x 600 module to be formed by fixing 600 mm long flush fitting cross tees centrally between the 1200 cross tees. Rate to include making necessary cut-outs or openings for light fixtures, air conditioning grills/diffusers/speaker and other utilities etc. complete to the satisfaction of Architect/ Bank's Engineer.	Sq.Mt.	95.50		
d	Fabricating and fixing wooden false ceiling having base of 12mm thick commercial Ply fixed in position with G.I framing. Design of mdf panels 75mmx11mm thick each space at 12mm gap complete with 1mm thick laminate of specified color & shade as per drawing. complete to the satisfaction of Architect/ Bank's Engineer.	Sq.Mt.	14.50		
e	Fabricating & fixing in position Wooden False Ceiling with Laminate 1mm thick over 12mm thick Comm ply suspended & secured to G.I. frame of false ceiling at 400 x 400 c/c sections with hangers in both directions secured to rcc roof. Laminate pasting in design as per detail drawings.	Sq.Mt.	10.50		

S.No.	Description of work	Unit	Qty	Rate (In Rs.)	Amount (In Rs.)
f	Supply and fixing of false ceiling system (waiting area) with panel sizes of 300mm x 3850mm in Polymer based material with thermal printing as per desired color and shade selected by architect/bank's engineer. Panel Specifications: Panel Sizes: 300mm x 3850mm Characteristics: Durable, moisture-resistant, water-resistant, and resistant to borer-fungus-termite attacks. Installation Requirements: Panels to be installed using GI sections (0.55mm / 0.8mm thick) Gauge and size of sections : 1. Perimeter channel for Fixing J trim 1.5" parameter 2. Furring Channel for Fixing Soffit. Fixed perpendicular to soffit panels every 450mm 3. Main Channel for Beam support. Fixed every 1000mm 4. Wall angle / channel for frame weight bearing Fixed ceiling to frame every 1000mm 5. Self Tapping screw - Philip pan head screw – 1" for GI channels	Sq.Mt.	9.00		
	Accessories SV 15 with dimensions 40x19x22x12x3050 (all in mm) for edge profiles SV 18 with dimensions 67x3050 mm with T head of 42mm for Connecting profiles.				
	Ceiling panels (wooden printed) make: Vox / Soulwood / Euro Pratik.				
	SUB TOTAL : 3.0 : FALSE CEILING			RS.	
4.0	COUNTER/ TABLES/ WORKSTATIONS				
	All Tables/ Counters/Work stations to have 18mm thk. BWR ply top and sides and 1.0 mm thk. laminate (Decorative/Texture/Metallic/High Gloss) finish on exposed surfaces along with 0.8 mm thk. white laminate on inside surface, drawer units to be made from 12 mm thk. BWR ply with 18mm thk. BWR ply FASCIA with 1.0 mm thk. laminate finish (as per individual item). The drawers to run on telescopic drawer channels. Drawer units shall have two smaller and one bigger drawer and auto locking arrangement as per specified hardware in make of materials. Footrest 75x50mm made of 2nd class teakwood member to be fixed in each table. The rate shall include providing all hardware such as drawer channels, S.S. handles, lock, aluminium cable manager flap type 80x160mm etc. complete. The item also includes a tray for keyboard running on telescopic channel, finished with laminate on top and rounded front of size 560x450mm, wooden platforms finished in laminate 1mm thick for CPU under tables etc. complete to the satisfaction of Architect/ Bank's Engineer.				
a	Providing and placing Branch Manager Table made of 12mm thk. BWR ply finished with approved 6mm thk. white solid acrylic surface on top & side edges on table and sides made with 19mm thk. commercial ply finished with 1.0mm thk. high gloss decorative laminate. Modesty panel to be made of 12mm thk. frosted toughened glass. Table top edges to be approx. 50mm thk. with solid acrylic surface finish as per design & details. Rest of the specifications for drawer units etc. shall be as per main specifications mentioned above etc. complete as per design/ drawing. The table size shall be 1950mm x 800 x 760(H)mm.	Nos.	1.00		
b	Providing and placing in position Officer Table made of 18mm thk. commercial ply top and sides finished with 1.0mm thk. laminate. Front modesty panel to be as per given design/ drawings made of 18mm thk. commercial ply finished with 1.0mm thk. laminate. Rest of the specifications for drawer units etc. shall be as per main specifications mentioned above etc. complete as per design/ drawing.				
	1600x760x760 (H)mm.	Nos.	3.00		

S.No.	Description of work	Unit	Qty	Rate (In Rs.)	Amount (In Rs.)
c	Providing and fixing Side Table of Officer Tables made of 18mm thick commercial ply and finished with laminate 1mm thick as per color & shade. The side table to have shuttered storage below with one shelf. The inside of side table to be finished with 0.8mm thk. white laminate. The rate shall include providing all hardware such as auto hinges, S.S. handles and locks etc. complete as per design/drawing. The side table size shall be 1000x450x760(H)mm.	Nos.	4.00		
d	Providing and placing in position Workstation Table (without drawer unit) made of 18mm thk. commercial ply top and sides finished with 1.0mm thk. laminate. Front modesty panel to be as per given design/ drawings made of 18mm thk. commercial ply finished with 1.0mm thk laminate. Rest of the specifications shall be as per main specifications mentioned above etc. complete as per design/drawing.	Rmt.	6.50		
e	Providing and placing in position Banking Counters in straight/curved shapes 750 mm high made of 18 mm thk. exterior grade ply duly rounded with 6mm thk. flexi ply covering in 750mm wide working top, finished with 6mm thk. high density white solid acrylic surface on top & side edges as per specified make in curved shape and rest of the structure made from 19mm thk. BWR ply finished with 1.0 mm thk. high gloss laminate in frosty white color ,design as per SBI specified standards, rest of the specifications for drawer units etc. shall be as per main specifications mentioned above but with divisions for currency as per Bank's instructions. The drawer units shall be provided with autolocking system for drawers etc. complete as per design/ drawing. (Measurement will be taken from top plan).	R.Mt.	8.40		
f	Providing and fixing Side Rack or Back Storage Unit for Banking Counters & Branch Mgr. Cabin made of 18 mm thk. BWR ply board having 450mm wide top provided with 6mm thk. high density corian solid acrylic surface on top & side edges as per specified make and sides with shutters design as per drawing/detail finished with 1mm thk. laminate in specified color & shade. The side table to have shuttered storage below with one shelf. The inside of side table to be finished with 0.8mm thk. white laminate. The rate shall include providing all hardware such as auto hinges, S.S. handles and auto locking locks for drawers etc. complete as per design/drawing.	Sq Mt	15.0		
g	Providing and fixing Writing Desk Cabinet made of 18mm thk. BWR ply finished with 1mm thk. laminate and having shelves for keeping Bank slips, and storage below with shutters as per the design/ drawing etc. complete to the satisfaction of Architect/Bank's Engineer. (Size of the writing desk shall be 1200mmx300x1100mm.)	Sq Mt	1.00		
h	Providing and fixing 12mm thk. Toughened Glass in front portion of single window counters with s/s brackets including cutouts for passing currency and communication as per drawing. The edges of the glass to be machine polished complete to the satisfaction of Architect/ Bank's Engineer.	Sq.Mt.	12.00		
SUB TOTAL : 4.0 : COUNTER/TABLES/WORKSTATIONS				RS.	
5.0	STORAGE CUPBOARDS				

S.No.	Description of work	Unit	Qty	Rate (In Rs.)	Amount (In Rs.)
a	Providing & fixing Low Height Box Storage cabinet 450mm deep of height 900/760mm height as per drawing/design , shelves to be made with 18 mm thk. BWR ply and 6mm thk. BWR ply fixed at the back. The shutters to be made with 18mm thk. BWR ply without handles as per design overlapping the frame, finished with 1.0 mm thk. laminate on all exposed surfaces & 0.8mm laminate on inside surface of box cabinet. Cabinet top edge made of 36mm thick as per drawing finished with 2mm thk. edge binding tapes , all shutters to have 1mm thk. edge binding tapes(rehau) as per details including S.S. handles, self closing hinges, locks, etc. complete to the satisfaction of Architect / Bank's Engineer. (Only front elevation will be considered for area calculation)	Sq.Mt.	8.50		
	SUB TOTAL : 5.0 : STORAGE CUPBOARDS			RS.	
6.0	MISCELLANEOUS				
a	Providing & applying the walls, ceiling and elsewhere with Plastic Emulsion Paint (roller finish) after preparing the base by applying 2 coats of birla white putty for making the surface plane & smooth and then applying 2 or more coats of plastic emulsion paint with final coat done with rollers as per manufacturer's specifications etc. complete to the satisfaction of Architect/Bank's Engineer. (Removal of existing paint incuded)	Sq.Mt	340.00		
b	Providing & applying Texture Paint (Berger/ Dulux/ Asian) in two or more shades as approved by Bank with roller & spray, after preparing the base for the same as per manufacturer's specifications etc. complete to the satisfaction of Architect/Bank's Engineer.	Sq.Mt	47.00		
c	Providing and applying approx. 12mm thk. POP Punning on walls , ceiling and elsewhere to give a clean smooth and plumb surface as per the instructions of Architect/Bank's Engineer.	Sq.Mt	47.00		
d	Providing and fixing panelling on wall in position with Aluminium Composite Paneling (ACP) for Cladding with framing of aluminium tube section of min. 50mmx25mm and 20 gauge at a spacing of 600mm center to center both ways. ACP to be of approved shade in 600mm wide panels or distributed equally. ACP sheets to be fixed to the frame with 3M make adhesive along with mirror screws. ACP sheets (Alubond/ Alstone/ Alcobond) to be min. 3mm thick with aluminum foil thickness to be min. 0.25mm on both sides. Item includes providing additional sections to fix indoor AC units which will be installed at the highest position etc. complete as per instructions of Architect/ Bank's Engineer. Item includes scaffolding as may be required etc. complete as per site conditions.	Sq.Mt	20.00		
e	SHUTTER BOXING - Providing & fixing in position Aluminium Composite Panel (ACP) with framing of Aluminium Tube sections of min 2" * 1" and 20 gauge 2'-0" C/C both ways. Mirror screws to be used. Joints to be finished with Silicon based sealant. ACP thickness of 3mm minimum. Aluminium foil thickness to be min 0.25 mm., 2'-0" C/C both ways. ACP to be in 2' width panels or distributed equally. ACP thickness of 3mm minimum. (Alubond/ Alstone/ Alcobond) or equivalent ISI approved brands to be used. Shades to be as per bank's approval. Trap door will be 12 mm marine ply finished with ACP, complete as per instructions of Architect/ Bank's Engineer. Item includes scaffolding as may be required etc. complete as per site conditions. (Only front facia to be measured for payment.)	Sq.Mt	3.50		

S.No.	Description of work	Unit	Qty	Rate (In Rs.)	Amount (In Rs.)
f	Providing and fixing Louvered Shutter Cabinet Box for main Electrical panel fabricated out of 19 mm thick Bwr block board and finished with 1 mm thick laminate on outside & 0.8mm laminate on inside of approved make, having aluminium louvers in powder coated white finish. Coating of fire retardent and anti-termite paint inside. complete as per instructions of Architect/ Bank's Engineer.	Sq.Mt	4.50		
g	Providing & fixing in position 4mm thick Lacquered glass (Blue) on facia of SWO counters duly fixed with adhesive/ s/s screw wherever required in desired pattern etc. complete as per instructions of Architect/ Bank's Engineer.	Sq.Mt	5.00		
h	Providing & fixing on fixed glass Frosting film 3M wherever required as per design & drawing in desired pattern etc. complete as per instructions of Architect/ Bank's Engineer.	Sq.Mt	6.50		
i	Providing and fixing wooden wicket gates of apprx. Size 800mm X 1220 mm made of 36 mm thk. BWR block board & both sides laminate 1mm thick of approved make and color complete with godrej premium night latch lock hinges etc. complete as per instructions of Architect/ Bank's Engineer.	No.	1.00		
j	Providing and fixing of pelmets L- shape near glass windows as per drawing made up of 36mm comm. Ply having the two dimentions 200mm each or more finished in laminate 1mm thick of desired color on exposed surface and 0.8mm white color on inside surface with teak margin 6mm thick on edge polished in natual color.	R.Mt.	13.50		
k	Providing and fixing Roller Blinds (Vista Levelor/ MAC/ DACK) of approved shade, texture and fabric including all associated accesories etc. complete to the satisfaction of Architect/Bank's Engineer. Base rate: Rs. Xxx per sq ft	Sq.Mt	20		
l	Providing and fixing of wooden planter boxes made up of 18mmthick ply on four sides with base as per design and drawing laminated with desired color of laminate 1mm thick on both sides. Lipping on edges with teak wood 6mm thick margin polished in melamine natural color complete to the satisfaction of Architect/Bank's Engineer.				
	Size : 500 x500x450mm	Nos	3.00		
m	Disposal of rubbish/ mulba after dismantling/ demolition including clearing building waste of all types, rank vegetation etc. all complete as per the directions of Bank's Engineer/ Architect.	No.	1.00		
	Note:- Bank shall not pay any extra cost charges to vendor for the dismanting of existing partition, furniture ,false ceiling, floor tiles, panelling/wall cladding, glass, windows, grills etc. This is a running branch for which vendor has to put temporary partition for smooth working of branch & customers at no extra cost. All New work wherever Scaffolding is required shall be arranged by Vendor at no extra cost.				
	SUB TOTAL : 6.0 : MISCELLANEOUS			RS.	
	SUBTOTAL INTERIOR WORKS RS.			RS.	
	SUBTOTAL CIVIL WORKS + INTERIOR WORKS RS.			RS.	

S.No.	Description of work	Unit	Qty	Rate (In Rs.)	Amount (In Rs.)
SALVAGE ITEMS					
	Salvage Items (Interior)				
1	Dismantling and removal (loading/ unloading, transportation etc. complete) of existing items from existing premises:-				
	Note: The Contractor may verify quantities and sizes at site.				
a	SWO Running Counter top /Table				
(i)	(Approx. size 29'-0"x2'-0" x 2'-6" Ht)	Rft	29		
(ii)	(Approx. size 9'-9" x 2'-0" x 2'-6" Ht)	Rft	9		
b	Branch Mgr.Table (Approx. size 6'-0" x 2'-6" x 2'-6" Ht)	Nos.	1		
c	Branch Mgr.Side Rack (Approx. size 3'-0" x 1'-4" x 2'-6" Ht)	Nos.	2		
d	Officer Table (Approx. size 5'-0" x 2'-6" x 2'-6" Ht)	Nos.	5		
e	Officer Table Steel Base (Approx. size 5'-0" x 2'-0" x 2'-6" Ht)	Nos.	6		
f	Running Counter Table	Rft	19.5		
g	Side Rack (Approx. size 2'-6" x 1'-4" x 2'-6" Ht)	Nos.	4		
2	Aluminium Partition & Door With Glass	Sqft.	650		
	Dismantling and removal (loading/ unloading, transportation etc. complete) of existing items from existing Bank's premises: For Salvage of above mentioned items the minimum Reserved Price shall be Rs. 34840/-				
	TOTAL SALVAGE			Rs.	
	TOTAL AMOUNTS AFTER LESS SALVAGE ITEMS (CIVIL+ INTERIOR WORKS)			RS.	
Note:- 1. The rates quoted includes all other taxes, duties, loading, unloading, transportation, other expenses etc to site. only GST will be paid Extra.					