



**SBI INFRA MANAGEMENT SOLUTIONS PVT.LTD.**

**CIRCLE OFFICE, THIRD FLOOR, STATE BANK OF INDIA, SYNERGY BUILDING, C-6, G-BLOCK, BANDRA KURLA COMPLEX, BANDRA EAST, MUMBAI-400051**

**PART – B: FINANCIAL BID**

<b>TENDER ID MUM201908001</b>
<b>DATE: 05.08.2019</b>

**TENDER FOR:**

**INTERIOR AND FURNITURE WORK FOR GOREGAON DIST. GONDIA BRANCH**

**TENDER SUBMITTED BY:**

**NAME :** \_\_\_\_\_

**ADDRESS :** \_\_\_\_\_

**DATE :** \_\_\_\_\_

**TENDER INVITED BY:**

**Vice President & Circle Head,**

**SBI Infra Management Solutions Pvt. Ltd; 3<sup>rd</sup> floor, Circle Office, State Bank of India, Synergy building, C-6, G-Block, Bandra -Kurla complex, Bandra East, Mumbai-400051.**

S.NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
1	<b>False Ceiling:</b> Providing & fixing in position 12 mm thick gypsum board false ceiling fixed with 16 gauge galvanized frame supported from and fixed to RCC slab with Anchor bolts. The ceiling should contain approx. 40 % of the ceiling area of 12mm thick Mineral Fibre ceiling Board of Armstrong or equivalent approved make with framework, runners, cross runners & suspenders from the existing ceiling as per the manufacturers details and specification and 600X 600mmX 15mm thick mineral fibre ceiling ( 600*600 mm ) - beuti sky or other approved pattern and stepping. All the joints to be properly sealed with jointing tape and finished with approved jointing material. The item includes making cut-outs and providing necessary frame work for light fitting, grill diffusers and ducts etc. which have to be made with frame of perimeter channels of size 20mm x 30mm x 0.55mm. thick supported suitably and angle bead is to be used at steps to get straight line finish etc. complete. The item rate shall also include preparation of surface with sanding, and 3 coats of Acrylic Emulsion paint in approved shade over a coat of primer / putty including necessary work etc. complete as per Bank Engineer's instruction.	220	Sq M		
2	<b>Single window counter :</b> Providing & fixing in position single window counter as per design, made of 18 mm / 19mm thick MR grade ply structure and laminated glass in approved shade, and front side teak wood moulding patti duly finished with three coats of P.U. finish, All exposed external surface finished with 1 mm laminate and internal surfaces finished with 0.8 mm laminate of approved shade and make with foot rest of 75 x 38 mm CPTW with 12mm thick plain glass of 150 mm deep of counter length at Service top adjacent to the top with 12mm thick and 380 mm height etching glass at front including making half round opening of 150 mm dia duly finished with crystal polish and providing granite platform of width 150 mm at front side and having CPU stand of 19mm thick MR grade ply including cable manager, a key board tray with telescopic arrangement.	4.5	Rmt		
3	Providing and fixing factory made <b>solid core flush door</b> in single leaf 30 mm thick, finished with approved 1mm th. Laminate on both faces with / without glazing and venetians in the positions shown on the drawings or as directed, all necessary beads, moulding and lapping, Stainless Steel fixtures and fastenings with CP / brass mortise lock, Stainless Steel handles on both sides, stoppers and exposed woodwork finished with French-polish complete. (Without door frame).	5	Sqm		
4	<b>Low / medium height partition:</b> Providing and fixing in position low / medium height partition made of 50 x 50 x 1.2mm medium duty aluminium hollow square pipes framed at 0.6 m to 0.45 m c/c both ways covered with 6 mm MR grade ply and 1mm thick laminate of approved shade & make, both sides including necessary opening / outing for receiving cheques & other papers, and to receive 10 mm th. Float glass including all necessary opening for electric / telephonic conduits etc. as per requirement. (Glass area in the partitions will be deducted in the measurements of partition).	25	Sqm		

S.NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
5	<b>Glass partition:</b> Providing and fixing 10 mm thick glass with etching as per design for low height partitions held with SS clits (D brackets). All exposed glass edges with rounded moulding and crystal polish. All exposed woodwork to be finished in 3 coats of French polish/ melamine polish.	8	Sqm		
6	<b>Providing and fixing fixed glazing</b> which consists powder coated approved make heavy duty 14 gauge 100 mm x 50 mm aluminium jumbo sections for top and bottom rail to hold 12 mm thick toughened glass of approved branch with edges machine polished. Providing etching to glass, locking system ( Godrej/Dorma/Ozone or approved make ultra mortise dead lock) along with pair of S S Handles, gaskets and other miscellaneous hardware etc complete.	10	Sqm		
7	<b>Main entrance door :</b> Providing and fixing fully glazed Main door which consists powder coated approved make heavy duty-14 gauge 100 mm x 50 mm aluminium jumbo sections for top and bottom rail to hold 12 mm thick toughened glass of approved branch with edges machine polished. Providing etching to glass, locking system (Godrej/Dorma/Ozone or approved make ultra mortise dead lock) along with pair of S S Handles, gaskets and other miscellaneous hardware etc complete.	10	Sqm		
8	Providing & fixing in position floor spring for receiving glass door of approved make. (DORMA / HETTICH or equivalent)	2	No.		
9	Providing and fixing in position door closer of approved make (Hyper / Godrej or equivalent).	4	No		
10	<b>Tables :</b> Providing & fixing in position tables made of 19mm MR grade Ply at top, side and front, support along with drawer unit & Key board tray with telescopic arrangement & CPU base resting on foot rest of teak wood member of 75 x 40 mm. 19mm th MR grade ply modesty panel. All external surfaces to be finished with 1 mm thick laminate and internal surface finished with 0.8 mm of approved shade and make. Including powder coated fittings like sliding channels, for key board & drawers, medium duty hinges for shutter, cable manager. S.S. handles in approved design and size and locks wherever directed in approved make. All exposed plywood edges to be finished with 6mm th. Teak wood beading with French polish in approved shade and necessary locks to shutters etc. complete in all respects.				
a	Branch Manager - 1.80 x 0.90 x 0.75	1	No.		

S.NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
b	Officer's Tables - 1.50 x 0.70 x 0.75	3	No.		
c	Staff Table - 1.20* .70* .75	1	No.		
d	Grahak Mitra table 1.2* .70* .75	1	No.		
11	<b>Low height &amp; Full height storage:</b> Providing & fixing in position 400mm deep low/full height storage made of 18/19mm MR grade ply at top, front and side with 12 mm MR grade ply at back, all external faces including back to be finished with 1 mm thick multi-colour laminate at outside and inside finished with 0.8 mm laminate with locking and SS handle arrangement of approved make complete with openable type shutter, beading patti etc. All exposed plywood edges to be finished with 6mm th. Teak wood beading with French polish in approved shade complete in all respect.	20	Sqm		
12	<b>Full height glazed/Partly glazed / partly panelled partition :</b> Providing and fixing in position partly glazed & partly panelled partition made of 50 mm x 50mm x 1.2mm medium duty aluminium hollow square pipes framed at 0.60 m. to 0.45 m c/c both ways covered with 6 mm MR grade ply and 1mm multi-colour laminate of approved shade and make with 6 mm thick glass panel with etching as per design and / or necessary beading patti including 3 coats of french polishing including door shutters as per architectural design with heavy duty hinges handles / handles / locks etc. of approved make.	30	Sqm		
13	Providing and fixing side table made of 18/19 mm thick ply for all top, support and side with 6 mm thick ply at back externally finished with 1.0 mm thick laminate and internal surface painted with three coats of synthetic enamel paint over a single coat of primer , both of approved make including brush finish S S handles, shutters , hinges with necessary teak wood beading including three coats of french polish to teak wood member and necessary locks to shutters etc. all required surface				
a	Size 1.05*0.4*0.75 m	1	No		
b	Size 0.9*0.4*0.75 m	2	No		

S.NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
14	<b>Full height panelled partition for server room:</b> Providing and fixing in position partly glazed & partly panelled partition made of 50 mm x 50mm x 1.2mm medium duty aluminium hollow square pipes framed at 0.60 m. to 0.45 m c/c both ways covered with 6 mm MR grade ply and 3mm aluminium composite panel of approved shade necessary beading patti including 3 coats of french polishing including door shutters as per architectural design with heavy duty hinges handles / handles / locks etc. of approved make.	5	Sq m		
15	<b>Cheque Writing desk :</b> Providing & fixing writing desk out of 19mm th.MR grade ply & 1 mm th. Laminate complete. Size 3'-0" x 1'-6"	2	No		
16	<b>Notice board:</b> Providing & fixing notice board with approved upholstery. Size 3'-0" x 1'-6"	2	No		
18	<b>Vertical blinds :</b> Providing & fixing in position 3" / 4" wide vertical blinds of approved make (Vista / Aerolux) and shade with all accessories and necessary fittings etc.	15	Sq M		
19	Providing and fixing counter type desk made of 18/19 mm thick ply for top , sides, with a cabinet with a drawer & shutter finished with 1 mm thick laminate to outer facae and synthetic enamel paint inside, as per specifications including provision for CPU base and footrest	1.2	Rmt		
20	Providing Chairs of approved quality and make				
a	BM Chair ( basic cost Rs. 5000 )	1	No		
b	Staff chair ( basic cost Rs. 3500)	8	No		
d	Visitor chair ( basic cost Rs. 3000)	10	No		
21	Providing & fixing Panelling in out of 12 mm thick ply and 1.0 mm thick laminate with aluminium frame 50mmx25mmx1.2 mm in walls with screws and finished with approved shade and make to column with accessories and as per Bank engineer's instructions etc. complete	20	sq m		

S.NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
22	Providing and fixing M S Self locking drawer of size 400*700*740 mm with tw self locking drawers etc complete as per specifications.	3	No		
23	Providing and fixing panelling on External walls and for External Rolling Shutters boxing. Framing shall consist of Both ways horizontally and vertically on the wall/column with Aluminium Sections of 50mmx25mmx1.2mm as directed by Bank /Architect. This framing would be covered with 6mm thk. Comm. Ply (In case of wooden frames), finished with 3mm thick exterior grade multi-coloured "Aluminium Composite Panel". The rate shall be inclusive of necessary scaffolding, cut-outs, fixtures and fittings, sealant etc. complete.	20	Sqm		
24	Providing and fixing frosted film of 3 M/ LG make of approved design pattern, shade and colour to glass panels.	5	Sqm		
25	Providing and applying acrylic emulsion paint of approved quality, shade and colour in 2 or more coats to achieve desired result including applying one coat of primer of cement paint, preparing the surface by cleaning the dust/dirt by watering/brushing the surfaces, filling in cracks/crevices ,scaffolding at all levels, necessary lead, lifts etc. complete	25	sq m		
26	Providing and Laying vitrified tiles of approved make and quality of required size for flooring and skirting in required position laid on bed of C.M.1:4 including cement float, filling joint with white / colour cement slurry, cleaning, curing, complete. 600 mm x 600 mm. size (Basic rate = Rs. 70/- per Sqft) The item rate shall be inclusive of removing the existing flooring & skirting.( for repair purpose )	5	sq m		

S.NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
	<b>S U M M A R Y :</b>				
	Total of Interior Work	Rs.			
	Less discount (if any)	Rs.			
	Total cost of work Tendered	Rs.			
	Add SGST @ 9%	Rs.			
	Add CGST @ 9%	Rs.			
	FINAL AMOUNT INCLUDING GST	Rs.			

Total Amount

Rupees in words: \_\_\_\_\_

\_\_\_\_\_  
Signature & Seal of Contractor

Date: \_\_\_\_\_