

**TENDER ID BHO201906092**  
**TENDER FOR INTERIOR AND FURNISHING WORKS AT CHIRIMIRI BRANCH, REGION-IV, AMBIKAPUR,**  
**BILASPUR MODULE**

SL.NO.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	<b>Gypsum Board Ceiling:</b> Providing, fabrication and fixing in position of false ceiling at a height of 10'-0" from floor or the height will be decided on the spot as per site conditions) by fixing 12 mm Th. Gypsum Board Sheets on frame work of GI sheet section. The main runners of 22 gauge GI sheet must be cross runners of 24 gauge GI sheet must be framed to form a mesh of 2'0"x2'0" c/c. The Gypsum Board must be fixed to the GI frame and joint to be properly filled in with POP paste and paper tape to get a leveled smooth ceiling. Recessing of the Gypsum Board for light fixtures must be done along with extra frame work of GI sheet section to hold the concealed light fixtures. Cost includes finishing of board joint and surface with plaster of paris including sand papering, painting etc. complete. (Only on areas as per direction)	Sqm	110.00		
2	<b>Fiber Board Ceiling:</b> Providing, fabricating and fixing of false ceiling at all height of 600 mmx600 mmx12 mm Armstrong / Everest mineral fiber ceiling tiles of type BIZA RH-90 laid on Armstrong / Everest prelude XL exposed grid system with 9 mm wide T section flanges color white. the framework comprises of main runner spaced at 1200 mm center. Hanger (GI wire) to be fixed by approved roof plug and screws etc. The last hanger at the end of each main runner should not be greater than 450 from the adjacent wall. Flush fitting 1200 mm long cross tees (with double stitching) to be interlocked between main runner at 60 mm center from 1200x600 mm modules. Cut cross tees longer than 600mm to be supported independently 600mmx600mm modules to be formed by fitting 600mm long flush fitting cross tees centrally between the 1200 mm cross tees. Perimeter trim to be Armstrong/Everest wall angle secured to walls at 450 mm maximum centers.	Sqm	129.00		
3	<b>Vitrified tile flooring:</b> Providing and fixing (600mm x 600mm) size Vitrified floor tiles, 10mm thick (or as specified by the manufacturer from <b>(Naveen / Johnson/ Kajaria)</b> , premium quality confirming to IS:15622 with (vains/shades), as per sample approved by the Bank in adhesive specially manufactured for this purpose by standard companies like Dr. Fixit/Sika/ Pidilite etc. including grouting the joints with white cement and matching pigments, chipping of existing floor surface, complete item of job. Area includes 15 mm high skirting on walls as per directions.	Sqm	273.00		
4	Providing a layer of wall putty (Birla or JK) after scrapping of existing wall surface. Cost includes sand papering finished item of job. (On specific areas as per directions/drawing (On specific areas as per directions/drawing (except Record room & strong room)	Sqm	243.00		
5	Providing a coat of primer (Asian/ Berger/ICI) on interior wall surfaces of Banking hall and certain areas/ Rooms as per drawing / direction including cost of labour materials complete. (On specific areas as per directions/drawing (except Record room & strong room)	Sqm	243.00		
6	<b>Painting</b> Finishing of walls with plastic/OBD/ACE/Enamel paint of Asian/ Nerolac/ Berger/ ICI to give an even shade three or more coats including putty and finishing the wall surface smooth.				
	(a) Oil Bound Distemper	Sqm	260.00		
	(b) Enamel Paint	Sqm	60.00		

7	Dismantling of existing aluminum / wooden partitions of the Branch	LS	1.00		
	<b>FURNITURE WORKS</b>				
8	<b>SINGLE WINDOW COUNTERS</b> : Providing, fabricating and fixing at site and in position modern Clerical/Cashiers Counters with side rack as per detailed drawing consisting of 18 mm thick GREEN, REGAL, LIBERTY or equivalent approved make commercial finished borer and termite resistant block board. The transaction top and vertical panel shall be made with 12 mm thick glass of approved make. The work top shall be supported by the drawer Unit of standard size housing 3 nos. 7" deep drawers. the drawers shall be made with 12 mm and 6 mm ply board. Each counters shall be made 4'-3" to 5'0" long or as directed at site as per site conditions and approved layout plan. All the exposed surfaces of the counters shall be finished with 1 mm thick laminates of Sunmica or equivalent approved make. The inside surfaces shall be finished with 0.8 mm thick skin laminates. The rate should include providing and fixing approved quality 3 nos. handles/knobs approved design and 3 nos. GODREJ cupboard locks. The rate should also include providing and fixing CPU compartment, Key Board drawers, cable manager fixed on approved channels and electrical switch board plate complete as per directed.	Rm	6.70		
9	<b>FULL HEIGHT PARTITION</b> : Providing, fabrication and fixing of flush type partition made of kassi wood framework, 9 mm thk plywood and 5.5 mm thick plane glass. The horizontal and vertical section (2"x2.5" of kassi wood must be framed to from a mesh of 2'0"x2'0" c/c and 9 mm thick plywood to be fixed on both sides of the framed grid. The glass must be held in position properly in line and level. The exposed surface of ply must be covered with 1.0 mm thick laminate of approved brand and shade of Sunmica or equivalent.	Sqm	73.60		
10	<b>LOW HEIGHT PARTITION</b> : Providing, fabrication and fixing of flush type partition of height 1.2m made of kassi wood framework, 9 mm thk plywood and 5.5 mm thick plane glass. The horizontal and vertical section (2"x2.5" of kassi wood must be framed to from a mesh of 2'0"x2'0" c/c and 9 mm thick plywood to be fixed on both sides of the framed grid. 10 mm thick 1'9" high glass (having its top edge machine polished), in harmony with the glass to be fixed above partition. The glass must be held in position with SS brackets. The exposed surface of ply must be covered with 1.0 mm thick laminate of approved brand and shade of Sunmica or equivalent.	Sqm	29.74		
11	<b>LOW HT. CABINET</b> : Providing and fabrication of 2'6" high and 1'6" wide file/storage cabinet with cabinet body of 18mm and back 6mm thick plywood. The shutter of the cabinet must be of 18mm block board and overlapping the cabinet to be fixed with EBCO hinges. All the external exposed surfaces of the cabinet must be covered with 1mm thick laminate of approved brand and shade of Formica or equivalent. All the internal / hidden surfaces to be laminated with 0.6 mm thick backer lamination. All the edges and corners of plywood to be protected with 6mm thick plain teak wood beading. Multipurpose lock and handle to be fixed shutters.	Sqm	7.52		

12	<b>TABLES :</b> Providing and fabrication of table with body of 18mm thick ply. The drawer shall be made with 12mm and drawer bottom and back with 6 mm thick plywood. A ready-made metallic keyboard tray EBCO make must be fixed under table top. The table top and all other exposed surfaces to be covered with 1.0mm thick laminate of approved brand and shade. All inside/hidden surfaces to be laminated with skin laminates. All the exposed edges and corners of plywood to be protected with 6mm thick plain teak wood bead. All the exposed surface to be finished with 0.6 mm thick backer laminates. Multipurpose lock must be fixed on shutters and drawers.				
13	a. 6'0"x2'6"x2'6"	No	1.00		
	b. 5'0"x2'6"x2'6"	No	4.00		
	c. 4'6"x2'6"x2'6"	No	0.00		
14	<b>Continuous table</b> (system room table) 2'6" wide and drawer unit at every 4'0" c/c in right side.	Rm	2.00		
15	<b>SIDE CREDENZA</b> Providing and fabrication of 2'6" high and 1'3" wide side cabinet with cabinet body of 18mm and back 6 mm plywood. The drawer shall be made with 12mm & 6mm thick plywood. The door of cabinet to be fixed with EBCO hinges. Drawer shall be made from 12mm and back shall be made from 6mm ply. All the external exposed surfaces of the cabinet must be covered with 1mm thick laminate of approved brand and shade of Formica or equivalent. All the internal / hidden surfaces to be finished with 0.6 mm thick backer lamination. All the edges/ corners of the plywood must be protected with 6mm thick plain teak wood. Multipurpose lock and handle to be fixed to shutters and drawers. (Size 3'-3"x 1'-3"x2'-6")	No	5.00		
16	<b>PANELLING OF WALL COLOUMN</b> Providing, fabrication and fixing of 12 mm thick plywood around the columns as per the drawing wooden plugs of teak wood to be nailed at 3'0"x2'0" c/c and all the plugs to be cut after leveling them with line - dory along the diagonals of the wall, such that the gap between the wall and the ply board is by screwing on the leveled plugs such that the final surface of the ply is smooth and in uniform level. The entire exposed ply to be covered with 1mm thick laminate 4" high skirting of 12 mm thick plywood to be fixed on exposed surfaces and it to be edge of the board to be protected with bead of teak wood.	Sqm	54.00		
17	<b>Main Entrance Glazed Door:</b> Providing and fixing 12 mm thick glass or 32mm thick partly glazed wooden door with all fittings of approved make like hinges, handles with lock, tower bolts, stoppers, etc. complete in all respects as per directions. Essential etching on glass with sbi emblem included in the rate.	Sqm	5.00		
18	<b>Cabin Door:</b> Providing and fixing 30mm thick wooden door with all fittings of approved make like hinges, handles with lock, tower bolts, stoppers, etc. complete in all respects as per directions. Cost includes frame preparation on partition. No extra cost will be paid for frame	Sqm	3.45		
19	<b>HYDRAULIC DOOR CLOSER :</b> Providing & fixing Hydraulic door closer (heavy duty) ISI make of Hyper/ Hardwin/ Everite make.	No	4.00		
20	<b>FLOOR SPRING</b> Providing & fixing floor spring (heavy duty) ISI make of Hyper/Hardwin/ Everite make.	No	2.00		

21	<b>CUSTOMER WRITING TOP WITH DUST BIN</b> Providing and fabrication of 3'6" having 2'0" x 1'6" customer writing top pigeon holes for keeping blank draft/voucher forms. The lower dust bin portion shall be 1'6" x 1'0" with single shutter and bolting arrangement for opening the dust bin. The cabinet body shall be made with 18mm and back 6 mm plywood. All the external exposed surfaces of the cabinet must be covered with 1mm thick laminate of approved brand and shade of Formica or equivalent. All the internal / hidden surfaces to be finished with 0.6 mm thick backer lamination. All the edges/ corners of the plywood must be protected with 6mm thick plain teak wood. Multipurpose lock and handle to be fixed to shutters.	Nos.	1.00		
22	<b>ALUMINIUM PARTITION/DOOR</b> Providing and fixing Aluminium Partitions in aluminum sections to be made from INDAL / ZINDAL all complete including glazing beads, gaskets with suitable heavy sections with 5mm thick clear float glass as per design and specifications, all complete with all approved quality of hardware including locks, floor springs, handles etc. as per instruction of the Bank. Section to be used : Top Bottom, side - 9223, Centre 922 (Fix Glaze Area) in doors - Top & Bottom 9206, centre 9219 Centre 9219. all complete work as per drawing ,design., specification and direction of Engineer-in-charge /Bank.. Cost includes one no. door lock .	Sqm	6.50		
23	<b>Grahak Mitra:</b> Providing and fixing Grahak Mitra Counter as drawing , Design and specification.	No.	0.00		
24	<b>ACP Penaling(Exterior Grade) at main Entrance:</b> Providing and fixing 3mm thick Aluminium composite Panel With Bank Monogram as per Drg, Design and specification of the Bank. Cost includes cot of Monogram in Blue ACP	Sqm	18.00		
		Total			

GST extra as applicable

Seal & Signature of the Vendor