

<b>SCHEDULE OF WORKS FOR INTERIOR WORKS FOR UNIFORM LAYOUT IMPLEMENTATION IN EAST FORT THRISSUR, KERALA POLICE ACADEMY AND PERINGAVU BRANCHES, UNDER RBO-I THRISSUR, AO THRISSUR.</b>					
Sl No	Description of work	Quantity	Unit	Rate	Amount
<b>I)</b>	<b><u>EAST FORT:-</u></b>				
	<b><u>PROVIDING CORIAN TOP/ LAMINATE CHANGE AND MINOR INTERIOR WORKS.</u></b>				
1	Providing and fixing 6 mm marine flexy plywood of approved make with curved bend in front modesty to the existing surface of counters using necessary frames.	23	Sq.M		
2	CORIAN TOP:- Providing, fitting and fixing flexible solid surface material (Corian solid surface - 6 mm thick)of approved shade and make as per drawing and design. Solid surface material is to be fixed with acrylic epoxy adhesive compound including surface and edge finishing and moulds. The fixing is to be done on exposed surface of counters, tables or any other surface as directed. The work is to be completed with all materials, accessories, labour, tools and tackles and in strict conformity with manufacturer's specification and recommendations. The job shall also include provisions for electrical, computer & telephone wiring conduits, switch boxes etc. All materials should be approved by the Bank. Executed plan and elevation area of the surface work shall be measured for finished work.	23	Sq.M		
3	Providing and fixing 6 mm ply wood finished with 1 mm laminate of approved make and shade to the existing table top finishing with necessary beedings etc complete.	6	Sq.M		
4	Providing and fixing 6 mm plywood with 1 mm laminate of approved make and shade to the existing partition/ panelling/ counter and table sides etc. and wherever necessary making the surface in level. Rate includes charges for removing and refixing existing glass /beedings etc. complete. Area of partition excluding existing glass area to be measured for payment.	167	Sq.M		
5	Remove the existing laminate and fix with new 1 mm laminate of approved make and shade	16.00	Sq.M		
6	Providing and fixing side portion glazing with "Blue Laminated / Lacquered transperated glass of 12mm thick of approved brand and shall be fixed with 'Doma' (or) equivalent brand 'SS ' 'D' brackets. The curved 12mm thick lacquered transperant toughened glass shall be fixed at front size in between counters as per drawing and shall be fixed suitably with 'SS' brackets.	8.00	Sq.M		
7	Providing and fixing front Modesty with 8 mm thick Aqua blue shade of Saint Gobain glass or equivalent fixed 3M stickering suitable at front vertical finished with 1 mm laminate.	12.00	Sq.M		

8	Painting the false ceiling with two coats of plastic emulsion paint of approved color	159.00	Sq.M		
9	Painting banking hall using approved quality ' Asian paint or equivalent two coats without putty finish	183.00	Sq.M		
10	Providing PVC telescopic key board tray with channel	12.00	Nos.		
11	Removing the existing drawer channel and fixing new telescopic channel of approved make	24.00	set		
12	Providing and fixing Godrej auto lock	11.00	Nos.		
13	Gypsum Board False Ceiling (for Locker room)	6.00	Sqm		
	Providing and fixing of M/F suspended false ceiling as the detail given in the drawings. With G.I frame work and 12.5 mm tapered gypsum board panels to form grids of 45.7 X 122 cm as per manufactures specification including provision for stepped shaped ceiling for lighting trough comprising				
	Frame work of intermediate channels (M.F.T) at 122 cm centers along one direction M/F ceiling section MF5 at 45.7 cm center along other direction. Perimeter channels (MF 6A) along walls around perimeter side of the ceiling. The intermediate channels suspended from ceiling,through starp hangers 25 X 0.5 mm (MF 8)at 122 cm centers connected to soffit cleats p534 (27 X 37 X 25 X 1.6mm) the cleats connected to ceiling through metal expansion rawl plugs 1/2" dia and 17/16" long with additional perimeter channels (MF 6A)for light fittings, Air conditioners Ducts,vertical drops, offset etc. 12.5mm thick gyp board with tapered edges fixed to underside of suspended grid with 25 mm screws to from grids with 2 coats of plastic emulsion paint of approved color and one coat of putty over a coat primer etc, complete.				
II)	<b>KERALA POLICE ACADEMY:-</b>				
	<b><u>PROVIDING CORIAN TOP/ LAMINATE CHANGE AND MINOR INTERIOR WORKS.</u></b>				
1	Providing and fixing 6 mm marine flexy plywood of approved make with curved bend in front modesty to the existing surface of counters using necessary frames.	7	Sq.M		

2	CORIAN TOP:- Providing, fitting and fixing flexible solid surface material (Corian solid surface - 6 mm thick)of approved shade and make as per drawing and design. Solid surface material is to be fixed with acrylic epoxy adhesive compound including surface and edge finishing and moulds. The fixing is to be done on exposed surface of counters, tables or any other surface as directed. The work is to be completed with all materials, accessories, labour, tools and tackles and in strict conformity with manufacturer's specification and recommendations. The job shall also include provisions for electrical, computer & telephone wiring conduits, switch boxes etc. All materials should be approved by the Bank. Executed plan and elevation area of the surface work shall be measured for finished work.	7	Sq.M		
3	Providing and fixing 6 mm ply wood finished with 1 mm laminate of approved make and shade to the existing table top finishing with necessary beedings etc complete.	3	Sq.M		
4	Providing and fixing 6 mm plywood with 1 mm laminate of approved make and shade to the existing partition/ panelling/ counter and table sides etc. and wherever necessary making the surface in level. Rate includes charges for removing and refixing existing glass /beedings etc. complete. Area of partition excluding existing glass area to be measured for payment.	37	Sq.M		
5	Remove the existing laminate and fix with new 1 mm laminate of approved make and shade	3.00	Sq.M		
6	Providing and fixing side portion glazing with "Blue Laminated / Lacquered transperated glass of 12mm thick of approved brand and shall be fixed with 'Doma' (or) equivalent brand 'SS ' 'D' brackets. The curved 12mm thick lacquered transperant toughened glass shall be fixed at front size in between counters as per drawing and shall be fixed suitably with 'SS' brackets.	2.00	Sq.M		
7	Providing and fixing front Modesty with 8 mm thick Aqua blue shade of Saint Gobain glass or equivalent fixed 3M stickering suitable at front vertical finished with 1 mm laminate.	3.00	Sq.M		
8	Painting banking hall using approved quality ' Asian paint or equivalent two coats without putty finish	71.00	Sq.M		
9	Providing PVC telescopic key board tray with channel	5.00	Nos.		
10	Removing the existing drawer channel and fixing new telescopic channel of approved make	15.00	set		
11	Providing and fixing Godrej auto lock	5.00	Nos.		

12	Providing and laying VITRIFIED FLOOR TILES of size 600x600mm - <b>double charged</b> , type and thickness around 12mm without warpage, of make Kajaria/Johnson/RAK with water absorption less than 0.08 % and conforming to I.S. 15622 and colour laid on 20 mm thick cement mortar 1:5 (1 cement: 5 coarse sand),for inside flooring including grouting the joints with white cement and matching pigment etc. complete. Minimum Base rate of tiles should be <b>Rs 600/sqm.</b>	38.00	Sqm		
<b>III)</b>	<b>PERINGAVU</b>				
	<b>PROVIDING CORIAN TOP/ LAMINATE CHANGE AND MINOR INTERIOR WORKS.</b>				
1	Providing and fixing 6 mm marine flexy plywood of approved make with curved bend in front modesty to the existing surface of counters using necessary frames.	10	Sq.M		
2	CORIAN TOP:- Providing, fitting and fixing flexible solid surface material (Corian solid surface - 6 mm thick)of approved shade and make as per drawing and design. Solid surface material is to be fixed with acrylic epoxy adhesive compound including surface and edge finishing and moulds. The fixing is to be done on exposed surface of counters, tables or any other surface as directed. The work is to be completed with all materials, accessories, labour, tools and tackles and in strict conformity with manufacturer's specification and recommendations. The job shall also include provisions for electrical, computer & telephone wiring conduits, switch boxes etc. All materials should be approved by the Bank. Executed plan and elevation area of the surface work shall be measured for finished work	10	Sq.M		
3	Providing and fixing 6 mm ply wood finished with 1 mm laminate of approved make and shade to the existing table top finishing with necessary beedings etc complete.	4	Sq.M		
4	Providing and fixing 6 mm plywood with 1 mm laminate of approved make and shade to the existing partition/ panelling/ counter and table sides etc. and wherever necessary making the surface in level. Rate includes charges for removing and refixing existing glass /beedings etc. complete. Area of partition excluding existing glass area to be measured for payment.	115	Sq.M		
5	Remove the existing laminate and fix with new 1 mm laminate of approved make and shade	20.00	Sq.M		

6	Providing and fixing side portion glazing with "Blue Laminated / Lacquered transperated glass of 12mm thick of approved brand and shall be fixed with 'Doma' (or) equivalent brand 'SS ' 'D' brackets. The curved 12mm thick lacquered transperant toughened glass shall be fixed at front size in between counters as per drawing and shall be fixed suitably with 'SS' brackets.	4.00	Sq.M		
7	Providing and fixing front Modesty with 8 mm thick Aqua blue shade of Saint Gobain glass or equivalent fixed 3M stickering suitable at front vertical finished with 1 mm laminate.	5.00	Sq.M		
8	Painting the false ceiling with two coats of plastic emulsion paint of approved color	117.00	Sq.M		
9	Painting banking hall using approved quality ' Asian paint or equivalent two coats without putty finish	191.00	Sq.M		
10	Providing PVC telescopic key board tray with channel	6.00	Nos.		
11	Removing the existing drawer channel and fixing new telescopic channel of approved make	18.00	set		
12	Providing and fixing Godrej auto lock	6.00	Nos.		
	<b>TOTAL</b>				
	<b>GST</b>				
	<b>GRAND TOTAL</b>				