

TENDER & SPECIFICATIONS FOR PROPOSED INTERIOR FURNISHING WORK FOR P.B.B. BRANCH AT					
<u>S.NO</u>	<u>ITEM AND SPECIFICATION</u>	<u>QTY</u>	<u>UNIT</u>	<u>RATE</u>	<u>AMOUNT</u>
	<u>INTERIOR WORK'S</u>				
1	<u>FULL HEIGHT PARTLY GLAZED PARTITION</u>				
	Providing & fixing at site partly glazed partition with 50 x 75 x 1.2 mm Aluminum box frame with spacing at 600- 900c/c horizontally & vertically, to be sandwiched with 8.0mm Commercial ply from both the sides and finished with 1.0mm thick approved shades of laminated finish, The middle portion to have 8.0mm plain float mm. glass to be fixed to be fixed in partition above 3'0" and upto 7'0" level to be fixed with 1.25" x 1" wooden beadings. The cost shall include all labor, materials, strictly as per the given design & drawing etc complete.	39.00	SQM		
2	<u>SOLID PARTITION</u>				
	Providing & fixing at site partly glazed partition with 50 x 75 x 1.2 mm Aluminum box frame with spacing at 600- 900c/c horizontally & vertically, to be sandwiched with 8.0mm Commercial ply from both the sides and finished with 1.0mm thick laminated finish on both the sides, The cost shall include all labor, materials, strictly as per the given design & drawing etc complete.	40.00	SQM		
3	<u>FLUSH DOOR'S FOR PARTLY/ SOLID PARTITION</u>				
	Providing & fixing at site Flush door shall be of 32.0mm Commercial grade flush door with 1.0mm lamination on both the sides, and central portion to have 8.0mm plain float glass to be fixed with help of teak wood beadings. The Door is to be fixed to existing wooden partition/wall with heavy duty 5" Stainless Steel hinges, and shall have godrej Or equivalent mortice lock. All the edges of the door to be covered with 35 x 12 mm Teak wood beadings, The cost shall include Frame of 2nd class BTC/ Teak wood Frame of 100mm x 50 mm, all labor, materials, mortice lock, tower bolt inside, door stopper strictly as per the given design & drawing etc complete.	10.00	SQM		
4	<u>HALF HT. PARTITION</u>				
	Providing and fixing at site 1200(h) half height partition with 50 x 75 x 1.2 mm Aluminium box frame at 600 to 900 mm c/c. or as per the drawing to be erected . The frame is to be sandwiched with 8mm thick Commercial ply to be fixed from both sides .The partition is to be finished with 1.0 mm thick approved colour laminate of standard make. The partition shall have 12.0 mm thick plain Glass of height 200-300mm on top portion of the partition, teak wood beadings, The teak wood beadings to be finished with melamine polish. of size 40 x 20mm with natural polish to match the partition. All other exposed edges of sections are to be properly covered with 8mm ply & laminated finish, The cost of partition shall include necessary fittings, labour, contingencies etc complete strcitly as per the given design & drawings.	23.00	sqm		

S.NO	ITEM AND SPECIFICATION	QTY	UNIT	RATE	AMOUNT
5	<u>FRONT & TOP TOUGHNED GLASS FOR COUNTER</u>				
	Providing and fixing over the SWO counter over Front & top with 12.0 MM toughened glass of height 450mm, and top size of 300mm width, the glass shall have necessary rounding finish/ bevelled edges as per the requirement, The Glass is to be fixed with side partition with help of Teak wood beadings and members, The wooden members to have mealamine polish, the cost shall include all materials, labour, transportation to site, fixing etc complete.	5.00	sqm		
6	<u>WICKET GATE</u>				
	Providing and fixing at site wicket gate in the existing partition to be made up well seasoned hard wood/ 32mm flush door with 8.0 mm commercial ply, to be laminated on both faces with 1.0 mm thick laminate of approved shade, The cost of the gate shall include SS hinges, door closer , tower bolt, locking arrangement etc. complete.	1.10	sqm		
7	<u>VERTICAL BLINDS</u>				
	Providing and fixing at site vertical blinds 100mm wide vertical blinds with extruded powder coated head rail housing control units, spacers, runners, tilt rod with reduction gear mechanism, tilt control for rotation for rotation of 180 degree louvers made of approved fabric/ colour scotch guard coating & bottom mechanism of powder coated galvanised steel with required components.	8.50	sqm		
8	<u>MAIN ENTRANCE/ BM DOOR WITH 12.0MM TOUGHNED GLASS & Patch Fittings</u>				
	Providing and fixing at site Main entrance/ other doors "fully glazed" of 12.0mm toughened glass to be fixed with patch fittings including locks, with 600mm SS brush finished "D" Type door handle. The cost shall include all the fittings, Door handles, locks all materials, transportation fixing , all labour, contingencies etc complete but excluding cost of Floor Spring.	4.60	sqm		
9	<u>FIXED GLAZING 12.0MM TOUGHNED GLASS</u>				
	Providing and fixing at site 12.0mm toughened glass fixed glazing to be fixed with SS patch fittings at the site including filling of silicon sealant at all edges, gaps, wherever necessary as per the site condition, all materials, labour etc complete.	9.00	SQM		
10	<u>FLOOR SPRING</u>				
	Providing and fixing at site heavy duty Hydraulic floor spring for 12.0mm thick toughened glass door with patch fitting of Godrej/ Doorma Make only, to be fixed at site, inclusive of all labour, materials, contingencies etc complete.	2.00	NOS		

S.NO	ITEM AND SPECIFICATION	QTY	UNIT	RATE	AMOUNT
11	COLUMN/ WALL PANELING WITH LAMINATED FINISH				
	Providing and fixing at site column/ wall paneling with 50 x 19mm aluminum pipe section to be fixed with spacing between 300-400mm c/c vertically and top & bottom horizontally, as per the requirement to be finished with 8.0mm commercial Grade ply finished with 1.0mm laminate. of approved colour to be fixed in given patter in two shades of approved colour and shade is to be fixed as per the given design & pattern. The top of the wall panelling to have 25 x 50mm teak wood beading on top to be finished with melamine polish, the cost shall include all materials, labour etc complete.	102	sqm		
12	ETCHING FILM				
	Providing and fixing at site approved design & pattern of etching film to be 3m 7725 325 Pressure sensitive film for permanent graphic fixed at site over the glazed area as per the given design & drawing including all materials, wastage etc complete.	28.0	SQM		
13	FALSE CEILING (GYPSUM)				
	Providing and fixing gypsum false ceiling. in 12.5mm thick Gypboard (POP) plain false ceiling with corner POP molding & GI suspended from RCC slab/ Beam as approved by Bank/ Architect including G.I. Parameter Channels of size 0.55 mm thick having one flange of 20mm and another flange of 30mm and web of 27mm along with parameter of ceiling,screw fixed, to the brick wall / partition with the help of nylon sleeves and screws at 600mm C/C. The suspended G.I. Intermediate channels of size 45 x 0.9 mm thick with two flanges of 15mm each from the soffit at 1200mm C/C with GI cleats and steel expansion fasteners. Ceiling sections of 0.55mm thick having web of	56.00	sqm		
	51.5mm and two flanges of 26mm each with lips of 10.5mm are then fixed to intermediate channel with help of connecting clips and in direction perpendicular to intermediate channel at 457 mm C/C. 12.5mmTapered edge Gypboard channel at 457mm C/C in both the directions screwed fixed to the ceiling section with 25mm dry wall screws at 230mm C/C screw, fixing is done mechanically with drilling machine and suitable attachment. Finally the boards are to be jointed and finished with jointing compound, paper tape andtwo coats of top Coat, suitable for Gypboard (As recommended practice of India Gyp.) For light fittings incutouts etc are to be made with a frame of parameter channels of size 20 x 27 x 30 x 0.5mm thick supported suitably. Angle beads, edge bends, control joints as required to be provided. The quoted rates to include allthe above items, ceiling to be painted with minimum two coats of plastic emulsion paint including base preparation. etc. complete.				

S.NO	ITEM AND SPECIFICATION	QTY	UNIT	RATE	AMOUNT
b.	GYPSON DESIGNER CEILING with PATTERN AS PER THE DESIGN				
	Providing and fixing gypsum false ceiling.2' to 3' width at edges as per the given design in 12.5mm thick Gypboard (POP) plain false ceiling with GI suspended from RCC slab/ Beam as approved by Bank/ Architect including G.I. Parameter Channels of size 0.55 mm thick having one flange of 20mm and another flange of 30mm and web of 27mm along with parameter of ceiling,screw fixed, to the brick wall / partition with the help of nylon sleeves and screws at 600mm C/C. The suspended G.I. Intermediate channels of size	10.00	SQM		
	45 x 0.9 mm thick with two flanges of 15mm each from the soffit at 1200mm C/C with GI cleats and steel expansion fasteners. Ceiling sections of 0.55mm thick having web of 51.5mm and two flanges of 26mm each with lips of 10.5mm are then fixed to intermediate channel with help of connecting clips and in direction perpendicular to intermediate channel at 457 mm C/C. 12.5mm Tapered edge Gypboard channel at 457mm C/C in both the directions screwed fixed to the ceiling section with 25mm dry wall screws at 230mm C/C screw, fixing is done mechanically with drilling machine and				
	suitable attachment. Finally the boards are to be jointed and finished with jointing compound, paper tape and two coats of top Coat, suitable for Gypboard (As recommended practice of India Gyp.) For light fittings in cutouts etc are to be made with a frame of parameter channels of size 20 x 27 x 30 x 0.5mm thick supported suitably. Angle beads, edge bends, control joints as required to be provided. The quoted rates to include all the above items, ceiling to be painted with minimum two coats of plastic emulsion paint including base preparation. etc. complete.				
14	FALSE CEILING (ARMSTRONG)				
	Providing and fixing of false ceiling at all heights of 600mmx600mmx12mm Armstrong mineral fiber ceiling tiles of type IBIZA RH-90 laid on Armstrong prelude XL exposed grid systems with 9mm wide T Section flanges colour white. The frame work comprise of main runner spaced at 1200mm centers securely fixed to the structural soffit approved hangers at 1200mm maximum centers. Hangers (GI wire) to be fixed by approved roof plug and screws etc. The last hanger at the end of each main runner should not be greater than 450mm from the adjacent wall. flush fitting 1200mm along cross tees (with double stitching) to be interlocked between main runners at 600mm c/ c to form 1200x600mm modules. Cut cross tees longer than 600mm to be supported independently. 600mmx600mm modules to be formed by fittings 600mm long flush fitting cross tees centrally between the 1200mm cross tees. Perimeter trim to be Armstrong wall angle secured to walls at 450mm maximum centers.	95.00	sqm		

S.NO	ITEM AND SPECIFICATION	QTY	UNIT	RATE	AMOUNT
15	<u>FULL/ HALF HEIGHT STORAGE</u>				
	Providing and fixing at site Full/Half height storage cabinet fully covered from all sides and 18" deep including necessary shelves as per the design and specifications with openable shutters made up of 18mm Commercial ply, The rear portion is to be closed with 12.0mm ply , The cabinet is to be finished with 1.0mm thick laminated finish on external surfaces and 0.8mm thick laminated finish on inside surfaces. All the exposed edges to be finish with 20 x 6.0mm teak wood beadings finished with mealamine polish, The cost shall include all materials, handels, magnetic catchers, all labor, accessories etc complete.	13.00	sqm		
16	<u>WRITING DESK</u>				
	Providing & fixing at site Wall mounted writing desk as per design & drawings in the Branch made up of 18mm thick Commercial ply and 1.0mm thick laminated finished, and inside surfaces with 0.8mm laminated finish, to be hanged from the wall having the space for keeping vouchers, top of 12 mm Toughned Glass per design & drawing etc. complete.	1.00	NOS.		
17	<u>NOTICE BOARD</u>				
	Providing & fixing at site notice board of size 4' x 3' to be made up of kail/pine wood frame of size 3" x1.5" teak wooden section The Notice board shall have 19.0mm soft board lining at back with approved shade of cloth, strictly as per the design & drawing etc complete, including all materials, labour etc complete.	2.00	SQM		
18	<u>CENTER TABLE</u>				
	Providing at site center table 2'0"x3'0" to be made up of 19 mm thick BWP ply with 8mm Top Glass, all the exposed sides properly laminated with 1.0 mm thick laminate strictly as per the given design & drawing, including all labour, materials, etc complete..	1.00	each		
19	<u>DROP & COMPLANT BOX</u>				
	Providing & fixing at site drop & complaint box of size 1' x 1'3" to be made up of 19mm commercial board frame, to be finished with 1.0mm thick laminated finish, and 0.8mm thick laminate on inside surfaces, strictly as per the design & drawing etc complete.	2.00	NOS.		
20	<u>DOOR CLOSERS</u>				
	Providing & Fixing Hydraulic Door Closers, godrej or EQ Make to Door Shutter with Frames using necessary Screws, Nuts & Bolts etc. complete.	4.00	NOS		
21	<u>ALUMINIUM CLADDING</u>				
	Providing & Fixing at site 3.0mm thick Aluminum External cladding to be fixed at the site over Aluminum tubular pipes placed between 600 x 750mm in both the directions with two colours, as per the design, all the joints shall be filled by exterior grade of Silicon sealant, the cost shall include all materials, labour etc complete	49.00	Sqm		

S.NO	ITEM AND SPECIFICATION	QTY	UNIT	RATE	AMOUNT
	<u>DISMANTELLING WORK</u>				
22	Dismantling of existing old furniture, Ceiling, partitions, worn out doors, electrical board, old electrical wiring , old conduit etc, including including clearing of site, transportation etc to the municipal dumping site etc complete	1	Job		
23	<u>Blow FRONT SHUTTER COVER FOR PANTRY</u>				
	Providing and fixing at site front shutter cover in 25.0mm thick Commercial block board with 1.0mm thick laminated finish on external surfaces and 0.8mm thick laminated finish on inside surfaces, the shutters to be fixed to main frame by heavy duty SS Hinges, the cost shall include all handles, magnetic catchers, locks accessories as required etc complete.	2	SQM		
24	<u>INTERNAL GLASS PARTITION</u>				
	Providing and fixing at site 12.0mm toughed glass internal partition of size 1050 x 1350mm with S.S patch fittings including with approved pattern of etching to be fixed at the site, the cost shall include all materials, labour etc complete.	3.00	sqm		
25	<u>PANTRY PLATFORM</u>				
	Providing and fixing at site Black coloured 18mm thick Granite stone with base support, edge moulding, including fixing of stainless steel sink over pantry platform including all base support with two nos marble pieces fixed to floor including all materials, labour etc complete Approx length 2.7 mtr	1	Nos		
	TOTAL INTERIOR WORKS FOR BRANCH (A)				
	<u>FURNITURES WORK</u>				
1	<u>MANAGER TABLE</u>				
a.	Providing at site Chief Manager Table Size- 6'x2'6"x2'6" at site as per design to be made up of 18 mm Commercial ply . The table shall have 1 No. 400mm wide cupboard with 1 No sliding tea tray and three Nos drawers on one side & provision of keeping Computer with Sliding keyboard Tray below it. All drawers are to be provided with telescopic sliding rails. The exposed edges of ply are to be finished with teak wood with matching shades. The table is to be finished with 1.0mm thick approved shades of laminate, and all the inside portion to have 0.8mm thick laminated finish, The cost of the table shall include all necessary SS fittings. Material, labour etc. complete	1.00	Nos		
b.	Providing & fixing at site/ rear credenza 3'0" x 16" x 2'6", which is an independent unit with storage almirah with openable shutters to be made up of 18mm Commercial ply to be finished with 1.0mm laminated finish . The inside portion shall 0.8mm thick white laminated finish. All drawers are to be provided with telescopic Sliding Rails. All the exposed edges to be finished with melaminated teak wood beadings, The cost shall include all necessary fittings, Knobs, locks etc. complete strictly as per the given design & drawing. The cost of the credenza shall include all necessary SS fittings. Material, labour etc. complete	1.00	No		

S.NO	ITEM AND SPECIFICATION	QTY	UNIT	RATE	AMOUNT
2	<u>SINGLE WINDOW TRANSACTION COUNTER</u>				
	Providing and fixing at site SWT counter of size-5'X2'6" to be made up of 18mm Commercial ply and finished of approved shade & colour Acrylic Surface tops 12.0mm " Corian" for counter top, Blue Lacquered Glass/ Blue Shade high Gloss PU coating on Fascia & Light Blue transparent Glass between single windows. The inside of counter shall have 0.8mm white laminated finish. Three Nos drawers are to be made at right side with heavy duty ISI Marked telescopic sliding rail. The drawers shall have self closing locks of godrej make. The counter shall have computer sliding Key Board tray to be fixed in it. provision to be made to keep CPU shelf as per the drawing to be placed below the corner of the table. All exposed edges to be ply to be finished with teak wood beading to be finished with melamine polish, The cost of the table shall include all necessary SS Finished fittings, all labour etc. complete, but excluding cost of Corian top which is to be paid separately	6.00	RM		
3	<u>CORIAN TOP/ SURFACE</u>				
	Providing and fixing at site 12.0mm thick Corian white glazed top over the SWO Counters, Manager's table, and other surfaces as per the given drawings and design, including finishing, polishing the finish to give desired results, the cost shall include all labour, materials, cost of fixing, polishing etc complete.	9.00	SQM		
4	<u>SALES / OFFICER TABLE</u>				
	Providing and fixing at site table size 5'X2'6" as per the design and shape to be made up of 18mm Commercial ply with 1 nos. cupboard below it having tea tray, sliding drawer unit (with sliding rails) . To be finished with 1.0mm thick approved shades of laminated finish, White laminate on sides and modesty panel. The table shall have computer with sliding keyboard as per design & specifications, all exposed surfaces to be finished with 1.0mm laminated finish and pattern of other color Laminate . All the inside surfaces to have 0.8mm thick laminated finish of approved colour and shades. All the edges shall be finished with teak wood beadings finished with melamine polish. The cost shall include all accessories such as sliding rails, drawer locks etc complete. The table is to be made with two different shades of laminate in skirting and design, including all materials, labor etc complete strictly as per the drawing.	8.00	Nos.		
5	<u>GRAHAK MITRA TABLE</u>				
	Providing and fixing Grahak Mitra Table size- 4'X 2'3"X3'6" as per given Design, Drawing in made 18mm thk. Commercial Ply & With approved colour laminate fixed with approved make and shade / design etc. complete. All the exposed edges to be finished with melamine polished teak wood beading, All inside surfaces to have 0.8mm thick laminated finish. The cost shall include all materials, labour, accessories etc complete,	1.00	Nos.		

S.NO	ITEM AND SPECIFICATION	QTY	UNIT	RATE	AMOUNT
6	<u>SIDE CREDENZA</u>				
	Providing & fixing at site rear credenza 3' x 16" x 2'6", which is an independent unit with storage almirah with openable shutters to be made up of 18mm Commercial ply to be finished with 1.0mm laminated finish . The inside portion shall 0.8mm thick white laminated finish. All the exposed edges to have melamine finished teak wood beadings, All drawers are to be provided with telescopic Sliding Rails. The cost shall include all necessary fittings, Knobs, locks etc. complete strictly as per the given design & drawing. The cost shall include all materials, labour, accessories etc complete,	6.00	Nos.		
	TOTAL FURNITURE WORKS FOR BRANCH (B)				
	<u>ESTIMATES FOR CIVIL WORKS</u>				
1	<u>POP PUNNING</u>				
	Scraping of old paint/ distemper wherever necessary from the existing walls, and applying of 4.0 to 8.0 mm thick lime punning over it to give a smooth leveled finish, the final coat of punning to have one coat of oil based Cement primer the cost shall include all labor , materials, etc complete.	130	SQM		
2	<u>ACRYLIC EMULSION PAINT</u>				
	Applying one coat of cement premier and applying two or more coats of Acrylic emulsion Royale/ Velvet touche to be applied over the punning area with roller to give desired smooth finish, including one coat of Birla Putty properly sand papered to give a neat smooth & silky finish, the cost shall include all materials, labour etc complete.	130	SQM		
3	<u>SYNTHETIC ENAMEL PAINT</u>				
	Two or more coats of approved shade synthetic enamel including one base coat of steel/ wooden primer over the existing wooden/ steel surfaces, with brush after cleaning & scrapping by wire brushing. Including all materials, labour etc complete.	35.0	SQM		
4	<u>OIL BOND DISTEMPER</u>				
	Two or more coats of Acrylic oil bond distemper with brush over the existing wall surfaces, after scrapping the existing finish, applying one coat of cement premier and one coat of putty to repair the wall as per the site condition including all materials, labour etc complete.	210.0	Sqm		
5	<u>TEXTURED PAINT</u>				
	Applying approved shade, pattern and surface textured paint over the wall, to give an even shade/ pattern, including all materials, labour etc complete, over the existing POP punning wall surface	22.0	sqm		
6	<u>WHITE WASH</u>				
	Two or more coats of white wash with brush over the existing ceiling, after scrapping the existing finish. to give a neat smooth finish including all materials, labour etc complete.	85.0	Sqm		

S.NO	ITEM AND SPECIFICATION	QTY	UNIT	RATE	AMOUNT
7	FLOORING DOUBLY CHARGED VITRIFIED TILES				
	Providing and fixing mirror polished Full body doubly charged vitrified tile flooring Premium quality, RAK, Kajaria, Jhonson, make with pattern of different color as per the given design, 600 X600 x 9.0MM tiles to be fixed at site at Floor and in skirting including leveling of the base below (if required) with 1:4 cement mortar, Including filling of the joints between two tiles with matching shade of "Tile joint filler", including all materials, labour etc complete all materials, labour etc complete.	220.0	SQM		
8	Removing of existing Vitrified tiles floor/wall tiles etc complete &, throwing away all the waste materials, away from the existing site including transporting, labour etc complete.	230	sqm		
9	TOILET WORK				
	WALL TILES				
a	Providing & Fixing at site 1st quality 6.0mm thick Glazed ceramic colored tiles of size 12" x 18" to be fixed on walls of toilet with 1:3 cement mortar after removing of existing finish & chipping of old plaster below the existing tiles the cost shall include all materials, labour, materials, etc complete.	28	SQM		
	FLOOR TILES				
b	Providing & Fixing at site colored 16" x 16" x 8.0mm anti skid ceramic floor tiles to be fixed over the floor surface after removing of existing floor in 1:3 cement mortar including all labour, materials, etc complete.	7	SQM		
c	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required : of Hindware/ Parryware/ RAK Basic price of seat Rs 8500.0	2.00	NOS		
	W.C. pan with ISI marked white solid plastic seat and lid				
d	Providing & Fixing at site Light Colored Wash basin of Standard size (450 x 350) including pedestal and heavy duty pillar cock Quarter Turn of Parko, Plumber, Jacuzzi make including CP heavy duty fittings all accessories such as PVC connection, Angle cock all materials, labour, materials, etc complete.	2	Nos.		
e	Providing & fixing at site 20mm CPVC pipe of 2.0mm wall thickness Class to be fixed in walls including all accessories after making Necessary chases in the existing Brick Work, fixing of pipe and making chases good including all accessories labour, materials, etc complete.	35	M		
f	Providing & Fixing at site heavy duty Quarter turn foam flow Bib cocks, with ceramic disc angle cock & other taps of Parko, Plumber, jacquar make as per the site requirement etc complete.	4	Nos.		

S.NO	ITEM AND SPECIFICATION	QTY	UNIT	RATE	AMOUNT
g	Providing and fixing at site 5.0mm mirror to be fixed at site with 12.0mm BWP ply backing and to 25 x 50mm teak wood frame duly painted to match the tile color including all materials, labour etc complete. Mirror size 750 x 600mm	2	Nos		
h	Providing & Fixing at site Light Colored Flat Full body Urinal pot of Standard size, including fixing of push button type heavy duty stopcock of Parko or equivalent make over each urinal for flushing purposes to be fixed at site including waste coupling, necessary PVC waste pipe, all fittings accessories, labour etc complete.	1	Nos.		
l	Providing & Fixing at site 100mm PVC waste/soil pipe of Kissan or equivalent make including all bends, Tees, and necessary accessories to be fixed at site at Ground floor toilets & first Floor for connections, connecting the same to individual toilets, 'making all necessary connections at ground floor including all materials, fittings such as TEE, Bends, inspection tees, necessary clamp, fixing the pipes with adhesive cement inclusive labour etc complete. The cost shall include removing of old Asbestos pipes and fixing of PVC pipes in place of existing pipe all labour etc complete	20	M		
j	Providing and fixing at site towel ring Stainless Steel heavy duty to be fixed at site with metallic Anchor fasteners etc complete.	2	Nos		
k	Providing and fixing at site 100mm inlet/75mm outlet nahani trap heavy duty PVC of approved make including stainless steel jali, including all materials, labour etc complete.	4	Nos		
	TOTAL FOR CIVIL WORK (C)				
ABSTRACT SHEET FOR PROPOSED INTERIOR WORK'S AT P.B.B. AT BHOPAL (BHOPAL REGION)					
SNO.	SUBHEAD				AMOUNT
	BRANCH				
A	TOTAL AMOUNT INTERIOR WORKS FOR BRANCH				
B	TOTAL AMOUNT FURNITURE WORK FOR BRANCH				
C	TOTAL AMOUNT CIVIL WORK FOR BRANCH				
	GRAND TOTAL				