BILL OF QUANTITY FOR HI WALL SPLIT AIR CONDITIONERS STATE BANK OF INDIA, PARSHURAMPUR BRANCH, RBO-V BASTI AO GORAKHPUR (U.P)

S.					
No.	Item Description	Unit	Qty	Rate	Amount
1	Supply of 1.5 Tr hi wall type BEE rated 5 star inverter technology split air conditioner with full function wireless remote and auto restart feature, with indoor/outdoor unit, gas charge, Copper condenser coils and Copper cooling coils company provided copper refrigerant pipe complete in all respects. Acceptable makes AC: Daikin/Toshiba/Godrej /Carrier/Blue Star/Voltas/Hitachi	Set	2		
2	Supply of 1 Tr hi wall type BEE rated 5 star inverter technology split air conditioner with full function wireless remote and auto restart feature, with indoor/outdoor unit, gas charge, Copper condenser coils and Copper cooling coils company provided copper refrigerant pipe complete in all respects. Acceptable makes AC: Daikin/Toshiba/Godrej /Carrier/Blue Star/Voltas/Hitachi	Set	2		
3	Supply of 4 KVA, wall mounted hi lo cut off stabiliser with TDR, voltage range 140-280V, complete in all respects. Stabilizer: Servel/ V Gaurd/ Marc/Sen & Pandit/ Stambh/ Inmag/Microtek	Set	4		
4	Installation, testing and commissioning of 1.5/1 Tr hi wall type split air conditioner as sl. no. 1, 2 & 3 and old AC dismantled from branch with wall cutting /mounting, and stabiliser making good of damages complete in all respects.	Set	6		
5	Supply, installation, testing and commissioning of insulated copper refrigerant piping set (suction and discharge)with duly insulated by nitrile rubber for 1.5/1 Tr AC. Size(thickness and dia) of both Copper pipe should as per recommendation of AC manufacturer's technical specification.(Old pipe dismantled from old branch is also to be used) Makes:Totaline/ Met Tube/Diamond/Star/Camipro	М	40		
6	Supply, installation, testing and commissioning of inter connecting wiring/cabling between indoor and outdoor of hi wall split AC(power supply will be made available at the outdoor unit, please quote accordingly)	М	50		
7	Supply, installation, testing and commissioning of PVC 25 mm water pipe with accessories and taking care to prevent leakages, for water drainage in concealed manner either on wall or under floor including making good of damages	М	40		

5	with one coat of primer and two coats of synthetic enamel outdoor type paint including its grouting and making good of damages, complete				
	in all respects.				
9	Dismantling of old hi wall Split/window ACs from the old branch premises and shifting/transportation to the new branch making good of damages, complete in all respects.	Nos	5		
10	Gas charging in the old split/window ACs dismantled from the old/existing branch premises and new/existing branch making good of damages, complete in all respects.	Kgs	2		
11 ¹	Supply, installation, testing and commissioning of suitable size MS member fabricated cage for outdoor unit as per Bank approved design duly painted with one coat of primer and two coats of synthetic outdoor type enamel paint.	Kg	80		
	SUB TOTAL (A): HI WALL SPLIT AIR CONDITIONERS				
1	Comprehensive Annual Maintenance Charges of 1.5Tr. AC(Quote exclusive of GST which will be payable additionally at prevalent rates, if payable. AMC expenditure for three years shall be considered for comparison of tenders to arrive at L-1)	AC	2	Quote per AC per annum rat	Amount shouldbecalculatedasunder:perACper annumrateX2(for2nos.AC)X3(forthreeyearsAMCexpenditure)
	Comprehensive Annual Maintenance Charges of 1 Tr. AC(Quote exclusive of GST which will be payable additionally at prevalent rates, if payable. AMC expenditure for three years shall be considered for comparison of tenders to arrive at L-1).	AC	2	Quote per AC per annum rat	Amount should be calculated as under:per AC per annum rateX2(for 2 nos. AC) X3(for three years AMC expenditure)
			1		1

Note :Rates are considered inclusive of all except GST. GST shall be admitted additionally at prevalent rates/rules