

STATE BANK OF INDIA

	NAME OF WORK	PROVIDING RR MASONRY RETAINING WALL IN PORTION BEHIND SBI STAFF QUARTERS AT DEVIKULAM (PRICE BID FORMAT)			
	NAME AND ADDRESS OF THE CONTRACTOR				
Sl. No	Description of work	Quantity	Unit	Rate	Amount
1	Earth work excavation in all classes of soil for foundation of the RR wall back filling where ever necessary and depositing the soil within an initial lead of 50m etc. complete	350	Cum		
2	Providing and laying RCC of M25 Mix for RR masonry foundation including reinforcement laid in mesh design bothways(10mm tor steel@15cm c/c both ways) concrete, shuttering, machinery, labour etc.complete.	14	Cum		
3	Providing RR masonry in superstructure of retaining wall in 4 steps of thickness 50cms in the first , 40cms in the second l, 30cms in the third and 20cms in the fourth in CM 1:4 including simultaneous pointing of the joints, watering, curing etc. complete at all levels. The rate should be inclusive of labour, machinery etc.complete.	70	Cum.		
4	Providing RCC columns of size 30cmsx30cms Mix M20 as stiffners for every 6 metres of RR masonry including reinforcement, concrete, machinery, shuttering, labour etc.complete	6	Cum.		
5	Providing and fixing expanded metal netting over RR masonry including material, labour, etc. complete	1200	Kg.		
	TOTAL				
	GST				
	TOTAL AMOUNT				

