



PRICE BID- INTERIOR RENOVATION WORKS SBI CHHANAGIRI BRANCH

TENDER ID: BHU201906009 Date: 08.06.2019

SI No	Item Description	Unit	Qty	Rate	Amount
1	Single Window Counter				
	<p>Providing and fixing in position 750 mm high single window counter with side credenza. The rate quoted for SWC shall consist of:</p> <p>a) Basic Structure: 19mm thick BWR/BWP ply for Top (1500 x 825 mm), Front (1500x750 mm), Two sides and one middle member (each 825x750 mm). Design and detail of the counters shall be as per Bank's new uniform colour, layout & elevation policy, with curvature on front made of flexi ply.</p> <p>b) One drawer unit (at every 1500-1800 mm length of counter) of 400mm wide (clear internal size). The chest of Drawer units shall have two smaller drawers of equal size on top and one bigger vertical filling drawer at bottom with autolocking push type locks (Godrej/Link) and "C" type SS finish handles. The drawers to be made out of 12mm thick BWR/BWP ply at sides, bottom and rear, 19mm thick BWR/BWP plywood at front side.</p> <p>c) One Side Table (Credenza) of size 1000x450x750mm with shutter unit of 600mm, with 2 drawers and two openable shutters made with 19mm BWP/BWR plyBoard with necessary hardware viz., ' W ' hinges, handles, locks, tower bolts, etc. Ebco/Godrej make telescopic sliding key board tray and a mobile CPU stand.</p> <p>d) The table and credenza top- exposed surfaces shall be clad with 1 mm thick laminate or equivalent make and shade as approved by EIC in the pattern as directed by the Engineer-in-charge with 6mm Flexi Plywood in curvature (which should be achieved with a frame work of 50mm x 50mm sal wood frame to be fixed from the front modesty panel / apron and the bottom of this niche to have provision of cove lighting with LED strips) and other exposed surface to be finished with 1 mm thick laminate of approved make and shade as directed by EIC.</p> <p>e) All un-exposed surfaces shall be clad with 0.7 mm thick laminate of approved make and shade.</p> <p>f) Ebco/Godrej make telescopic sliding key board tray and a mobile CPU stand</p>	Nos	5		
2	Work-station for Officer/staff with side credenza				
a	Branch Manager				
	<p>Providing executive type manager table of 1800x900x750 mm and side credenza 1050x700x400 mm with table top of 25mm th. ply and a front drawer unit consisting 3 Nos of drawer units slides on telescopic slider made up of 19mm thk ply with locking arrangement. The exposed edge surfaces are to be finished with 1.0mm thk laminates as per design of approved shade and the inner surface is finished with 0.7 mm thk laminate. The side credenza will have two drawer unit slides on telescopic slider and two cupboard unit. Quoted rates shall also include cost of polished teak wood moulding (finished 40x20 mm section) to edges of table. top: polished teak wood- lipping (6mm thick) to free edges of block board /plywood surfaces; approved drawer-slides, hinges and locks with keys in duplicate : other necessary hardware and accessories including satin finish S.S handles. knobs and wire - managers , foot rest etc. of approved quality. It also include readymade keyboard of engineering plastic .The keyboard is a pullout type, fixed to channels and screwed to below table top . The CPU stand is made up with 19 mm ply with laminate finish as per design. The work should be completed including all labour and material.</p>	Nos	1		
b	Officer/staff				
	<p>Providing executive type manager table of 1500x900x750 mm and side credenza 975x700x400 mm with table top of 19mm th. ply and a front drawer unit consisting 3 Nos of drawer units slides on telescopic slider made up of 19mm thk ply with locking arrangement. The exposed edge surfaces are to be finished with 1.0mm thk laminates as per design of approved shade and the inner surface is finished with 0.7 mm thk laminate. The side credenza will have two drawer unit slides on telescopic slider and two cupboard unit. Quoted rates shall also include cost of polished teak wood moulding (finished 40x20 mm section) to edges of table. top: polished teak wood- lipping (6mm thick) to free edges of block board /plywood surfaces; approved drawer-slides, hinges and locks with keys in duplicate : other necessary hardware and accessories including satin finish S.S handles. knobs and wire - managers , foot rest etc. of approved quality. It also include readymade keyboard of engineering plastic .The keyboard is a pullout type, fixed to channels and screwed to below table top . The CPU stand is made up with 19 mm ply with laminate finish as per design. The work should be completed including all labour and material.</p>	Nos	3		
3	Ply partition work				

	Providing and Erecting in position low/ full height (upto ceiling) partitions to be made out of 50 mm X 50 mm X 1.5mm thick Aluminum Tubular section frame work 600 mm c/c bothways (Vertical & Horizontal) fixed with 50 mm X 50 mm X 2.5mm thick Aluminum Angle Cleats with Pan Headed Screws covered with 9mm thick BWR/BWP PLY on both sides and ply fixed with Flat Headed Metal Screws .The aluminum members of partition shall rigidly fixed to the existing Ceiling /Floors / Beams & Side Walls, whichever is applicable & as directed, the alternate members and corner members fixed upto existing Slab, Beams, whichever applicable. All exposed surfaces of the partition shall have approved brand and shade 1.0mm thick laminate from both sides as directed complete. The necessary openings in the partitions shall be provided for A.C. Grill, Electrical Conduits, Electrical Switches, A.C. Opening, Electric Fixtures and Fittings etc. complete as per requirements/instructions of the Architect / Engineer.	Sqm	65		
4	Full height double skin baison board partition				
	Providing and Erecting in position full height (upto ceiling) partitions to be made out of 50 mm X 50 mm X 1.5mm thick Aluminum Tubular section frame work 600 mm c/c bothways (Vertical & Horizontal) fixed with 50 mm X 50 mm X 2.5mm thick Aluminum Angle Cleats with Pan Headed Screws covered with 9mm thick Baison board on both sides and finished with 1mm laminate on 4mm ply fixed on outer surface and 2 coats paint on inner surface .The aluminum members of partition shall rigidly fixed to the existing Ceiling /Floors / Beams & Side Walls, whichever is applicable & as directed, the alternate members and corner members fixed upto existing Slab, Beams, whichever applicable. All exposed surfaces of the partition shall be finished with one coat primer and two coats of plastic emulsion paint directed complete. The necessary openings in the partitions shall be provided for A.C. Grill, Electrical Conduits, Electrical Switches, A.C. Opening, Electric Fixtures and Fittings etc. complete as per requirements/instructions of the Architect / Engineer.	Sqm	10		
5	Flap doors: Providing and fixing flap door shutter made out of 50mm x 75mm wood sections for frame work 6mm ply fixed on both sides with 1mm laminate including all hardware fittings of S.S. finish, door stopper, door buffer, auto locking SS Knob , 2 Nos. SS 2 ball-bearing hinges, slide bolt all complete as per drawing, design, specification & direction of Engineer-in-charge. The rate shall include cost of all materials, labour, taxes, T&P, transportation, royalties etc.	Sqm	4.2		
6	Wall & Column Panelling				
	Providing and Fixing paneling for walls, columns etc. made out of 50 mm X 25 mm X 1.5mm thick Aluminum Tubular frame work at every 600 mm c/c (Vertical /Horizontal) both ways, covered with 9mm thick BWR/BWP PLY upto ceiling height etc. complete. All the exposed surfaces of the paneling shall be finish with approved make 1 mm laminate upto ceiling height . complete as per site requirements, detail drawing and the instructions of the Architect/Engineer.	Sqm	40.00		
7	Glass partition				
	Providing, making and fixing in position 12mm thick toughened clear float glass in the front side/ transacation side of half height partitions of Single Window Counters of appropriate size . All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets. The cost to include all materials, labour, fixing etching film and cut outs etc., for a neat finished job as per drawings and diretions etc., complete	Sqm	8.75		
8	Entrance Door (Glazed)				

	Providing, fixing in position glazed entrance Double door OR Single door with patch fitting of approved make using 12mm thk toughened glass edge polished. The Door to consist of Heavy Duty Floor spring (paid extra), Upper Patch, Bottom Patch, Lock Keeper Plate, Euro Profile Cylinder (EPC), "H" Type Handle 32 x 600mm, Corner Lock and the side fixed glass to have 2 Nos. Bottom Patch and 2 Nos. Upper Patch for each door to a neat finish etc., complete as per drawing	Sqm	2.6		
9	Storage Cabinet				
	Providing and fixing 750mm high and depth of 450 storage cabinet having minimum 2 filing cabinets made out of 19 mm thk. BWP block board. All exposed surfaces shall be clad with 1 mm thick s laminates of approved make and shade except edges . Edges which shall be covered with 1mm thk PVC lipping as directed by the Engineer-in-charge and Cabinet Top is to be provided with 1mm thick laminate. All un-exposed surfaces shall be clad with 0.7 mm thick laminate of approved make and shade storage cabinet should be complete in all respect as per the drawing and direction of Engineer-in-charge including all hardware and locking arrangements. The rate shall include cost of all materials, labour, taxes, T&P, transportation,	Sqm	8.15		
10	Vertical Blind				
	Providing & fixing vertical blinds of approve pattern and shade of Vista Leveller / Mac/equivalent as approved of 100 mm size including nylon twisted cords, ladder cords, powder coated aluminium top & bottom rail to windows/ partitions etc. cost includes all materials, labour, tax, lead, T&P etc. complete in all respects as per the direction of Bank's Engineer.	Sqm	9.25		
11	False Ceiling Grid Type				
	Providing & fixing in position Modular grid tile- false ceiling of Armstrong make 600 x 600 mm x 15/16 mm Dune Supreme RH 95 Prima tile (mineral fibre) with beveled Tegular edge framework as specified by Armstrong Co.and silhouette grid. Making necessary framework for A. C. ducting, if any, and necessary cutouts for diffusers and light fittings, taping and finishing to proper line & level.Installation to comprise main runner at 1200 centers fixed to structural outfits. First and last Armstrong suspension system should not be greater than 6000 from adjacent wall. 600x600 cross tees shall be provided between 1200 tees. M6 anchor fastner with verticle hangers made of galvanised steel 26x26x25x1.2mm , a pre straight hanger wire 2.68mm dia, adjustable hookss clipss of 0.8mm thick spring steel of 2.68mm shall be used. .(Note :- Only the plan area will be measured for payment. No extra payment will be made for cutouts, grooves, mouldings etc.)	Sqm	100		
12	False Ceiling Gypsum				
	Providing & fixing at site plain gypsum board stepped/ flush false ceiling as per pattern & design made from 12.5mm thk paper reinforced gypboard sheets fixed with mainframe channels 80mm x 26mm x0.5mm, every 450mm c/c or as mentioned in drawing intermediate channels 15mm x 45mm x 0.9mm at every 1220mm c/c with perimeter channel 20mm x 26mm x 0.5mm all along the wall shall be provided. The whole system to be suspended with strap bolts as recommended using rawl plugs 12.5mm dia. x 35mm long, with 6mm dia bolt & soffit cleat 27mm x37mm x 25mm x1.6mm thk. Gypboards to be screw fixed to the above framework using 25 mm dry wall screws. Provisions of melamine polished white beach wood moulding at wall / partition joints. Arrangements are to be made to accommodate light fixtures by forming recessed channels etc., wherever directed. Depressions, nails & screws, jointing & finishing etc., shall be done with jointing compound & paper tape. Ceiling shall be finished with painting 2 coats of plastic emulsion paint (velvet touch) of approved shade . Ceiling to be leveled & free from cracks including fixing GI perimeter to hold light fittings. Item to be completed in all respect to the Architect's approval. Provision of Opening (openable) min 4 nos(for maintenance purpose) in ceiling as per site conditions are to be done with necessary timber frame work tied with perimeter channel properly such as to match the remaining area of ceiling by leveling perfectly complete in all respect. This rate includes cost of all materials, labours, royalty,taxes, lead & lift to the place of work& also the cost of all fittings, (Measurements shall be taken for flat surface)	Sqm	185		
13	Floor Spring				
	Providing and fixing floor spring of Godrej/ Dorma two speed in floors for fixing flush doors. Necessary pivot shall be provided at bottom and top so that the flush door shall be operated. The cost includes cuttting and making the good of the floor etc complete as directed.	Nos	2.00		

14	P & F wall mounted running table of depth 600 mm and upto height 750 mm in 19 mm thk BWR ply of approved brand for table & top sides with necessary frame work made of sal wood / aluminum tubular section for fixing table in position & finished with 1mm laminate on exposed surface and 2 coats enamel paint at interior. Cost also include one single drawer unit per 1500 mm length of table.	rmt	2.00		
	Sub- Total				
15	Salvage value:				
	Dismantling and shifting the existing partitions, tables etc and catering away as buy back item. Cost to include making temporary arrangements for functioning of office using these items and the clenaing the premes as directed by EIC. Minimum Rs.10,000/-	Job	1	(-)	
	Grand Total				
	Note: GST shall be paid extra as per prevailling market rates				