PROVISION OF 35 WORK STATIONS AT B-WING ,GROUND FLOOR ,GITC BUILDING					
Sr No.	**Description**	**Qty**	**Unit**	**Rate**	**Amount**
1	Supplying and fixing of ready made knock down type computer Tables made of approved colour having provision for one 4 " deep drawer and open slot for keeping CPU , Providing and fixing wire manager, key board etc Size of table - 30"x 24"x30"	35.00	No.s		
3	Providing and fixing low height wooden partition made out of frame work of 2"x1 1/2" aluminium pipe of 18 gauge at a distance of 16" center to center in both direction, covered with 6 mm thick ply IS 303 finished with matching veneer of approved shade and make. top teak wood patti and polishing etc complete.	500.00	sft		
4	Carefully dismantling of flooring for creating race way and fixing new vitrified tiles of matching shade	20.00	sft		
5	Removing of wooden partitons and storing serviceable materials in our godown as directed by EIC	35.00	sft		
	Total Rs.				
	GST as applicable				
	Grand Total Rs				

NOTE: Work shall be completed in 15 days from date of issue of work order

Signature of Cotractor with Company seal
Mobile no.
Date:

PROVISION OF 46 WORK STATIONS AT C-WING ,2ND FLOOR LOBBY ,GITC BUILDING					
Sr No.	**Description**	**Qty**	**Unit**	**Rate**	**Amount**
1	Supplying and fixing of ready made knock down type computer Tables made of approved colour having provision for one 4 " deep drawer and open slot for keeping CPU , Providing and fixing wire manager, key board etc Size of table - 30"x 24"x30"	46.00	Nos		
2	Providing and fixing wooden T- shape partition 12" high with 6" base made out of 18mm thick ply IS 303 finished with 1mm thick laminate of approved shade and make on top of tables for fixing electrical switches/wires /cable and beeding patti ,polishing etc complete.	40.00	sft		
3	Providing and fixing low height wooden partition made out of frame work of 2"x1 1/2" aluminium pipe of 18 gauge at a distance of 16" center to center in both direction, covered with 6 mm thick ply IS 303 finished with matching veneer of approved shade and make. top teak wood patti and polishing etc complete.	152.00	sft		
4	Carefully dismantling of flooring for creating race way and fixing newgranite tiles of matching shade	20.00	sft		
5	Removing of wooden partitons and storing serviceable materials in our godown as directed by EIC	240.00	sft		
6	Finising the edges of wooden partions with beeding patti and polishing ect complete as directected by EIC	20.00	Rft		
7	P/F table top made 18mm ply IS -303 and matching 1mm thick laminate ,finishing ,folishing etc complete	20.00	sft		
	Total Rs.				
	GST as applicable				
	Grand Total Rs				

NOTE: Work shall be completed in 15 days from date of issue of work order

Signature of Cotractor with Company seal
Mobile no.
Date:

PROVISION OF 20 WORK STATIONS AT LLMS DEPT. 5TH FLOOR ,A&B-WING,GITC					
Sr No.	**Description**	**Qty**	**Unit**	**Rate**	**Amount**
1	Carefully dismantling existing partitions of 4' ht, cabinets, work stations etc. and stacking the same as per instructions of bank officials.	250.00	sft		
2	Supplying and fixing of ready made computer Tables made of approved colour having provision for one 4 " deep drawer and open slot for keeping CPU , Providing and fixing wire manager, key board etc Size of table - 36"x 24"x30"	20.00	No.s		
3	Providing and fixing low height wooden partition made out of frame work of 2"x1 1/2" aluminium pipe of 18 gauge at a distance of 16" center to center in both direction, covered with 12 mm thick ply IS 303 finished with 1 mm laminate of approved shade and make.	130.00	sq. ft.		
	Total Rs.				
	GST as applicable				
	Grand Total Rs				

NOTE: Work shall be completed in 10 days from date of issue of work order

Signature of Cotractor with Company seal
Mobile no.
Date:

PROVISION OF 11 WORK STATIONS AT 5TH FLOOR C & D -WING,GITC, BUILDING.					
Sr No.	**Description**	**Qty**	**Unit**	**Rate**	**Amount**
1	Supplying and fixing of ready made knock down type computer Tables made of approved colour having provision for one 4 " deep drawer and open slot for keeping CPU , Providing and fixing wire manager, key board etc Size of table - 30"x 24"x30"	11.00	No.s		
2	Providing and fixing low height wooden partition made out of frame work of 2"x1 1/2" aluminium pipe of 18 gauge at a distance of 16" center to center in both direction, covered with 12 mm thick ply IS 303 finished with 1 mm laminate , top 12mm TW patti with polishing etc complete as directed by Bank of approved shade and make.	130.00	sq. ft.		
	Total Rs.				
	GST as applicable				
	Grand Total Rs				

NOTE: Work shall be completed in 10 days from date of issue of work order

Signature of Cotractor with Company seal
Mobile no.
Date:

PROVISION OF 13 WORK STATIONS AT 2ND FLOOR ,BREAK OUT AREA ,TURBHE BUILDING					
Sr No.	**Description**	**Qty**	**Unit**	**Rate**	**Amount**
1	Supplying and fixing of ready made knock down type computer Tables made of approved colour having provision for one 4 " deep drawer and open slot for keeping CPU , Providing and fixing wire manager, key board etc Size of table - 30"x 24"x30"	13.00	No.s		
2	Providing and fixing low height wooden partition made out of frame work of 2"x1 1/2" aluminium pipe of 18 gauge at a distance of 16" center to center in both direction, covered with 8 mm thick ply IS 303 finished with matching veneer of approved shade and make. top teak wood patti and polishing etc complete.	100.00	sft		
	Total Rs.				
	GST as applicable				
	Grand Total Rs				

NOTE: Work shall be completed in 10 days from date of issue of work order

Signature of Cotractor with Company seal
Mobile no.
Date: