

SCHEDULE OF WORKS FOR INTERIOR WORKS FOR UNIFORM LAYOUT IMPLEMENTATION IN OLLUKARA AND KOORKENCHERY BRANCHES, UNDER RBO-I THRISSUR, AO THRISSUR.					
Sl No.	Description of work	Quantity	Unit	Rate	Amount
I)	<b>OLLUKARA</b>				
	<b><u>PROVIDING CORIAN TOP/ LAMINATE CHANGE AND MINOR INTERIOR WORKS.</u></b>				
1	Providing and fixing 6 mm marine flexy plywood of approved make with curved bend in front modesty to the existing surface of counters using necessary frames.	18	Sq.M		
2	CORIAN TOP:- Providing, fitting and fixing flexible solid surface material (Corian solid surface - 6 mm thick, DuPont make.) of approved shade and make as per drawing and design. Solid surface material is to be fixed with acrylic epoxy adhesive compound including surface and edge finishing and moulds. The fixing is to be done on exposed surface of counters, tables or any other surface as directed. The work is to be completed with all materials, accessories, labour, tools and tackles and in strict conformity with manufacturer's specification and recommendations. The job shall also include provisions for electrical, computer & telephone wiring conduits, switch boxes etc. All materials should be approved by the Bank. Executed plan and elevation area of the surface work shall be measured for finished work.	18	Sq.M		
3	Providing and fixing 6 mm ply wood finished with 1 mm laminate of approved make and shade to the existing table top finishing with necessary beedings etc complete.	6	Sq.M		
4	Providing and fixing 6 mm plywood with 1 mm laminate of approved make and shade to the existing partition/ panelling/ counter and table sides etc. and wherever necessary making the surface in level. Rate includes charges for removing and refixing existing glass /beedings etc. complete. Area of partition excluding existing glass area to be measured for payment.	197	Sq.M		
5	Remove the existing laminate and fix with new 1 mm laminate of approved make and shade	165	Sq.M		
6	Providing and fixing side portion glazing with "Blue Laminated / Lacquered transperated glass of 12mm thick of approved brand and shall be fixed with 'Doma' (or) equivalent brand 'SS ' 'D' brackets. The curved 12mm thick lacquered transperant toughened glass shall be fixed at front size in between counters as per drawing and shall be fixed suitably with 'SS' brackets.	6	Sq.M		
7	Providing and fixing front Modesty with 8 mm thick Aqua blue shade of Saint Gobain glass or equivalent fixed 3M stickering suitable at front vertical finished with 1 mm laminate.	8	Sq.M		
8	Painting the false ceiling with two coats of plastic emulsion paint of approved color	250	Sq.M		
9	Painting banking hall using approved quality ' Asian paint or equivalent two coats without putty finish.	300	Sq.M		
10	Providing PVC telescopic key board tray with channel	10	Nos.		
11	Removing the existing drawer channel and fixing new telescopic channel of approved make	30	set		

12	Providing and fixing Godrej auto lock	7	Nos.		
13	<b>Custom Made Full Height Solid Partition:</b>	14	Sq.M		
	Supply and set in position of custom made double skin full height partitions as per shape and size shown in the drawing.				
	Frame Work Detail: Aluminium sections of size 63.5 X 38.1X1.2 mm thk. of INDAL/JINDAL as internal frame structure, vertically at about 60cm centers varied along columns wall ends, junctions of walls, as necessary. Horizontally of the same size of frames at floor level, 750 mm, 1500 mm, 2100 mm, and roof level.				
	Lining Work: <b>6 mm Plywood</b> of approved make on both sides of framework from floor level to 6" above false ceiling level, and to be finished with 1mm laminate of approved colour and shaped on both sides including necessary grooves and steam beach beadings.				
	Measurement for the partition area shall be considered from floor level to false ceiling level only.				
<b>II)</b>	<b><u>KOORKENCHERY</u></b>				
	<b><u>PROVIDING CORIAN TOP/ LAMINATE CHANGE AND MINOR INTERIOR WORKS.</u></b>				
1	Providing and fixing 6 mm marine flexy plywood of approved make with curved bend in front modesty to the existing surface of counters using necessary frames.	19	Sq.M		
2	CORIAN TOP:- Providing, fitting and fixing flexible solid surface material (Corian solid surface - 6 mm thick, DuPont make) of approved shade and make as per drawing and design. Solid surface material is to be fixed with acrylic epoxy adhesive compound including surface and edge finishing and moulds. The fixing is to be done on exposed surface of counters, tables or any other surface as directed. The work is to be completed with all materials, accessories, labour, tools and tackles and in strict conformity with manufacturer's specification and recommendations. The job shall also include provisions for electrical, computer & telephone wiring conduits, switch boxes etc. All materials should be approved by the Bank. Executed plan and elevation area of the surface work shall be measured for finished work.	19	Sq.M		
3	Providing and fixing 6 mm ply wood finished with 1 mm laminate of approved make and shade to the existing table top finishing with necessary beadings etc complete.	11	Sq.M		
4	Providing and fixing 6 mm plywood with 1 mm laminate of approved make and shade to the existing partition/ panelling/ counter and table sides etc. and wherever necessary making the surface in level. Rate includes charges for removing and refixing existing glass /beedings etc. complete. Area of partition excluding existing glass area to be measured for payment.	116	Sq.M		
5	Remove the existing laminate and fix with new 1 mm laminate of approved make and shade	23.00	Sq.M		
6	Providing and fixing side portion glazing with "Blue Laminated / Lacquered transperated glass of 12mm thick of approved brand and shall be fixed with 'Doma' (or) equivalent brand 'SS ' 'D' brackets. The curved 12mm thick lacquered transperant toughened glass shall be fixed at front size in between counters as per drawing and shall be fixed suitably with 'SS' brackets.	7.00	Sq.M		

7	Providing and fixing front Modesty with 8 mm thick Aqua blue shade of Saint Gobain glass or equivalent fixed 3M sticking suitable at front vertical finished with 1 mm laminate.	10.00	Sq.M		
8	Painting the false ceiling with two coats of plastic emulsion paint of approved color	170.00	Sq.M		
9	Painting banking hall using approved quality ' Asian paint or equivalent two coats without putty finish	300.00	Sq.M		
10	Providing PVC telescopic key board tray with channel	12.00	Nos.		
11	Removing the existing drawer channel and fixing new telescopic channel of approved make	18.00	set		
12	Providing and fixing Godrej auto lock	9.00	Nos.		
13	Solid block works of approved qty of size 30x20x15cm & of compressive strength not<35 kg/cm <sup>2</sup> in foundation and plinth in C.M. 1:6 Extra for solid block work in super-structure above plinth level including staging if required.	4.00	Cum		
14	Plastering with Cement Mortar 1:5, (1 cement 5 sand) 12mm thick one coat floated hard and traveled smooth to inside walls including all staging work watering,curing etc complete.	36.00	Sqm		
15	Finishing New cement plastered wall with one coat primer, 2 coat of putty and painted with 2 coat of plastic emulsion paint after cleaning the surface .	36.00	Sqm		
16	FALSE CEILING:				
	Gypsum Board False Ceiling	9.00	Sqm		
	Providing and fixing of M/F suspended false ceiling as the detail given in the drawings. With G.I frame work and 12.5 mm tapered gypsum board panels to form grids of 45.7 X 122 cm as per manufactures specification including provision for stepped shaped ceiling for lighting trough comprising				
	Frame work of intermediate channels (M.F.T) at 122 cm centers along one direction M/F ceiling section MF5 at 45.7 cm center along other direction. Perimeter channels (MF 6A) along walls around perimeter side of the ceiling. The intermediate channels suspended from ceiling,through starp hangers 25 X 0.5 mm (MF 8)at 122 cm centers connected to soffit cleats p534 (27 X 37 X 25 X 1.6mm) the cleats connected to ceiling through metal expansion rawl plugs 1/2" dia and 17/16" long with additional perimeter channels (MF 6A)for light fittings, Air conditioners Ducts,vertical drops, offset etc. 12.5mm thick gyp board with tapered edges fixed to underside of suspended grid with 25 mm screws to from grids with <b>2 coats of plastic emulsion paint of approved color and one coat of putty</b> over a coat primer etc, complete.				

17	Providing and fixing good quality Aluminium composite panelling for ATM room, at the exterior columns, with white coloured panels.	27.00	Sqm		
18	Providing fixed glazed partition with powder coated Aluminium frame work twin syle sections top & bottom vertically and horizontally as required with all fixtures, with 12mm edge polished glass in between frame work including all labour charges etc complete.	9.00	Sqm		
19	Fully glazed Door for ATM room				
	Providing fully glazed door with powder coated Aluminium frame work twin syle sections top & bottom as required with all fixtures, with 12mm edge polished glass in between frame work including all labour charges etc complete. Rate shall include necessary etching film / LOGO, approved locking systems, 1 pair of 600mm long S. S. (H Shape) Handles of approved make, floor springs etc.	2.00	Sqm		
	<b>TOTAL</b>				
	<b>GST</b>				
	<b>GRAND TOTAL</b>				