

PRICE BID: LAST DATE AND TIME FOR SUBMISSION 2:00 PM ON 21.01.2020

BOQ FOR INTERIOR WORKS					
SBI BHADRAK BRANCH,RBO-III,AO-II,BBSR					
Item No.	Description	Qty.	Unit	Rate	Amount
1	Single Window Counters: 1.52mX 0.915mX 0.762m or 5'-0" (5'-0"to5'-6")X3'-0"X2'-6". Side table 0.915mX 0.405m or 3'-0"X1'-4"): Providing, making & placing in position SW counter table and side table with the following specifications: a) Table top made in 19 mm block board/BWR ply, all other members with 18/19 mm BWR plywood with 1 mm laminate, all edges to have 20 X 6 mm beech wood lipping except top which has to have Corian Top as per item no.22 (which will be paid separately. b) The front side of the table to have two pieces of 12 mm toughened glass upto 4'-0" height from floor level with frosted film with cut out for cash transaction. c) The drawer unit to have three drawers with necessary hardware, viz: drawer channels, handles, locks & denomination partitions, etc. d) One CPU pedestal. e) One plywood key board tray with channels to be provided. f) One foot rest g) Side table to have drawer cum cupboard unit be made with 19 mm block board/BWR ply and other members with 18/19 mm BWR plywood & 1 mm laminate with necessary hardware viz: cabinet hinges, handles, locks, tower bolts, etc. and 1"X1 1/2" beech wood beading and 3/4" X 1/4" beech wood lipping top to have Corian as per item no.22 etc.	4	Each		
2	Full Height Glazed Partitions:- Providing & fixing in position as per the layout full metal stud dry wall partition with the following specifications: a) supporting system comprising of best locally available make 51 X 35 X 0.55 mm thick aluminium studs @ 600 mm c/c and 51 X 32 mm aluminium tracks at floor, middle, door and ceiling level with joints staggered. The verticals should touch the ceiling with horizontal ceiling channel at slab/beam bottom. The rate should include necessary strengthening with studs/tracks or channel at doors and other openings. b) 9 mm BWR plywood fixed on both sides with 25 mm dry wall screws. c) 1 mm laminate on both sides (dark for bands, light for body) upto false ceiling level. d) 6 mm thick clear float glass with frosted film design as directed between 1050 X 2000 mm level in specified areas fixed with 85 X 15 mm beech wood jamb and 12 X 12 mm beech wood beading. e) All beech wood members to have melamine polish finish. Length X height upto false ceiling will measured for payment.	187	Sq.M		
3	Full Height Cement Board/ACP Partitions:- Providing & fixing in position of ACP or cement board as per the layout full metal stud dry wall partition with the following specifications: a) supporting system comprising of best locally available make 51 X 35 X 0.55 mm thick aluminium studs @ 600 mm c/c and 51 X 32 mm aluminium tracks at floor, middle, door and ceiling level with joints staggered. The verticals should touch the ceiling with horizontal ceiling channel at slab/beam bottom. The rate should include necessary strengthening with studs/tracks or channel at doors and other openings. Length X height upto false ceiling will measured for payment.	40	Sq.M		
4	Doors in partitions: The door frame made of approved quality Beach/Safeli wood. The Shutter to be 35mm thk BWR Block Board with both side finished with 1mm thk laminate with necessary inlays and grooves as per drawing. The door inlet with 8mm thk glass with etching design as directed. The edges of the door and four side of the glass shall be fixed with beading. The door to be provided with handles, locks of Doorset, door closers and stoppers etc. and other necessary hardware. All beading surface to be finished with melamine polish as instructed by Bank's Engineer/architects, all complete as per drawings. All materials to be approved by Bank's Engineer/architects.	35	Sq.M		
5	Systems Work Station: Providing, fabricating and fixing of Computer desks of0.762mX 0.61m or 2.5'Hx2.0' B size in the given length as per drawing and made with 19mm Plywood (of approved make) frame work having one 16" wide and 2' deep storage unit at every 4.0' length. Arrangement of Moulded Key Board Tray with channels, cable manager and foot rest of 4" x 1.5" Saal wood section shall be provided at every 4' length. Each storage unit shall consist of four sliding drawers of 5" height & the drawers shall be fitted with telescopic channels and automatic push type locking arrangement, brush steel finished handle and all exposed edges of plywood shall be fixed with steam beach wood beading finished with melamine polish. All visible surfaces such as front, sides, top, back, drawer outside etc.shall be laminated with 1 mm thick of approved shade and make. All invisible surfaces such as drawer inside, drawer supporting cabinet etc. shall be painted with two coats of enamel paint with a coat of primer and putty. The rates should include locking arrangement for all drawers alongwith best quality 4" brush steel handles, etc. complete. Cost should also inclusive of paneling, lapping of edges with plywood to achieve thickness as per design and approval of Engineer-in-charges.	3.50	Rm		

PRICE BID: LAST DATE AND TIME FOR SUBMISSION 2:00 PM ON 21.01.2020

BOQ FOR INTERIOR WORKS					
SBI BHADRAK BRANCH,RBO-III,AO-II,BBSR					
Item No.	Description	Qty.	Unit	Rate	Amount
6	Main Door:- Main Door frame made of approved quality Beach/Safeli wood. The Shutter to be 35mm thk BWR Block Board with both side finished with 1mm thk laminate with necessary inlays and grooves as per drawing. The door inlet with 8mm thick glass with etching design as directed. The edges of the door and four side of the glass shall be fixed with beading. The door to be provided with handles, locks of Doorset, door closers and stoppers etc. and other necessary hardware. All beading surface to be finished with melamine polish as instructed by Bank's Engineer/architects, all complete as per drawings. All materials to be approved by Bank's Engineer/architects.	8	Sq.M		
7	Main Door with 12mm thick toughened glass:- Providing & erecting fully glazed frame less glass doors made out of 12 mm thk. Toughened glass work with pencil polish edges all around. Glass door shall be fixed with top edge fixed to MS support structure/ beams/ roof lintel/ wooden frame work with necessary patch fittings. Rate is to be inclusive of all required necessary hardware fittings i.e. door handles/ bottom locks etc. and etching as directed by Engineer-in-charge. However floor spring is to be paid separately.	4	Sq.M		
8	Low Height Partition: Providing and fixing GI metal stud low height partitions with the following specifications. a) Supporting system comprising of best locally available make 51 X 35 mm aluminium studs at 600 mm c/c and 51 X 32 mm aluminium tracks at floor, middle and at 1200mm level with joints staggered. The rate should included necessary strengthening with studs/tracks or channels at openings. b) 9mm plywood with 1mm laminate (dark for bands and light for body) on both sides c) 85 X 15mm beech wood capping on top and sides of openings. The beech wood members to have melamine polish finish. d) 8 mm glasses with edges polished and with etching design above 3'-0" height at specified areas as directed.	98	Sq.M		
9	Backside Door for for SW counters:- : providing & fixing in position 35 mm flush door finished with 1 mm lamination on both the sides and edges covered with beech wood beading. The rate to include for providing 'Godrej' night latch, all hardware etc. complete..	4	Sq.M		
10	Wicket Gate: Providing & fixing Wicket Gate made out of 32 mm flush door finished with 1 mm lamination of approved shade on both sides with all necessary hardware such as hinges, tower bolt etc. complete. The edges shall be finished with beech wood beading polished.	1.50	Sq.M		
11	Wall Panelling: Providing & fixing aluminium stud wall panelling with the following specification: a) Supporting system comprising of best locally available make 51 X 35 X 0.55 mm thick aluminium studs @ 600 mm c/c and 51 X 32 mm aluminium tracks at floor, middle, door level and ceiling level with joints staggered. The verticals should touch the ceiling with horizontal ceiling channel at slab/beam bottom. b) 9 mm BWR plywood fixed on one side with 25 mm dry wall screws for the entire height of panelling. c) 1 mm laminate (dark for bands, light for body) upto false ceiling level. e) All beech wood members to have melamine polish finish. length X height up to false ceiling will be measured for payment.	120	Sq.M		
12	Column Panelling:- Same as item no.11 but for columns.	74.00	Sq.M		
13	Storage Units: Providing/making and placing in position low height storage units upto 0.762m or 2'-6" height or height as directed and 0.457m or 1'-6" deep made with 18/19 mm BWR plywood front sides and middle shelf and back side with 6 mm BWR ply covered with 1 mm laminate (dark for bands and light for body) at all exposed surfaces. Inner/unexposed surfaces to painted with two or more coats of enamel paint with putty finish including melamine polish finish for all wooden members. The rate to include cost of all necessary hardware viz., cabinets hinges, locks, handles, tower bolts etc. The unit should have beech wood beading 25 X 40 mm at top and edge lipping 20 X 6 mm complete.	64.00	Sq.M		
14	Plain Gypsum False Ceiling:- Providing and fixing Concealed Grid suspended ceiling system of 12.5mm India Gypsum Plaster Boards fixed to Frame Work of the company, Metal System concealed grid key lock suspended ceiling system consisting of 5mm suspension rod, adjustable spring loaded suspension clip, top cross rail of 3000mm long of 0.55BMT and furring channel 4000mm long made of 0.5mm BMT the top cross rail to be suspended from ceiling at every 1200mm and furring channel to be fixed to top cross rail at every 600mm to make a grid of 1200 x 600m. All the above components are to be made of galvanized steel. The rates to include cutouts for lighting fixtures / AC grilles / Fire Alarm Detectors etc., along with necessary strengthening and supports for fixing of these. The board joints are to be flush finished with jointing compound and paper tape, two coats of emulsion paint over a coat of primer etc., complete as directed.	18	Sq.M		

PRICE BID: LAST DATE AND TIME FOR SUBMISSION 2:00 PM ON 21.01.2020

BOQ FOR INTERIOR WORKS					
SBI BHADRAK BRANCH,RBO-III,AO-II,BBSR					
Item No.	Description	Qty.	Unit	Rate	Amount
15	0.609mX0.609m (2'-0"X2'-0") Silhouette Grid False Ceiling:- Providing and fixing in true horizontal level false ceiling grid system of Armstrong World Industries/Insula/Daikin etc.. The suspension system shall be 2'-0"X2'-0" plain grid system with 15mm wide flanges main runners and cross tees to have mitred ends with "birds mouth " notches to provide mitred cruciform junctions. Main runners to be spaced at 4'-0" fixed by using 2mm pre-straightened GI wire. Main tee, rotary stitched of size 15mm x 44mm x 3600mm at every 4'-0" c/c maximum and 4'-0" cross tee of size 15mm x 44mm x 1200mm at every 2'-0" c/c maximum and 2'-0" cross tee of size 15mm x 44mm x 600mm at every 4'-0" c/c maximum and 19mm x 19mm x 3000mm wall angle around the wall to form grid size of 2'-0" x 2'-0" and suspending the grid using 2mm pre-straightened GI wire and 6mm nylon rawl plug at every 4'-0" intervals at the main tee and laying of 15 mm thick mineral fiber tiles manufactured by Armstrong/Insula/Daikin etc. of size 2'-0"X 2'-0" 15mm over the formed grid etc., complete as directed.	181	Sq.M		
16	Repairing of existing Plain Gypsum False Ceiling:- Repairing to existing gypsum false ceiling with all required materials wherever necessary to make it good. The rates to include cutouts for lighting fixtures / AC grilles / Fire Alarm Detectors etc., along with necessary strengthening and supports for fixing of these. The board joints are to be flush finished with jointing compound and paper tape, two coats of emulsion paint over a coat of primer etc., complete as directed.	377	Sq.M		
17	BM's table: Size 1.67mX0.915mX0.762m , Side credenza 1.143m X 0.405m X 0.762m Or (Size 5'-6" X 3'-0" X 2'-6", Side credenza 3'-9"X1'-4"X2'-6"); Providing, making & placing in position executive table and side table ('L' Shaped) with the following specifications: a) Table top made in 25 mm block board/BWR ply & all other members with 18/19 mm BWR plywood with 1 mm laminate, except on top (which has to have Corian Top as per item no.22 and will be paid separately) all edges to have 20 X 6 mm teak wood lipping. b) One drawer cum shutter unit with necessary hardware viz: drawer channels,handles, locks etc. c) One CPU pedestal. d) One plywood key board tray with channels to be provided e) One foot rest f) Side table with shutters to be made with 25 mm block board/BWR ply with 1mm laminate or top and other members with 18/19 mm BWR plywood & 1 mm laminate with necessary hardware viz: cabinet hinges, handles, locks, tower bolts, etc. and 25 X 40 mm beech wood beading and 20 X 6 mm teak wood lipping etc. g) All the exposed surfaces to have 1 mm laminate of approved shade and brand. All unexposed surfaces to have two coats of enamel paint with putty. All wooden members to have melamine polish. h)The side credenza will have two drawer unit slides on telescopic slider and two cupboard unit. Quoted rates shall also include cost of polished teak wood moulding (finished 40x20 mm section) to edges of table. top: polished teak wood- lipping (6mm thick) to free edges of block board /plywood surfaces; approved drawer-slides, hinges and locks with keys in duplicate ; other necessary hardware and accessories including satin finish S.S handles	1	Nos.		
18	Tables for officer: 1.52mX0.762mX0.762m with side credenza (Size 5'-0"X2'-6"X2'-6", Side credenza 3'-6"X1'-4"X2'-6"); Same as item no. 17 but for the change in size.	9	Nos.		
19	Tables for others: 1.37mX0.762mX0.762m with side credenza (Size 4'-6"X2'-6"X2'-6", Side credenza 3'-6"X1'-4"X2'-6"); Same as item no. 17 but for the change in size.	6	Nos.		
20	Tables for Grahak Mitra & Tech Mitra: Same as item no. 17 but for the change in size.	1	Nos.		

PRICE BID: LAST DATE AND TIME FOR SUBMISSION 2:00 PM ON 21.01.2020

BOQ FOR INTERIOR WORKS					
SBI BHADRAK BRANCH,RBO-III,AO-II,BBSR					
Item No.	Description	Qty.	Unit	Rate	Amount
21	Repair and Refabrication of old existing work stations: Repair and re fabrication of existing tables/work stations including side cradenza and drawers by providing and fixing necessary hardwares such as channels, locks, handles, hinges, keyboard trays, sliding channels etc, as per the site condition. Remodeling the table as per Bank's new uniform colour, layout & elevation policy. Scrapping or making the existing surface rough. Providing and fixing 3.4 mm thick MDF board on the existing partition/door/table top or side etc., with necessary adhesive and nails/screws, hardwares etc. Thereafter, providing and fixing 1mm thick laminate of approved shade & colour, complete in all respect as per the direction of EIC. Polishing the beading etc, as per the site condition to match with the new ambience policy of the Bank. All unexposed surfaces of the table/ counters/ shelves to be painted with synthetic enamel paint/ fixing 0.8 mm thick laminate, as per the site condition. The table front edges to be provided and fixed with 35 mm x 12 mm thk boader lipping on sides and top finished with 1 mm laminate. Quoted rates shall also include cost of polished teak wood moulding and repair or fixing new hardware /channels /locks , hinges and locks with keys in dupli'cate : other necessary hardware and accessories including satin finish S.S handles. knobs and wire - cable managers as required to the furnitures The work should be completed including all labour and material.	14	Nos.		
22	White Acrylic Solid Surface(Corian/Equivalent make Finish):- Providing & fixing cladding with 'Corian/equivalent make' finish using 6 mm thick white Acrylic solid sheets of 6 mm thickness on top of tables, SW counters and fascia where directed. The rate to include all materials, labour etc. complete.	19	Sq.M		
23	12 mm glass on table top:- Providing & placing in position 12 mm glass on top of BM's table, side table, corners grounded properly, making hole for wire manager etc. complete.	36	Sq.M		
24	Wall paper:- Providing & fixing wall paper, of approved shade & design, basic price to be minimum Rs120/- per sft finished complete as directed.	10	Sq.M		
25	Interior Paintings: Supplying and applying of two coats of plastic emulson paints of ICI/DULUX/BERGER over a single coat of primer to all the inside walls,roofs etc .The surface to be painted need to be prepared by applying putty wherever required to make it smooth and good as per the direction of Bank .The rate should include supplying of labour,materials and scaffolding wherever required and all complete.	500	Sq.M		
26	Synthetic Enamel Paintings: Scrapping the old surface of the grills/rallings/wooden panel as directed by the Bank. making the surface free from dust thereafater applying one coat primer with two or more coat of synthetic enamel paint of Asian or equiv of berger/ ICI/ with approved shade and colour. Cost also include touch up finishing to the surface/wall surface to get uniform and smooth look, complete in all respect as per the direction of EIC.	175	Sq.M		
27	Polishing of railing/Baluster: Scrapping the old surface of the baluster/rallings as directed by the Bank, making the even and surface free from dust thereafater applying one coat primer with two or more coat of melamaine polish with approved shade and colour. Cost also include touch up finishing to the surface of the wood to get uniform and smooth look, complete in all respect as per the direction of EIC.	50	R.M		
28	Stickers with 3M Designer Film:	5	Sq.M		
29	Vitrified Tiles: Providing and laying in position Premium quality doubly charged vitrified tiles flooring of size 600mmX600mm (2'0"x2'0") and 10mm thickness of Kajaria/Jhonson/Nitco/ Naveen/Asian or equivalent make, laid as per design in line without gaps, leveled with four inch skirting, with chemical plaster (Laticrete) over existing flooring complete as per manufacturers specification.(Basic price of tile shall be Rs 650.00 per sqm.)	687	Sq.M		
30	Vitrified Tiles Skirting: Same as above but for 100mm high skirting	412	R.M		
31	Granite flooring: Supplying and fixing of prepolished granite of 18mm/20mm thick over a base course of minimum 15 mm thick cement sand mortar (1:4) with white cement pointing, grouting etc. as specified and directed, laid to required slope, cutting in required shape to corners / jointing etc. with all labour and materials complete. The surface shall be mirror polished including edges for a smooth finish.The colour and shade of granite shall be approved by the Bank. The basic cost of granite is Rs 2800/- per sqm.	131	Sq.M		
32	Wall cladding: Providing and fixing in position Premium quality doubly charged vitrified tiles (GVT) in walls of size 600mmX1200mm (2'0"x4'0") and 10mm thickness of Kajaria/Jhonson/Nitco/ Naveen/Asian or equivalent make, laid as per design in line without gaps, leveled with four inch skirting, with chemical plaster (Laticrete) over existing flooring complete as per manufacturers specification.(Basic price of tile shall be Rs 680.00 per sqm.)	27	Sq.M		
33	Soft board: of size 1500X1200 as directed.	2	Each		
34	Cheque Writing Table:- Supplying & fixing cheque writing table as per the standard design.	3	Each		

PRICE BID: LAST DATE AND TIME FOR SUBMISSION 2:00 PM ON 21.01.2020

BOQ FOR INTERIOR WORKS					
SBI BHADRAK BRANCH,RBO-III,AO-II,BBSR					
Item No.	Description	Qty.	Unit	Rate	Amount
35	Roller Blinds:- Providing, Fitting & Fixing of Roller Blind of approved Make and approved Fabric Shade with Head Box. The blind should be of manual control by means of roller glide chain drive system. Fabric shall be manufactured from polymer coated glass of Luxaflex/MAK/Vista/Equivalent. Etc. complete in all respects as per the direction of Bank's Engineer.	58	Sq.M		
36	Cheque drop/Suggestion box: Supplying and erecting cheque drop box (overall size 450 mm x 300 mm x 750 mm) made. of 19mm thick phenol formaldehyde bonded plyboard and the curved portion at top made out of 90 mm x 90 mm C.Pteak wood section. A slit opening of 10 mm x 150 mm is to be provided at the top of the box. An openable shutter of 259 mm x 262 mm size made of 19 mm thick phenol formaldehyde bonded block board is to be provided at 1.50 mm above finished floor level. All the exposed timber surfaces including. all free edges are to be finished with 1 mm thick laminate sheet of combination shade .Inner faces of block board surfaces are to be finished with minimum two coats of synthetic enamel. paint of approved shade and quality over a coat of approved primer.Rate .to include cost of necessary hardware fittings e.g. brass hinges, lock, knob etc. of approved.designand quality.	2	Each		
37	Providing and fixing of 12mm thick toughened glass: Supplying and fixing of 12mm thick toughened glass protruded in the partition for SW counter in trapezoidal shape with necessary brackets complete in all respect.	5	Sq.M		
38	Aluminium framed sliding windows: Supplying and fixing of sliding powder coated aluminium framed with 5mm thick glass window with all accessories complete, as per the direction of Bank.The rate should include supplying of labour,materials and scaffolding wherever required and all complete.	5	Sq.M		
39	Cover to rolling shutter: Providing, fabricating and fixing cover for rolling shutter made of 51mmX51mm aluminium frame work spaced at 460mm (18") c/c both directions, fixing 19mm plywood and 1mm laminate(only out side), providing trap door for rolling shutter maintenance with necessary hardware all complete.	4.0	Sq.M		
40	Buy back old counters, partitions wooden tables etc; The rate should include for supplying of labours for dismantling and removing of old partitions/furnitures/counters/ tables etc.(Except the work stations proposed to be reused and existing false ceiling)	-1.0	LS		
Total					

Amount in words:

GST WILL BE PAID EXTRA AS PER THE ACTUAL

NOTE:

- 1) The quantities put to tender are tentative only. Payment would be made on the basis of the actual quantity executed after completion of the work.
- 2) Materials specification to be strictly as per items and approved materials only. A copy of approved materials to be obtained by the contractor from the Engineer-in-Charge before commencement of the work.
- 3) Prior to starting of work contractor to discuss with the Engineer-in-Charge and sample materials are to be approved before start of the work at site.
- 4) The colour scheme has been finalized and the Contractor to collect the same from the Engineer-in-Charge before procurement of the materials from the market.
- 5) The successful Contractor should be responsible to make the area/duct/walls water tight without any extra charges.

Signature of the Contractor