

SCHEDULE OF QUANTITIES FOR INTERIOR FURNISHING WORKS
IN SBI "MEENA BAZAR" BRANCH (NEW BRANCH)
(DISTT.- CHAMPAWAT, UTTARAKHAND)

SR. NO.	DESCRIPTION OF WORKS	QNTY.	UNIT	RATE	AMOUNT
1	Providing and fixing 750 mm deep Customer Counters fabricated out of 19 mm thick commercial board finished with 1.0 mm thick laminate of approved make, shade and texture on all exposed surfaces including front of drawers, sides etc. and with all exposed internal surfaces, leg space, CPU space & key board drawer area to be finished with 1.0 mm thick laminate except top and front fascia (part) of the counter which shall be finished with corian of approved make, shade and texture (cost of corian only shall be paid extra under respective item). Transaction counter to be fabricated out of 12 mm thick toughened glass (acid wash & sand blasted) of 300 mm width (average) & fixed at 900 mm height with stainless steel studs as per approved sample. Front glass panel to be fixed between transaction counter & public counter complete (cost of glass only shall be paid extra under the respective item) with providing and fixing shelves, shutter, drawer & finishing of all internal surfaces (vertical & horizontal) with 0.8 mm thick laminate as per approved sample , steem beech wood beeding (12 X 6mm), 100 mm wide skirting with 2 nos. 19 X 6 mm steem beech wood moulding, necessary hardware, Hettich/Ozone/Godrej/ Ebco make telescopic sliding channel, Hettich/Ozone/Godrej/ Ebco make auto locks, Hettich/Ozone/Godrej/ Ebco make handles as per approved sample, Hettich/Ozone/Godrej/ Ebco auto-closing hinges for shutters as per approved sample, including providing and fixing 150 mm wide decorative ornamental column with grooves, beading, polishing of wood surface in melamine spray finish complete with making good all the surfaces, proving and fixing stainless steel cable manager in stone inclusive of cost of cutting hole in stone etc. complete.	5	RM		
2	Providing and fixing in position 12mm thick Corian of approved make, shade and texture duly fixed with adhesive wherever required in desired pattern and shape/ moulding etc. complete.	7	SQM		
3	Providing and fixing in position 4 mm thick Lacquered Glass of approved make, shade duly fixed with adhesive wherever required in desired pattern etc. complete.	2	SQM		
4	Providing and fixing 12mm thick clear Toughened Glass in front of public counters, cash counters & elsewhere held together with SS clamps & SS studs as per approved sample including providing and fixing steam beach beadings (18x18mm), steam beach moulding (62x31mm) along with polish & melamine spray finish etc. complete.	4	SQM		

5	<p>Providing and fixing Low Height Partition (up to 1500 mm) consisting of first class kailwood frame work of wood size 50 mm X 50 mm, except in skirting member which shall have 2 nos. 50 mm X 50 mm members at required spacing but not exceeding 600 mm center to center in either direction, 6 mm commercial ply finished with 1 mm thick laminate of approved make, shade and texture on both sides complete with 4.00 mm wide grooves vertically & horizontally in desired pattern/ curve inclusive of providing and fixing 10 mm thick etched glass as per approved design having curved top shape in low height partitions as per requirement, 2nd class C.P. teak wood moulding (65 X31 mm) on free end/ top of low height partition, 2nd class teak wood beading(12 X 12mm). Rate to include providing 2-3 bends and skirting with different shades of 1.00 mm thick metallic laminate including providing and applying fire retardant VIPER paint over wooden frame work and polishing wherever required etc. complete.</p> <p>Note: Measurement for one face of partition will be made for the purpose of payment.</p>	18	SQM		
6	<p>Providing & placing in position Side Cabinets having side partition drawers, shelves & shutter fabricated out of 19mm thick commercial board with 6mm thick commercial ply wood backing, all exposed surfaces, sides & front finished with 1mm thick laminate of approved make, shade and texture & top with 19mm thick pre-polished granite stone as per approved sample of basic rate Rs. 300/- per sq.ft. with half round edges complete with shelves, drawers, shutter, 100mm wide decorative metallic skirting (as per approved sample) including providing and fixing necessary hardware, hinges, locking arrangement with Hettich/Ozone/Godrej/ Ebco make locks, Hettich/Ozone/Godrej/ Ebco make telescopic steel channel runners, Hettich/Ozone/Godrej/ Ebco make handles as per approved sample, finishing of all internal surfaces vertical & horizontal with 0.8 mm thick laminate as per approved sample & providing polish on exposed wood surface with melamine spray etc. complete .</p>				
(I)	1050x450x750mm for BM.	1	NO.		
(ii)	900x450x750mm	3	NO.		
7	<p>Providing and fixing in position wooden built-in Storage Cabinets 450 mm deep. (continuous divided vertically @ 3'0" (900 mm) center to center distance or as per site condition having sides, partitions, shelves & shutters fabricated out of 19 mm thick commercial board & 6.00 mm thick commercial ply on back, finished with 1.00 mm thick laminate of approved make, shade and texture on all exposed surfaces, top, skirting (in different shade), 6 X 19 mm thick CP teak wood beading on exposed edges of 19 mm thick board, complete with shelves, shutters including necessary hardware, self closing hinges, SS handles, magnetic catches, locking arrangement with Hettich/Ozone/Godrej/ Ebco make locks, 75 mm brass tower bolts, finishing of all internal surfaces (vertical & horizontal) with 0.8 mm thick laminate as per approved sample, melamine polish on wooden surfaces.</p> <p>Note: Only front elevation will be considered for area/ quantity calculation.</p>	7	SQM		

8	<p>Providing and fixing in position Tables fabricated out of 19mm thick commercial board with all exposed surfaces inclusive of leg space area & CPU area finished with 1mm thick laminate of approved make, shade and texture & table top finished with 1.0mm thick thick laminate of approved make, shade and texture with 31x6mm steem beech wood moulding & 12mm thick etched plate glass complete inclusive of providing and fixing with drawers, shelves, shutter & 100mm wide skirting of metallic decorative laminate metallic in modesty panel as per approved sample 12x12mm steem beech beading including necessary hardware, Hettich/Ozone/Godrej/ Ebco make locks, locking arrangement, Hettich/Ozone/Godrej/ Ebco make telescopic steel channel runner for drawers, providing and fixing key board drawer, Hettich/Ozone/Godrej/ Ebco make handles (as approved sample) & polishing the exposed steem beech wood surface with melamine spray finish etc. complete along with finishing of all internal surfaces (vertical & horizontal) with 0.8 mm thick laminate as per approved sample. Rate to also include for providing and fixing SS cable manager, cutting & making hole and making good the surface etc. complete.</p>				
(I)	BM Table size: 2100mm x 900mm	1	NO.		
(ii)	May I Help You Table 2100 X 600 mm (curved in plan)	1	NO.		
9	Providing and placing 10 mm thick glass duly cut to shape/ size as directed including beveling, grinding etc.	2	SQM		
10	<p>Suspending system and frame work shall match layout of A.C. ducts/grills, electrical/fire protection wiring/fixtures, return air grills etc. Rate to include provision of extra frame work needed due to layout and fixtures etc referred above. Rates to include necessary scaffolding item includes design work cutting and bending in curved shapes as per requirements for providing false ceiling.</p> <p>Providing and fixing Gypsum Board False Ceiling with INDIA GYPSUM having main ceiling sections at 1200 mm center to center and cross members at 450 mm center to center. The grid work to be suspended from AC sheet ceiling (at height of approx. 12') with hangers at every 1200 mm center to center in both directions. The Framework to be as per manufacture's specifications. 12.5 mm GYPBOARD to be screwed to the frame. The board is to be finished with fitting the tapered edges of the board with jointing compound and finishing with paper tape of INDIA GYPSUM. The ceiling is to be finished with a top coat as per approved manufacturer. The item also includes painting the ceiling with plastic emulsion paint in 2 or more coats after preparing the base. The item includes all necessary cut outs for electrical/air conditioning grills and necessary framework for them. Item includes cove and step design in hall near windows and in customer area in all curves as per requirements. Rates also to include formation of cove (in center) of size approximately 2000 X 1500 mm or else as per Bank etc. complete.</p> <p>Note: Measurement shall be taken of the plan area only.</p>	50	SQM		

11	<p>Providing & fixing ARMSTRONG False Ceiling with 600X 600mmX 15mm thk tiles mineral fibre accoustic ceiling tiles with Microlook edges and having noise reduction properties as per manufacturer's specifications duly fixed with screws & GI framework suspended from AC sheet ceiling (at height of approx. 12') in combination with gypsum board false ceiling in required design & pattern. Item includes providing extra support for fixing light fixture. Providing and fixing suspended grid false ceiling in tiles of size 600mm x 600mm. A concealed grid system consisting of main runner spaced at 600mm center to center securely fixed to the structural soffit/slab by Nonius hanger at not exceeding 900mm center. Main runner shall be fixed to the Z-section / T-section by performed clip. White zinc coated perimeter angle profiles A-srw-15/B 25mm x15mm x8mm x 15mm / A-RWL 24mmx 24mm x 0.6mm shall be provided at the edges. Perimeter wedges shall be used to prevent the opening of panel joint. Transverse joints shall be supported by T-sections / L-section/ splines.</p> <p>Rectifying all defects and cracks formed during the construction period before handling over the work complete. The rates shall include for necessary supports, scaffolding, labour. All complete as per drawing, approval and instructions of the Architect/ employer.</p>	80	SQM		
12	<p>Providing and applying two or more coats of Plastic Emulsion Paint (roller finish) of approved make and shade over walls etc. after preparing the surface with a coat of primer and 6 mm thick plaster of paris punning to give a smooth and even surface etc. complete.</p>	200	SQM		
13	<p>Providing and applying two or more coats of Synthetic Enamel Paint of approved make and shade over a coat of primer as per manufacturer's specifications. The item is inclusive of scrapping, levelling and preparing the surface before applying primer etc. complete.</p>	100	SQM		
14	<p>Providing and applying two or more coats of Texture Paint/ Surface Coating of approved make and shade over walls etc. after preparing the surface with a coat of primer and 6 mm thick plaster of paris punning to give a smooth and even surface etc. complete.</p> <p>Note: Basic rate of Texture Paint to be Rs. 50 per Sq. Ft.)</p>	70	SQM		
15	<p>Providing and fixing Louvered Shutter Cabinet for main panel fabricated out of 19 mm thick commercial board and finished with 1 mm thick laminate of approved make, shade and texture, louvers fabricated out of steam beech wood duly polished with melamine spray and all other specifications complete in all respect as per the instructions of SBI/MS/SBI.</p>	4	SQM		
16	<p>Providing and fixing in position 600 mm deep Running Counter in system room fabricated out of 19 mm thick commercial board finished with 1.00 mm thick laminate of approved make, shade and texture on all exposed surfaces including top, front of drawers, sides including providing sliding key board and drawers. The rate shall include providing and fixing 0.8 mm thick laminate on all internal surfaces of drawers and inner side of back ply, providing the sides and both sides of vertical, horizontal members with teal wood moulding, necessary hardware such as Hettich/Ozone/Godrej/ Ebco make locks, Hettich/Ozone/Godrej/Ebco make telescopic sliding channels, Hettich/Ozone/Godrej/Ebco make handles etc as per approved sample, SS cable manager etc. complete.</p>	2	RM		
17	<p>Providing and fixing 12 mm thick Toughened Glass Glazing of approved make with all fittings including floor spring (in door), 2'-6" long SS handles, door lock along with all associated patch fittings of approved make including etching film (garware) along with blasted etching "State Bank of India" (in door/ elsewhere) etc. complete.</p>				

(i)	Fixed Glass Glazing	4	SQM		
(ii)	Openable Glass Door	2	SQM		
18	Providing and fixing 100 mm wide Vertical Blinds of 'MAC' or 'VISTA' make with rotating and pull apart arrangement etc. complete.	10	SQM		
19	Providing and fixing Voucher Tray 900x300x300 mm deep made out of 19 mm thick commercial board finished with 1 mm thick laminate of approved make, shade and texture with writing top and racks for keeping vouchers as per Bank's design and duly fixed to wall/pillars or elsewhere as per the instructions of the Branch etc. complete.	1	NO.		
20	Providing and fixing 1 mm thick laminate over 6 mm thick ply duly finished with beading, polish etc.	20	SQM		
21	Providing and placing in position center tables of size 1200x600x450 mm with 40mm teakwood legs 62.5x35 mm teakwood frame at top as detailed. 10mm bevelled brown glass fixed in SS spacers on top. The table to be finished in melamine polish complete.	1	NO.		
22	Measurement of height shall be taken from finished floor level up to the level of false ceiling, in case of varying heights on either side of partition, average height shall be considered. The rate to include provision of extra frame work as necessary for skirting and making cutouts for electrical switch plates, switch boxes, light fittings etc, making provision for laying conduit. All wood to be applied with 2 coats of fire retardant paint of VIPER make and 1 coat of wood preservative with anti-termite properties. Providing & fixing Wall Paneling over GI framework of member/ sections size 50mmx35mm placed at the spacing of 600 mm centre to centre both ways fixed on wall and covered with 12.00 mm commercial ply with 1 mm thick lamination of approved make, shade, texture including 2-3 bends and skirting with different shades of 1.00 mm thick metallic laminate duly fixed with adhesive & horizontal grooves in desired pattern, finishing of grooves with polish in desired shade, polishing of exposed wood, etc. complete. The rate should be inclusive of necessary cut out/panel for electrical/fire/telephone wiring etc. as required. Top of paneling and exposed edges of wood etc. to be provided with 2 nd class teak wood and beadings of size 40 mm X 12mm in desired pattern etc. complete with spirit polishing in desired shade etc. complete.	80	SQM		
23	Aluminium Glazing Partition:- Providing and fixing fixed Aluminium Glazing Partition of required size as per site made up of 83.5mm wide vertical members, 85-90mm wide top and bottom members and 83.5mm wide middle member. Members to be of aluminium with powder coating of black/Ivory shade. Thickness of the section of the aluminum sheet forming the members to be not less than 1.5 mm. Item includes providing 6 mm thick clear float glass of Modi / Saint Gobain / Asahi make, door closer, latch lock, handle in the aluminum door along with all accessories as may be required etc. Complete	33	SQM		

24	<p>Aluminium Door:- Providing and fixing glazed Aluminium Door of size 3' x 7' made up of 83.5mm wide vertical members, 85-90mm wide top and bottom members and 83.5mm wide middle member. Members to be of aluminium with power coating and of black shade. Thickness of the section of the aluminum sheet forming the members to be not less than 1.5mm. Item includes providing 6 mm thick clear float glass of Modi/ Saint Gobain/ Asahi make, door closer, latch lock, handle in the aluminum door along with all accessories as may be required. Item also includes providing Godrej/ Dorma/ Haffle make 100kg weight floor spring with 0.3 million cycles rating along with pivot of same make on top. Item includes providing wool pile/ weather strip on the un-pivoted vertical member of the door and a customized door handle of approved colour to fit on the aluminium sections etc. complete.</p>	8	SQM		
25	<p>False ceiling:- Providing and fixing plain non perforated metal sheet GI tiles Armstrong Grid False Ceiling of size 600mm x 600mm having ceiling sections at 600 mm center to center both ways duly fixed with screws. The grid work to be suspended from ceiling with hangers at every 600 mm center to center in both directions. The framework to be as per manufacturer's specifications. Item includes providing extra support for fixing light fixture etc. complete.</p>	10	SQM		
26	<p>Wall paneling:- Providing & fixing in position Aluminium Composite Paneling (ACP) with framing of aluminium tube sections of min 1.5"x1" and 20 gauge at a spacing of 2' center to center both ways. ACP to be of bright silver shade in 2' width panels or distributed equally. ACP sheets to be fixed to the frame 3 M make adhesive along with mirror screws . Joints to be finished with silicon based sealant. ACP sheets to be min. 3mm thick with aluminium foil thickness to be min. 0.25 mm on both sides. Item includes providing additional sections to fix indoor AC units which will be installed at the higher position.</p>	20	SQM		
27	<p>Back room partition:- Providing and fixing Partition for backroom made up of Aluminium Composite Panel (ACP) sheets only on the ATM side with framing of aluminium tube sections of min. 1.5" x 1" and 20 gauge at a spacing of 2' center to center both ways. ACP to be of bright silver shade in 2' width panels or distributed equally. ACP sheets to be fixed to the frame with 3M make adhesive along with mirror screws. Joints to be finished with silicon based sealant. ACP sheets to be min. 3mm thick with aluminum foil thickness to be min. 0.25mm on both sides. Item also includes providing a door of size 2' x 7' for the backroom made up of Aluminium Composite Panel (ACP) sheets only on the ATM side with framing of aluminium tube sections as specified above along with Godrej make heavy duty Lock, 3 numbers 3" SS hinges, handles etc. complete.</p> <p>Note:- Measurement of partition shall be only taken upto false ceiling level For the purpose of payment.</p>	5	SQM		
28	<p>Louvers:- Providing and fixing powder coated 1' wide Aluminium Louvers of approved shade in aluminum partition and door of backroom Including all accessories required for installation of the louvers etc. complete.</p>	1	SQM		

29	<p>Shutter Box:- Providing and fixing Shutter Boxing for rolling shutter made up of Aluminium Composite Panel (ACP) sheets only on the outer visible side with framing of aluminium tube sections of min. 1.5" x 1" and 20 gauge at a spacing of 2' center to center both ways. ACP to be of bright silver shade in 2' width panels or distributed equally. ACP sheets to be fixed to the frame with 3M make adhesive along with mirror screws. Joints to be finished with silicon based sealant. ACP sheets to be min. 3mm thick with aluminum foil thickness to be min. 0.25mm on both sides. Item includes providing trap door of required size in the bottom of the shutter boxing made up of Aluminium Composite Panel (ACP) sheets only on the outer visible side with framing of aluminium tube sections as specified above along with Godrej make heavy duty tower bolts, required numbers of 3" SS hinges, handles etc. complete. Item includes providing additional sections to fix LED down-lighters which will be installed at the required position.</p> <p>Note: Only front of boxing including trap door shall be measured for payment purpose and sides of the boxing shall not be measured for payment.</p>	15	SQM		
GRAND TOTAL (EXCLUDING GST)					