

BILL OF QUANTITIES (BOQ) FOR INTERIOR WORKS

MANTRALAYAM BRANCH - KURNOOL DISTRICT

S.No.	Description	Qty	Unit	Rate	Amount
1	<p><u>Full Height Partly Glazed Partitions with laminate finish and glass:</u> Providing and fixing metal stud dry wall partition with following specifications:</p> <p>a) The Partition will be either solid or partly glazed as per specific site conditions and drawings.</p> <p>b) Supporting system comprising of best locally available 51mm / 50mm x 35mm / 34mm x 0.5mm metal studs at 600mm c/c and 51mm / 50mm x 32mm x 0.5mm metal tracks at floor, middle, door and ceiling level with joints staggered to avoid through joints. The vertical members should touch the ceiling with horizontal ceiling channel at slab / beam bottom. The rate should also include necessary strengthening with studs / tracks or channels at doors and other openings.</p> <p>c) 12mm MDF Exterior Grade Board fixed on both sides with 25mm dry wall screws for the entire height of the partition except where glass panels are specified, covered with 1 mm laminates as per standards of SBI and as directed (Plain Blue, White or Veneer finish colours).</p> <p>d) 8 mm clear float glass with 85 mm X 18 mm around mdf Exterior Grade jamb and 12 mm X 12 mm MDF button beading on both sides of the glass to have neat finish as per directions etc. Complete.</p> <p>e) All exposed surfaces of MDF board members to have minimum two coats of zinc oxide white polish over a coat of primer.</p> <p>f) Rate to include cost of all material, labour, transportation,</p>	40	Sq.M		
2	<p>Low Height Glazed Partitions with laminate finish.</p> <p>Same as item 1 above, but for height of 1200mm from finished floor level, to a neat finish as per drawings and directions etc., complete and the following:</p> <p>(a) 12 mm thick MDF exterior grade beeding on top, & vertical surfaces of end partitions as per directions etc., complete.</p> <p>b) MDF board shall be covered with 1 mm Laminate (blue & white color as per standards od SBI). The partition to have 12mm Clear Float Glass fixed with SS " D " brakets, from 900mm level to 1200mm level as directed.</p>	35	Sq.M		

3	<p>Doors in Partitions:- Providing and fixing 35mm thick solid core flush shutter with 85mm x 18mm MDF Exterior Grade jamb around and 12mm x 12mm MDF Exterior Grade beading fixed 1mm Laminate as specified on both sides and 8mm clear float glass with 3M privacy film fixed as directed with 65mm x 18mm MDF Exterior Grade jamb around the glass opening and 12mm x 12mm MDF Exterior Grade beading for fixing of glass on both sides. The rate to include necessary hardware viz., door stopper, door buffer, pair of " H " type handles, Mortise Dead Lock and Euro Profile Cylinder - Key and Knob 70mm SS, 4 Nos. SS 2 ball-bearing hinges - (127mm x 76mm x 2.5mm) door closer (all of approved make and quality). All exposed surfaces of MDF Exterior Grade members, etc. shall be finished with ZINC oxide white polish, complete as directed.</p>	10	Sq.M	
4	<p>12 mm Toughened glass partition:- Providing, making and fixing in position Fixed 12mm toughened glass as fixed glass from Floor to available Ceiling level for Partitions. The glass is to be fixed with patch fittings and all the edges of the glass have to be polished for a smooth finish. The work includes cost of all materials, approved hardware, making necessary template before toughening of glass and fixing the same as per site conditions to a neat finished work as per drawings and directions etc., complete.</p>	4	Sq.M	
5	<p>Toughened Glass Main Door:- Providing, making and fixing in position Main Entrance Glass Work comprising of Door opening of approximate size 1800mm x 2250mm - 2400mm in two pieces, and Partition Doors of approximate size 900 - 1000mm x 2250mm - 2400mm. The entire work to be done as per site conditions with following specifications etc., complete as directed.</p> <p>Entrance door - Providing, fixing in position glazed entrance Double door and Single door with patch fitting or approved make (Double Door approx. Size: 1800mm - 1500mm x 2400mm - 2250mm and Single Door approx. Size: 900mm - 1200mm x 2400mm - 2250mm) using 12mm toughened glass edge polished. The Door to consist of Heavy Duty Floor spring or Dorma or equivalent, Upper Patch, Bottom Patch, Lock Keeper Plate, Euro Profile Cylinder (EPC), "H" Type Handle 32 x 600mm, Corner Lock and the side fixed glass to have 2 Nos. Bottom Patch and 2 Nos. Upper Patch for each door to a neat finish etc., complete as per drawing. The work includes cost of all materials, approved hardware, making necessary template before toughening of glass and fixing the same as per site conditions to a neat finished work as per drawings and directions etc., complete.</p>	10	Sq.M	

6	<p>Column Panelling:- Providing and fixing metal stud column panelling with following specifications: (a) Supporting system comprising of best locally available 51mm / 50mm x 35mm / 34mm x 0.5mm metal studs at minimum 600mm c/c and 51mm / 50mm x 32mm x 0.5mm metal tracks at floor, middle, lintel level and ceiling level with joints staggered to avoid through joints. The vertical members should touch the ceiling with horizontal ceiling channel at slab / beam bottom. The rate should also include necessary strengthening with studs / tracks or channels at doors and other openings.</p> <p>b) Column Panelling from floor level upto ceiling level to have 12 mm MDF board Exterior Grade covered with 1 mm approved laminate as directed by Bank's Engineer complete.</p> <p>c) All exposed surfaces of MDF Exterior Grade members to have minimum two coats of Zinc Oxide white polish over a coat of primer finish.</p> <p>d) All sections used should adhere to the manufacturers guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified sections. Length X height upto false ceiling will be measured for payment.</p>	5	Sq.M	
7	<p>Grid False Ceiling :- Providing and fixing in the true horizontal level false ceiling system of mineral Fibre Ceiling tiles .The suspension system shall be the 'Trulock Silhouette' revealed profile grid system with 15mm wide flanges incorporating a 3mm or 6mm central recess color black or white revealed Silhouette main runners and cross tees to have mitered ends with birds mouth notches to provide mitered cruciform junctions. Main runners to be spaced at 12mm c/c fixed by using 2mm pre straightened GI Wire.Main tee,rotary stitched of size 15mm x44mmx3600mm at every 1200mm c/c maximum and 1200mm cross tee of size 15mmx44mm x1200mm at every 600 mm c/c maximum and 600mm c/c cross tee of size 15mmx44mmx600mm at every 1200mm c/c. The tiles should have Humidity Resistance (RH) of 90% - 99%, Colour White, in module size of 600 x 600 x 16mm, suitable for Green Building application (DUNE SUPREME / DUNE OF ARMSTRONG MAKE - RADAR CLIMAPLUS / PIN PERF CLIMAPLUS OF USG BORAL / CELOTEX PIN / CELOTEX FINE FISSURED OF GYPROC). The work includes cost and conveyance of materials and labour charges includings. All Operational charges tools lifts and all heights etc. surfaces of the false ceiling should be with drop ceiling.Manufactures specifications to be strictly followed.</p> <p>No extra shall be payable for making cutouts and providing frame for cutouts of for making stagged ceiling. making complete as per the design. The rate shall be inclusive of all the necessary material,required</p>	90	Sq.M	

8	<p>Gyp Board False Ceiling:- Providing, supplying, and fixing in position of Gypsum Board False Ceiling as per manufacturers specification and instructions with 12.5 mm thk board.Gypboard Screw- fixed to the underside of suspended G.I grid.G.I grid should be constructed and suspended from the main ceiling as per the manfactures instructions and as per the specifications using original Co. Specified framework sections G.I24 Guage the Gypboard should be fixed to G.I Grid with 25mm long Dry wall Screws. The Gypboard to be used should be12.5mm thk tapered edge boards.the boards should be taped and filled from underside to give smooth, seamless ceiling. The rates should include necessary additional ceiling sections and intermediate channels openings for light fixtures, vertical drops offsets etc. Additional Intermediate Channels should be fixed to strap hangers for additional support to prevent strap hangers from buckling, swaying at every 1200mm. Item to be completed in all respects including necessary sleeves for ducts finishings of joints cutouts supports for light fixtures A.C grills speakers etc. applying of paint to the ceiling of two coats luppum and one coats of primer and two coats of royal lemulsion paint of approved colour to suit the interiors of the bank, making complete as per the design.The rate shall be inclusive of all the necessary material, required hardware, labour, transportation, necessary for the complete execution of the item.</p>	60	Sq.M	
9	<p>Storage Unit:- Providing, making and placing in position Storage Units of required height made in 18 mm MDF Exterior Grade Board to all members except top which shall be 25mm block board. The top of 25mm Block Board to have extra thickening with 18mm x 50mm MDF Exterior Grade Board and front vertical facia to have 12mm x 43mm MDF Exterior Grade Board lipping and the front facia and remaining all exposed faces to have 1mm Laminate as specified. as specified and all unexposed faces to have 0.8mm Laminate, all other exposed surfaces of MDF Exterior Grade members to have Zinc Oxide white polish and all necessary hardware viz., 'W' or wing hinges, locks, handles, tower bolts etc., and MDF Exterior Grade beading 36mm x 36mm at top and MDF Exterior Grade edge lipping 18mm x 12mm etc., as per drawings and directions etc., complete.</p>	10	Sq.M	

10	<p>BM Table:- Providing, making and placing in position Executive Table and Side Table of approximate size 1950 mm x 900mm x 750mm + side table 1200mm x 450mm x 750mm with following specifications.</p> <p>a) Main Table and side Table top and to be made in 25mm block board with 1 mm laminate of approved shade & design and the verticals towards the modesty panel. The modesty panel to have 18mm MDF Exterior Grade Board clad with 1mm Laminate as specified.</p> <p>(b) The " L " shaped table top of 25mm Block Board to have extra thickening with 18mm x 50mm MDF Exterior Grade Board and front vertical facia to have 12mm x 43mm MDF Exterior Grade Board lipping covered with 1 mm laminate of approved shade & design for the entire table top and the front facia and remaining all exposed faces to have 1mm Laminate as specified.</p> <p>(c) All other members to be with 18mm MDF Exterior Grade Board and all exposed faces of the table to have 1mm Laminate as specified above to be used.</p> <p>(d) All the edges of 18mm MDF Exterior Grade Board to have 18mm x 12mm MDF Exterior Grade edge lipping. (e) One readymade CPU mobile pedestal, One Molded Key Board Tray with channels and one Ready Made Modular Foot Rest - 400mm x 350mm x 65mm. etc.,</p> <p>f) One Three Drawer Unit made with 18mm MDF Exterior Grade Board and 12mm MDF Exterior Grade Board. The unit to have one vertical filing drawer at</p>	1	Each	
11	<p>Other Officers Table Size 1650 X 750 X 750 mm side table 1050 X 400X 750 mm :- Same as above item no.10 bur for size.</p>	2	Each	

12	<p>Grahak Mitra:- Providing and Fixing GRAHAKMITRA/TECHMITRA table of size 2400 mm x 750 mm x 1200 mm with following specifications:</p> <p>a) The Table Top shall be made with 25 mm thk block board or BWR ply with 6mm thk CORIAN TOP as per the Drawing b) The sides (Verticals) shall be with 25 mm thk BWR Ply in Varied ht with 6 mm thk CORIAN finish on all the Exposed surfaces and 1mm thk laminate on all internal surfaces per the drawing.</p> <p>c) Front Modesty Panel shall be with 25 mm thk BWR ply with 6 mm thk WHITE CORIAN finish and with AQUA BLUE SHADE GLASS in varied ht as per the Drawing.</p> <p>d) The Table Front Modesty Panel shall be made with provision for LED lighting at skirting lvl as per the Drawing e) The Table shall be provided with Drawer unit Comprising of 3 nos of sliding drawers with sleek Telescopic channels, Handles ,locks and Necessary Hardware,ss cabel manager, required as per the Drawing The Table shall be provided with Moulded CPU Trolley with castors and Moulded Key board Tray with Telescopic Channels.</p> <p>FOOT REST in CRCA sheet: Ergonomic Footrest Angle Adjustable Promotes Stress Free Posture Slip resistant surface Reduces pressure on the back of the thigh Platform Size : 445mm (W) x 295mm (D) Anti termite solution to be sprayed before using the Ply in the work and making complete as per the design and drawing.The rate shall be inclusive of all the necessary material,required hardware, labour, transportation,</p> <p>necessary for the complete execution of the item.</p>	1	Each	
----	---	---	------	--

13	<p>SW Counters:- Providing, making and placing in position Single Window Counters along with necessary partitions (The partititions will be measured and paid under Low Height partitions) with following specifications:</p> <p>a) The overall size of each Single Window Counter to be 1500 mm - 165000mm x 900mm - 975mm x 750mm + 1050mm x 450mm x 750mm.</p> <p>(b) Table top of main table and side table to have 25mm Block Board to have extra thickening with 18mm x 50mm MDF Exterior Grade Board and front vertical facia to have 12mm x 43mm MDF Exterior Grade Board lipping cladded with 6mm thick acrylic solid surface for the entire table top and the front facia and remaining all exposed faces to have 1mm Laminate as specified. The acrylic solid surface to continue in the front side with curvature from the front table top to the modesty panel in front with cove lighting provision.</p> <p>(c) All other members to be with 18mm MDF Exterior Grade Board / 2 Nos. of 6mm Flexi Plywood in curvature (which should be achieved with a frame work of 50mm x 50mm sal wood frame to be fixed from the front modesty panel / apron and the bottom of this niche to have provision of cove lighting with LED strips) and all exposed faces of the table to have 6mm thick acrylic solid surface as specified in the drawing to be used.</p> <p>(d) All the edges of 18mm MDF Exterior Grade Board to have 18mm x 12mm MDF Exterior Grade edge lipping. (e) One</p>	6	Each	
14	<p>12mm Glass Divider Providing, making and fixing in position 12mm thick toughened clear float glass in the front side of half height partitions of Single Window Counters of approximate size 1250mm x 400mm - 100mm in tapered shape. All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets. The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and diretions etc., complete. Stickers with blue colour 3 M film as directed.</p>	6	Each	
15	<p>12 mm glass for transanction top:- Providing, making and fixing in position 12mm thick clear float glass in the front side of approximate size 1650mm x 450mm with a central cut out of 200mm x 175mm. All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets. The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and diretions etc., complete.</p>	6	Each	

16	<p>Wall mounted writing desk:- Providing, making and placing in position Wall Mounted Writing Desk 750mm x 300mm x 600mm with following specifications. (a)) The entire unit is to be made with 18mm MDF Exterior Grade Board clad with 1mm Laminate. (b) The Writing Desk to have 12mm thick toughened clear float glass with 25mm champered bull nosing around at top fixed with SS supports. (c) All members to be with 18mm MDF Exterior Grade Board and all exposed faces to have 1mm Laminate as specified. (d) All the edges of 12mm / 18mm MDF Exterior Grade Board to have 18mm x 12mm MDF Exterior Grade edge lipping. (e) All the unexposed faces to have 0.8mm Laminate. The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.</p>	1	Each		
17	<p>Corian Finish:- Providing & fixing cladding with 'Corian' finish using Acrylic sheets of 6 mm thickness on top of tables, facia storage units etc. where directed. The rate to include all materials, labour, transportation, wastages etc. complete.</p>	5	Sq.M		
Total (excluding GST)					
Rupees					
Contractors Signature					