

**INTERIOR FURNISHING WORK FOR STATE BANK OF INDIA FOR CCGRO BRANCH,
AT 11TH FLOOR, BVR EK COMPLEX ELLISBRIDGE, AHMEDABAD**

BILLS OF QUANTITIES

(NOT TO BE FILLED BY THE BIDDER)

Sr. No.	Description	Quantity	Unit
---------	-------------	----------	------

Note : Rate should be inclusive of material,labour,tools, machinery, scaffolding, final disposal of debris ,cleaning cutting wastage etc. all taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the time of payment of Bills

Work in the carried out at 11th floor of the Building

[A] FURNISHING WORK

2 RECONDITIONING OF EXISTING TABLES & SIDE STORAGE TABLE & STORAGE CUP BOARD

Reconditioning ,Refixing and alignment of work station Tables,Side Tables, cup board ,Misc.and Other furnitures to be used from existing premises including polishing and minor repairs. Contractor must visit site to assess work involved before quoting.

Removing refixing and realignment of existing Tables

- i) Reconditioning of existing Tables/ Side Table, etc. removing existing laminate by Hot Iron and fixing 1 mm thick new laminate as per approved shade and design instruction by Architect
- ii) Providing and fixing with 1.0 mm thick laminate as apron on 3 sides frosty white laminate and High gloss laminate on Top as directed complete.
- iii) Repairing of drawers and shutter and painting /polishing complete as directed. Replacing of approved make multipurpose lock & handle/sliding channels etc.
- iv) Rate also including Removing existing furnitures etc and Transporting the same to new location as directed complete.

[a] Table Size 8'-0"x 3'-0" For GM-1	1	NO
Side Credenza Size 4'-6"x1'-6"x2'-6" height	1	NO
[b] Table Size 7'-3"x 3'-0" For GM-2	1	NO
Side Credenza Size 4'-6"x1'-6"x2'-6" height	1	NO
[c] Table Size 6'-3"x 2'-9" For AGM-1 to 4	4	NO
Side Credenza Size 3'-6"x1'-4"x2'-6" height	4	NO
Back side Storage Cup Board Approx. Size 6'-3"x 1'-4" x 3'-0" ht.	4	NO
[d] Table Size 5'-9"x 2'-6" For CM-1 to 5	5	NO
Side Credenza Size 3'-3"x1'-4"x2'-6" height	5	NO
[e] Table Size 5'-3"x 2'-6" For OFFICER	16	NO
Side Credenza Size 3'-3"x1'-4"x2'-6" height	16	NO
[f] Table Size 4'-9"x 2'-4" For PA & VEGELANCE OFF & Security	4	NO
Side Credenza Size 3'-3"x1'-4"x2'-6" height	4	NO
[g] Reinstallation & Reconditioning of Server Room Table with modification & repairing etc complete.	1	NO
[h] MEETING ROOM TABLE With Top glass Approx. Size 8'-0" x 4'-0"	1	NO
[i] MEETING ROOM TABLE With Top glass Approx. Size 7'-0" x 3'-6"	1	NO

(NOT TO BE FILLED BY THE BIDDER)

Sr. No.	Description	Quantity	Unit
3	<p>P & F STORAGE CABINATE Supplying and providing storage cabinet with High gloss laminate on Top & 35 mmx6mm thick Burma Teak beading on Edges with Polish. and 1.00 mm thick frosty white laminate on Front shutter. Laminate to be provided only on front,side visible surfaces Size : Depth 1'-4" ,. 2'-6" ht. having openable shutter as directed. storage Cabinet shall be made from 18mm thick commercial ply wood for Top with High gloss laminte finish and 18mm thick ply wood for verticle, shelves, shutters and 6mm commercial plywood for backing with 1.0 mm thick High gloss laminate on all exposed surface. with verticle (at 3'-0" c/c) shelves at 1'-3" c/c Openable shutters in 18mm thick commercial ply wood with all S.S hinges, towers bolts, powder coated handle, ball catches, S.S approved make (group lock) multi purpose lock complte. Edges to be finished with teak wood lipping etc. including all internal surface to be polished/painted etc. complte. Laminate to be provided only on over visible surface All the surface without laminate shall be Polished/ synthetic enamel paint of approved shed Front surface area shall be measured for payment purpose.</p>	36	SQMT
3[a]	<p>RECONDITIONING OF EXISTING STORAGE CUP BOARD Reconditioning of existing Storage cup board, etc. removing existing laminate by Hot Iron and fixing 1 mm thick new laminate as per approved shade and design instruction by Architect Providing and fixing with 1.0 mm thick frosty white laminate as apron on front sides shutter and High gloss laminate on Top as directed complete. Repaing of drawers and shutter and painting /polishing complete as directed. Replacing of approved make multipurpose lock & handle,stopper etc. Rate also including Removing existing Storage cup baord and Transporting the same to new location as directed complete.</p>	12	SQMT
4	<p>P/F ELECTRIC CUB BOARD Providing and fixing Electric cup board using 18mm thick bision panel for verticale and shelves and aluminium framing of 50x25x1.20mm thick with 6mm thick bision panel on both side for shutter with 1.0 mm thick laminate on all exposed surface and polishing/ synthetic enamel paint on all internal surface. shutter with approved make lock handle, hinges,ball catches P&fixing S.S Perforated jali shall be provided in shutter etc.complete as directed, depth of cup board 1'-3".Shutter height up to 7'-0" and above fixed Type up to false ceiling bottom</p>	5	SQMT
4[a]	<p>P/F PANTRY PLATFORM CUB BOARD SHUTTER Providing and fixing cupboard shutters below pantry platform using 1 1/2" x 2 1/2" T.W members for frame, 18mm Tk plywood with 1.0mm lamiante for shutters. Providing 1/2" th T.W beading all around shutter. Providing S.S hinges, Handles, stoppers and magnetic catch as directed. All the surface shall be polished/ synthetic enamel paint as directed complete.Providing and fixing 0.60mm thick balancing laminate on internal shutter surface</p>	4	SQMT

(NOT TO BE FILLED BY THE BIDDER)

Sr. No.	Description	Quantity	Unit
5	<p>P/F BOTH SIDE LAMINATE SOLID/ PARTLY GLAZED FULL HEIGHT PARTITION</p> <p>Providing and fixing both sides laminate full height partly glazed partition using 50mm x25mm x 1.50mm thick Aluminium members in a maximum grid of 2'-0" x 2'-0" P/fixing 12mmthick MDF Board Exterior Gare on both sides,1.0mm laminate of approved make shall be fixed on MDF board, Providing 5.0/8.0 mm th float glass as directed in the partition. Providing door shutter using 30mm thick flush shutter with both side laminate and fixing 6 mm thick glass shall be provided in door shutter providing 5" Long 3 Nos stainless steel hinges/doorstop shall be provided as directed. Godrej Mortice lock shall be provided in door shutter Steam beach Beading shall be provided for fixing glass. All visible members if not laminated shall have lacquer polished as directed.</p> <p>For purpose of payment partition height up to bottom of false ceiling only shall be measured and paid . No extra payment shall be made for members going up to slab/beam bottom</p>	272	SQMT
5[a]	<p>P/F LOW HEIGHT BOTH SIDE LAMINATE PARTITION</p> <p>Providing and fixing low height partition using 50mm x25mm x 1.50mm thick Aluminium members maximum in grid of 2'-0" x 2'-0" P/fixing 12mm Thick MDF Board Exterior Garde of approved brand on both side of aluminium skeleton and fixing 1.0 mm thick laminate of approved shed on both sides. Fixing 1.0 laminate in a shape as directed shall be fixed on all exposed edges. Fixing 12mm th free clear float glass as directed. Applying polish on exposed steam beach members with lacquer polished edges as directed complete. Laminate to be provided only on visible surface</p>	53	SQMT
6	<p>Providing and fixing Isolated flush door shutter (Partly Glazed and Partly Laminate) with frame as follows.</p> <p>Providing and fixing 4"x2" steam beach member for frame and Flush door shutter made out of 31 mm thick flush door with 6 mm thick clear float glass vision panel secured with 12 mm thick steam beach beading, 31x 12 mm thick steam beach periphery patti around shutter edges, 1 mm thick laminate on both sides, 35x12mm thick steam beach stopper patti on frame including 3 Nos 5" long SS hinges with countersunk SS screws, Approved make Ded Lock, S.S Handles,150 mm long Door stoppers, doorstop of approved make etc. all exposed surface /edges not laminated be provided with lacquer polish complete as per drawing & instructions</p>	10	SQMT
6[a]	<p>Providing and fixing Isolated solid flush door shutter with Aluminium Frame and both side Bison panel for UPS Room</p> <p>Providing and fixing aluminium frame of 65mm x 38mm x 1.5 mm thick and door shutter made out of 50x25x1.5mm thick framing at maximum 1'-6" C/C both way with 6 mm thick Bison Panel on both side with painting.Providing 6 mm thick clear float glass vision panel secured with 12 mm thick steam beach beading, 31x 12 mm thick steam beach periphery patti around shutter edges, aluminium stoper patti on frame including 3 Nos 5" long SS hinges with countersunk SS screws, Approved make Ded Lock, S.S Handles,Door stoppers, doorstop of approved make etc. complete as per drawing & instructions</p>	2	SQMT

(NOT TO BE FILLED BY THE BIDDER)

Sr. No.	Description	Quantity	Unit
7	GLASS DOORS AND PARTITIONS		
7[a]	P & F FULLY GLAZED DOOR WITH PATCH FITTINGS for Main Entrance Door Providing & Fixing fully glazed main door at the main entrance and ATM. The Item includes fixing of 12 mm th. Toughened glass with the help of top patch & bottom patch fittings . The door will have patch lock, pti pivot, floor spring & 600 mm long handles both sides, (Approved Make), fixed with the glass by making necessary cutouts & holes. The glass edges shall be polish on all sides. The entire door shall be erected in complete line & level. The door will have S.S brush finish Signage for pull & push. The patch fittings (Approved make) shall be of aluminium with s,s, matt finish coating & signage shall be of kich make. The entire door, complete in all respect should be installed in positions as req.	8	SQMT
7[b]	Same as above item but P & F FULLY GLAZED PARTATION With Patch Fitting for front side Main Entrance [FIXED PORTION]	3	SQMT
8	Wall panelling with laminate finishing for wall and Piller etc Providing and laying panelling on walls & pillars having 12 mm thick MDF Board exterior grade and 1.0mm th laminate fixed on wall & pillars with Aluminium. framing of 25mmx25mmx1.20mm thick at maximum 2'-0" c/c bothways on wall and pillar etc complete as directed. panelling as per design and instruction of Architect. .	78	SQMT
8[a]	Creating Box for fixing AC machine and concilinding of copper and drain pipe and around front side main entrance door Above and Side jams using 18 mm thick BWP plywood with 1.00 mm Thick Laminate shall be used with framing of aluminium framing as per requirement and drawing etc complete as directed.	17	SQMT
8[b]	P/A TEXTURE PAINT Providing and applying Texture paint of Heritage/Berger brand on internal walls. Rate includes surfaces preparation, applying necessary coats of paint to obtain Uniform and even finish. Rate also includes applying paint of approved shed etc. complete.	20	SQMT
8[c]	P/A WALL PAPERS on wall Providing and applying Wall paper approved by Architect / Bank's Engineer, wall paper basic price of Rs 120=00 Per Sq.Ft	10	SQMT
8[d]	P & F SOFT BOARD Providing and Fixing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6mm thick commercial plywood on back side and 12mm th soft board on front. Fixing cloth of selected design of Basic rate of Rs. 250 per mt.steam beach member shall have polish as directed complete.	3	SQMT
8[e]	Extra for providing and fixing aprox. 3.5 mm thick veneer of basic rate of Rs.180=00 per Sft instead of Laminate for Table , Side Table, Storage cup board, wall panelling etc in approved pattern as per drawing and directions including 3 coats of melamine spray finish polish complete.	15	SQMT

(NOT TO BE FILLED BY THE BIDDER)

Sr. No.	Description	Quantity	Unit
9	Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surfaces as per drawing & direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification.	25	SQMT
10	Providing and fixing "Dorma/Ozone" or equivalent make door closure. etc complete	19	NO
11	Supplying and fixing Roller Blind Blackout of Vista make or approved make with selected fabric of approved design and shed. (Basic Price of Rs 135=00 Per Sq.Ft)	51	SQMT
12	Reconditioning of existing Sofa with Arm Rest Reconditioning of existing sofa by changing Upholstry of Rs. 650 per mt. Rubber form (40 density sleepwell - 4" thick in seat and 3" thick in back)backing cloth replacing any broken polishing of wooden members complete as directed. Contractor must visit site before quoting. (Rate Also including shifting from existing premisses to new primisses)	5	RMT
12[a]	Same as above but withiout arm rest Sofa	13	RMT
13 FALSE CEILLING WORK			
13[a]	P/F GYPSUM BOARD FALSE CEILLING Providing and fixing Gypsum board 12.50 mm thick false ceiling in steps and design using Original Indian Gypsum board with original GI sheet section of Gypsteel ULTRA (Gypsteel Ultra shall be used) supporting system in line and level. Finishing the surface and applying 3 coats of Plastic emulsion paint as directed complete. Entire work to be done as per standard specifications of Saint Gobin Gyproc India. After completion of work certificate from Saint Gobin Gyproc Company shall be submitted along with bill stating that work is satisfactorily completed as per their specification Note : (1) Rate includes making necessary cutouts for lighting fixtures (2) Pattas of Less than 1'-0" shall be measured in Sqft and not in Rft and paid in Sqft. (3) Only finished visible surface area shall be measured for payment.	290	SMT
13[b]	Providing and Fixing of Mireral Fibre Acoustical Suspended ceiling system with FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be duceducted for payment purpose After completion of work certificate from Company shall be obtained that work is carried out as per their specifications	208	SMT

(NOT TO BE FILLED BY THE BIDDER)

Sr. No.	Description	Quantity	Unit
14	Removing of existing Fire proof record room door and reinstalling same at new premisses with necessary civil work etc complete as directed	1	JOB
[B] BUY BACK OF OLD FURNITURE			
Less Dismantallating of entire furniture and fixtures from existing premisses and buy back of furniture not required by Bank as follows (Old Premisses at CG Road Navrangpura First Floor & Secord Floor)			
1	L Type Work Station with Low height Partition (5'-3"x4'-0")	9	NO
2	Work station straight	10	RMT
3	Wooden Table Approx Size 5'-0"x 2'-6"	4	NO
4	Storage cup board up to 7'-0" height	35	SQMT
5	Low Height Storage cup board	25	SQMT
5[a]	Electrical wooden Cup Board	7	SQMT
6	Wooden Partition up to 7'-3" ht	175	SQMT
7	Low height Wooden Partition up to 4'-6" ht	30	SQMT
8	12mm thick Toughend Glass Main entrance door 2 Nos	7	SQMT