



## PRICE BID

**Name of the Work :- Facelifting of 6th floor corridor, chairman's room and dinning area at SBI LHO building, Bhubaneswar Tender ID: BHU201905003**

Sl. No	Item Description	Unit	Quantity	Rate (Rs.)	Amount (Rs)
1	<b>Wooden Flooring</b> Providing & Laying in position 8mm tk laminated wooden flooring of approved shade of square foot /pergo make of size 1292mmx192mm having smart lock tunge and groove joints to secure long lasting joint. The edges of tounge and groove of planks duly pre impregnated with paraffin. The approved decor planks to be placed on underlay of 0.2mm tk alkali resistant polyethylene sheet -density 935 kg/m3 to resist any moisture movement from the sub floor and secure flating floor installation.Ref: Pergo Red Oak	Sqm	123.79		
2	<b>Luzon Blinds</b> Providing and fixing best quality Luzon blinds of approved brand and make or approved design, colour(s) and quality as per specifications and directios of the Engineer-in-Charge with all labour, tools & tackles, hardwares and all other materials complete.Ref make: Marvel LET 1502	Sqm	92.63		
3	<b>Wall Paper</b> Providing & fixing Living wall paper (Alfa, Luxe, Patterns specification) gravure printed-pre-trimmed-washable -strippable of approved shade and design including preparation of wall surface, fixing with sutibale glue as per the manufacturer specification and as per direction of EIC. Ref make: Alfa3717,Alfa3704,Luxe6718	Sqm	184.07		
4	<b>Wooden Panelling With Vineer</b> Providing & fixing Wooden Panelling on where ever required wall.framing shall consist of aluminium section 50mm x 25mm @ 600mm c/c both ways Horizontaliy & verticallywith on the wall, This framing would be cover by 6mm thkcomm. ply Finished in approvedVineer finished in melamine polish.Wooden moulding, lipping etc as directed by bank Or EIC. Basic cost: Rs.130/- per sft	Sqm	20.39		

<b>5</b>	<b>Glass door</b> Providing and fixing 12 mm thick frameless Glass door shutter of approved brand and manufacture, including providing and fixing top & bottom patch fittings and making necessary holes etc. for fixing required door fittings, all complete as per direction of Engineer-in-charge including required (Door handle, floor spring, lock and stopper to be paid separately). All fittings shall be of dorma/ozone/haffelle / Godrej make.	Sqm	3.98		
<b>6</b>	<b>Plain Glass Shelves &amp; Mirror</b> providing & fixing 6mm thick of approved make clear mirror ( 1st Quality) or glass for shelves of storages .	Sqm	5.28		
<b>7</b>	P & F Frosted Glass Film as per approved brand and pattern	Sqm	4.81		
<b>8</b>	<b>Floor Spring</b> Providing and fixing floor spring of Godrej/ Dorma two speed in floors for fixing flush doors. Necessary pivot shall be provided at bottom and top so that the flush door shall be operated. The cost includes cutting and making the good of the floor etc complete as directed.	Nos	1.00		
<b>9</b>	<b>Vitrified Shined tiles flooring (1200 x 600mm)</b> Providing and laying 1200mm x 600mm nano polished double charged vitri-fied shine tiles of approved make, Shade & pattern as per approved by engineer in charge in CM 1:4 in proper line & level with out spacers for maintaining the grid lines. Rate shell be inclusive of providing and laying necessary pcc and cement mortar and joint filling coumpounds. all complete, including cost of all materials, labour, T&P etc. required for the work.Ref make: Clay- Paradise Crema	Sqm	22.79		
<b>10</b>	<b>Granite Work</b> Providing and laying 19mm thick Granite slab of approved quality on steps, window sill, door sill as required area with necessary joint filling 7 backing materials . The edge shall be moulded and machine polished with anti skid strip. Rate shall be including cost of all labour and material.	Sqm	0.56		
<b>11.A</b>	<b>Vineer Polish Work</b> Providing and applying Melamine polish of approved make quality & shade as per engineer in charge direction on wooden or metal surface.the rate shall be include scrapping , levelling & preparing the surface	Sqm	418.34		
<b>11.B</b>	<b>Vineer Polish Work</b> Providing and applying Melamine polish of approved make quality & shade as per engineer in charge direction on wooden or metal surface.the rate shall be include scrapping , levelling & preparing the surface	Rmt	31.48		

<b>12</b>	<b>Emulsion Paint</b> Painting with Emulsion paint semi gloss of approved shade & colour on wall/ gypsum partition/gypsum ceiling or equivalent make with two coats of putty, two coats of approved primer and three coats of approved lister paint including preparation of surface, scrapping, sand papering scaffolding all materials labour etc complete	Sqm	930.68		
<b>13</b>	<b>Enamel Paints</b> Providing and applying 1st quality with two coats of Enamel paint over a coat of Primer of approved make quality & shade. The rate shall include with scrapping, leveling, labour & other necessary materials.	Sqm	11.46		
<b>14</b>	<b>Putty &amp; POP Work on internal surface</b> Providing and applying plaster of wall putty or paris putty of 1mm thickness over plastered surfaces & Gypsum false ceiling to prepare the surface even and smooth complete.	Sqm	930.68		
<b>15</b>	<b>Gyp False Ceiling Repair</b> Repairing Gypsum board false ceiling & if required fixing gyp. board made from 12.5 mm thick paper reinforced gypsum board sheets the Gypboard should be fixed to G.I. grid with 25 mm long Drawali Screws. The 'Gypboard' to be used should be 12.5mm thick tapered edge boards. The boards should be taped and filled from underside to give smooth, seamless ceiling. The rate should include necessary additional ceiling sections and intermediate channels openings for light fixtures	Sqm	751.10		
<b>16</b>	<b>Armstrong Ceiling</b> Supply and installation of (Micro Perforated) Armstrong make Acoustical Mineral Fiber Ceiling Panels of size 600 X 600 X 15 mm, ANF tegular edge laid on 15 mm exposed grid system, main tee are double web design roll formed from hot dipped galvanized steel with prepainted steel capping, Main Tees are 3600 X 38 mm long with Base Metal thickness of 0.38 mm, has cross Tee slots at 100 mm centres and suspension holes in the bulb conveniently located at every 52mm, suspended with CL 315 Clip with heavy duty plugs to be suspended with	Sqm	3.54		
<b>17</b>	<b>Dismantling Brick work</b> Dismantling of existing brick work/ RCC Members as directed by the EIC ..... The surface should be made smooth by necessary plastering, painting and finishing.	Sqm	8.44		
<b>18</b>	<b>Dismantling Vertical blinds</b> Dismantling of existing Vertical blinds as directed by the EIC .The surface should be made smooth by necessary plastering, painting and finishing.	Sqm	92.63		

<b>19</b>	<b>Dismantling Carpet flooring</b> Dismantling of existing Carpet Flooring as directed by the EIC .The surface should be made smooth by necessary plastering, painting and finishing.	Sqm	61.96		
<b>20</b>	<b>Dismantling Wall &amp; Floor Tile</b> Dismantling of existing Tile On wall & floor as directed by the EIC . The surface should be made smooth by necessary plastering, painting and finishing.	Sqm	40.26		
<b>21</b>	<b>Dismantling Storage cabinet</b> Dismantling of existing wooden wall panelling , partition & Storage cabinet as directed by the EIC . The surface should be made smooth by necessary plastering, painting and finishing.	Sqm	4.70		
<b>22</b>	<b>Brick work</b> 1st class brick work on wall in cement mortar including racking out joints and curing complete as directed in super structure above plinth up to 1st floor level ( protruding M.S rod/Tor steel of column to be embeded in cement mortar and will be measured and paid separately)	Sqm	2.80		
<b>23</b>	<b>Plaster Work</b> Providing & laying 16mm thick cement plaster in proportion 1:6 to all levels to surface of Brick /RCC walls & ceillings in single coat . Finished rough to receive plaster of paris levelling coat. The rate shall be include necessary scaffolding Curing etc complete	Sqm	25.98		
<b>24</b>	<b>SANITARY FITTINGS</b>				
<b>i</b>	Supply installing & fixing of Floor Mounted EWC/Wall mounted EWC including matching Standard Seat cover, angle cock etc complete. Ref make: Jaquar ACS WHT 87951	Each	1.00		
<b>ii</b>	Supply installing & fixing of Concealed cistern JCS wht 2400 FS	Each	1.00		
<b>iii</b>	Supplying all material, labour T&P and Fixing <b>Cabinet Wash basin</b> at toilet . All complete as per specification and direction of the Engineer- In-Charge. LC624802222 L CUBE vanity Basin.	Each	1.00		
<b>iv</b>	Supplying all material ,labour T&P and fixing <b>Flat black large urinal</b> .All complete as per specification and direction of the Engineer-in-charge. Parryware New magnum CO 583	Each	1.00		
<b>v</b>	Supplying all materials, labour, T&P and fixing standard size <b>Paper Holder</b> with flip recessed type . as per specification and direction of the Engineer- In-Charge. Jaquar AKP 35753	Each	1.00		

<b>vi</b>	Supplying all material, labour T&P and Fixing <b>Bottle Trap</b> Waste at Urinal Waste All complete as per specification and direction of the Engineer- In-Charge. Jaquar ALD CHR 769L	Each	1.00		
<b>vii</b>	Supplying all material, labour, T&P and fixing standard size <b>Two way Bib cock</b> with flange of jaquar as per specification and direction Of Engineer-in-charge. Jaquar ALI 85041	Each	1.00		
<b>viii</b>	Supplying all material, labour T&P and Fixing standard size <b>Push cock</b> in Urinal . All complete as per specification and direction of the Engineer- In-Charge. Jaquar PRS 077	Each	1.00		
<b>ix</b>	Supplying all material, labour, T&P and fixing standard size 15mm <b>Angular Stop cock</b> of jaquar as per specification and direction Of Engineer-in-charge Jaquar ALI 85053	Each	1.00		
<b>x</b>	Supplying all material, labour, T&P and fixing of <b>Sensotronic Piller Cock</b> of jaquar with complete kit as per specification and direction Of Engineer-in-charge Jaquar SNR CHR 51011	Each	1.00		
<b>xi</b>	Supplying all material, labour T&P and Fixing standard size <b>Towel Rack</b> of Jaquar AQN 7781 600mm as per specification and direction of the Engineer- In-Charge.	Each	1.00		
<b>xii</b>	Fixing 45" x 30" <b>Mirror</b> at Wash basine top as per specification and direction of the Engineer- In-Charge.	Each	1.00		
<b>xiii</b>	Supplying all material, labour T&P and Fixing standard size <b>Glass Self</b> of AQN-7751 600mm as per specification and direction of the Engineer- In-Charge.	Each	1.00		
<b>xiv</b>	Supplying all materials, labour, T&P and fixing standard size <b>Health Facuit</b> of Jaquar as per specification and direction of the Engineer- In-Charge.Jaquar ALD 577	Each	1.00		
<b>xv</b>	Providing and fixing circular type stainless <b>Steel jali</b> (grating) with hole for floor as per specificationOf Engineer-in-charge	Each	2.00		
<b>xvi</b>	Providing and fixing <b>110 mm dia</b> Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing	Rmt	2.00		
<b>xvii</b>	Providing & fixing <b>25 mm dia</b> chlorinated Polyvinyi chloride (CPVC) pipe with refilling & testing of joints complete as per direction of Engineer-in-charge	Rmt	10.00		
<b>xviii</b>	Providing & fixing <b>15mm dia</b> chlorinated Polyvinyi chloride (CPVC) pipe with refilling & testing of joints complete as per direction of Engineer-in-charge	Rmt	3.00		
	<b>TOTAL AMOUNT</b>				
	<b>Note: GST shall be paid extra as applicable</b>				