

BOQ FOR SITC OF AIR CONDITIONERS- BRANCH PREMISES, RBO-II, A.O. KANPUR:

S.NO.	ITEM DESCRIPTION	Qty	Rate	Amt.
1.	Supply , installation, testing & commissioning(SITC) of 1.5TR high wall 3 star (highest star rating in this segment), BEE rated, mounted type air conditioner, wireless remote controlled with auto restart feature complete in all respect with indoor, outdoor unit, <u>copper condenser & copper cooling coil</u> interconnecting piping, wiring/ installation / drain pipe etc. (Upto 3 meters length). Item should also include 4 KVA hi/lo cut off, TDR relay start stabilizer, wall mounted,voltage range 140-280V, Complete in all respects. Stabilizer: <u>Make of Air Conditioner:</u> Voltas/Bluestar/Carrier/Hitachi/Daiken <u>Make of Stabilizer:</u> Servel/ V Guard /Stambh/Inmag/Marc/Sen & Pandit/Microtek	04 N0s		
2	Additional refrigerant interconnecting copper piping (both) with insulation, drain pipe, wire mesh cover throughout for protection for 1.5TR high wall ACs. Item is for interconnection piping additional to 3 meters which is included in item sl. No2.	20 Mtrs		
3	Suitable angle iron stand for 1.5 Tr. split AC made of minimum section 35x35x4 mm. duly painted with one coat of primer and two coats of enamel paint. The stand will have to be grouted /anchored to wall/ ledge in a safe manner to suit site conditions. (as per sl 2.)	04 Nos		
4	Electrical cabling from indoor to outdoor unit with suitable PVC copper wire for 1.5/2TR high wall ACs. Item is for cabling additional to 3 meters included in item sl. 2.	45 mtrs		

PLACE:

Signature and Seal of Bidder

DATE :

5.	Comprehensive Annual Maintenance Charges of 1.5 Tr. AC (Quote exclusive of GST which will be payable additionally at prevalent rates, if payable. AMC expenditure for three years shall be considered for comparison of tenders to arrive at L-1)	4 No.	Quote per AC per annum rate Amount should be calculated as under: per AC per annum rateX4 (for 4 no. AC) X3 (for three years AMC expenditure)	
GRAND TOTAL				

PLACE:

Signature and Seal of Bidder

DATE :