



**SBI INFRA MANAGEMENT SOLUTIONS PVT.LTD.**

**CIRCLE OFFICE, THIRD FLOOR, STATE BANK OF INDIA, SYNERGY BUILDING, C-6, G-BLOCK, BANDRA KURLA COMPLEX, BANDRA EAST, MUMBAI-400051**

**PART – B: FINANCIAL BID**

|                                |
|--------------------------------|
| <b>TENDER ID: MUM201910010</b> |
| <b>DATE : 01.10.2019</b>       |

**TENDER FOR:**

**INTERIOR REPAIR AND REARRANGEMENT WORK OF SHIVAJI CHOWK WARDHA BRANCH**

**TENDER SUBMITTED BY:**

**NAME :** \_\_\_\_\_

**ADDRESS :** \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

**DATE :** \_\_\_\_\_

**TENDER INVITED BY:**

**Vice President & Circle Head,**

**SBI Infra Management Solutions Pvt. Ltd; 3<sup>rd</sup> floor, Circle Office, State Bank of India, Synergy building, C-6, G-Block, Bandra -Kurla complex, Bandra East, Mumbai-400051.**

| S.NO. | PARTICULARS                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | QTY | UNIT | RATE | AMOUNT |
|-------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|------|------|--------|
| 1     | <b>Single window counter</b> : Modification of existing single window counters with 6 mm thick MR grade ply structure with double layer of flexi-ply (12 mm + 6 mm thick) ( the bottom of this niche to have provision of cove lighting with LED strips) on front made of flexi ply and glass ( height 750 mm ) as per design. All exposed external surface finished with 1 mm high gloss laminate and internal surfaces finished with 0.8 mm laminate of approved shade. The work is to be completed with providing of foot rest, key board tray with telescopic arrangement. vertical glass of 12 mm to be fixed at the front of SWO with one horizontal glass ( if required) of approx 150mm with itching and crystal finish etc. complete as per instructions of EIC.Design and detail of the counters shall be as per Bank's new uniform colour, layout & elevation policy available with Bank's Engineer.                                                                                                                             | 6.5 | Rmt  |      |        |
| 2     | <b>Glass partition</b> : Providing and fixing 10 mm thick glass with etching as per design for low height partitions held with SS clits (D brackets). All exposed glass edges with rounded moulding and crystal polish. All exposed woodwork to be finished in 3 coats of French polish/ melamine polish.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | 6   | Sqm  |      |        |
| 3     | <b>Repair of BM table including side credenza irrespective of dimension (minimum size of table 1500*750*750 mm/1800*750*750 mm and side credenza 900*450*750 mm /1050*450*750 mm)</b> : Providing and fixing necessary hardware such as channels, locks,handles,hinges,key board trays,sliding channels etc,as per the site condition.Remodeling the table as per Bank's new uniform colour, layout & elevation policy. Scrapping or making the existing surfce rough. Providing and fixing 6 mm thick plywood on the existing partition/door/table top or side etc.,with necessary adhesive and nails/screws, hardware sets.Thereafter,providing and fixing 4mm thick vineer with PU polish of approved shade & colour, complete in all respect as per the direction of EIC.Polishing the beading etc,as per the site condition to match with the new ambience policy of the Bank. All unexposed surfaces of the table/counters/shelves to be painted with synthetic enamel paint/fixing 0.8 mm thick laminate, as per the site condition. | 1   | No   |      |        |
| 4     | <b>Repair of Officer and Staff table irrespective of dimension ( Minimum table size 1500*750*750/1200*750*750 respectively mm)</b> : Providing and fixing necessary hardware such as channels,locks,handles,hinges,keyboardtrays,sliding channels etc,as per the site condition.Remodeling the table as per Bank's new uniform colour, layout & elevation policy. Scrapping or making the existing surface rough. Providing and fixing 6 mm thick plywood on the existing partition/door/table top or side etc.,with necessary adhesive and nails/screws,hardware sets.Thereafter,providing and fixing 4mm thick veneer with PU polish of approved shade & colour, complete in all respect as per the direction of EIC.Polishing the beading etc,as per the site condition to match with the new ambience policy of the Bank. All unexposed surfaces of the table/counters/shelves to be painted with synthetic enamel paint/fixing 0.8 mm thick laminate,as per the site condition.                                                        | 4   | No   |      |        |

| S.NO. | PARTICULARS                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | QTY | UNIT   | RATE | AMOUNT |
|-------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|--------|------|--------|
| 5     | <b>Repair of side credenza irrespective of dimension ( Minimum size 900*450*750 mm) :</b> Providing and fixing necessary hardware such as channels,locks,handles,hinges,keyboardtrays,sliding channels etc,as per the site condition.Remodeling the table as per Bank's new uniform colour, layout & elevation policy. Scrapping or making the existing surface rough. Providing and fixing 6 mm thick plywood on the existing partition/door/table top or side etc.,with necessary adhesive and nails/screws, hardware sets.Thereafter,providing and fixing 4mm thick veneer with PU polish of approved shade & colour, complete in all respect as per the direction of EIC.Polishing the beading etc,as per the site condition to match with the new ambience policy of the Bank. All unexposed surfaces of the table/counters/shelves to be painted with synthetic enamel paint/fixing 0.8 mm thick laminate, as per the site condition. | 4   | No     |      |        |
| 6     | <b>Repair of existing low height storage (minimum depth 400mm/450 mm):</b> Scrapping or making the existing surface rough. Providing and fixing 6 mm thick plywood on the existing partition/door/table top or side etc., with necessary adhesive and nails/screws,hardwares etc.Thereafter,providing and fixing 1mm thick laminate of approved shade & colour to all exposed surface ,complete in al respect as per the direction of EIC.Polishing the beading etc,as per the site condition to match with the new ambience policy of the Bank.                                                                                                                                                                                                                                                                                                                                                                                            | 9   | Sq Mtr |      |        |
| 7     | <b>Repair of existing low height storage with plywood and veneer (minimum depth 400mm/450 mm) :</b> Scrapping or making the existing surface rough. Providing and fixing <b>6 mm thick plywood</b> on the existing shutter/top or side etc etc., with necessary adhesive and nails/screws,hardwares etc.Thereafter,providing and fixing <b>4 mm thick veneer</b> of approved shade & colour to all exposed surface ,complete in al respect as per the direction of EIC.Polishing the beading etc,as per the site condition to match with the new ambience policy of the Bank. ( mode of measurement will be LxH)                                                                                                                                                                                                                                                                                                                            | 3   | Sq Mtr |      |        |
| 8     | Providing & fixing in position floor spring for receiving glass door of approved make. (DORMA / HETTICH or equivalent)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | 2   | No.    |      |        |
| 9     | Providing and fixing in position door closer of approved make (Hyper / Godrej or equivalent).                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | 7   | No     |      |        |
| 10    | <b>Grahak Mitra Table :</b> Providing & fixing in position Grahak Mitra table of size 1350 mm*750mm*675 mm made of 18 mm MR grade Ply at top, side and front, support along with drawer unit & Key board tray with telescopic arrangement & CPU base resting on foot rest . 18 mm th MR grade ply modesty panel with fixing blue glass. All external surfaces to be finished with 1 mm thick laminate and internal surface finished with 0.8 mm of approved shade and make. including powder coated fittings like sliding channels, for key board & drawers, medium duty hinges for shutter, cable manager. S.S. handles in approved design and size and locks wherever directed in approved make. All exposed plywood edges to be finished with 6mm th. Teak wood beading with french polish in approved shade and                                                                                                                         | 1   | No.    |      |        |

| S.NO. | PARTICULARS                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | QTY | UNIT | RATE | AMOUNT |
|-------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|------|------|--------|
|       | necessary locks to shutters etc. complete in all respects.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |     |      |      |        |
| 11    | <b>Low height &amp; Full height storage:</b> Providing & fixing in position 400mm deep low/full height storage made of 19mm MR grade ply at top, front and side with 12 mm MR grade ply at back, all external faces including back to be finished with 1 mm thick multi-colour laminate at outside and inside finished with 0.8 mm laminate with locking and SS handle arrangement of approved make complete with openable type shutter, beading patti etc. All exposed plywood edges to be finished with 6mm th. Teak wood beading with french polish in approved shade complete in all respect. | 3   | Sqm  |      |        |
| 12    | <b>Vertical blinds :</b> Providing & fixing in position 3" / 4" wide vertical blinds of approved make (Vista / Aerolux) and shade with all accessories and necessary fittings etc.                                                                                                                                                                                                                                                                                                                                                                                                                | 25  | Sq M |      |        |
| 13    | <b>Providing &amp; fixing Panelling</b> out of 6 mm thick ply and 1.0 mm thick laminate of approved shade and make to existing columns , tables , partitions, doors along with necessary accessories required if any etc. complete                                                                                                                                                                                                                                                                                                                                                                | 110 | sq m |      |        |
| 14    | <b>Providing and fixing panelling on External walls / External Rolling Shutters</b> boxing and E lobby. Framing shall consist of Both ways horizontally and vertically on the wall/column with Aluminium Sections of 2"x1" as directed by Bank /Architect. This framing would be covered with 6mm thk. Comm. Ply (In case of wooden frames), finished with 3mm thick exterior grade multi-coloured "Aluminium Composite Panel". The rate shall be inclusive of necessary scaffolding, cut-outs, fixtures and fittings, sealant etc. complete.                                                     | 30  | Sqm  |      |        |
| 15    | <b>Providing and applying acrylic emulsion paint</b> of approved quality, shade and colour in 2 or more coats to achieve desired result including applying one coat of primer of cement paint, preparing the surface by cleaning the dust/dirt by watering/brushing the surfaces, filling in cracks/crevices ,scaffolding at all levels, necessary lead, lifts etc. complete                                                                                                                                                                                                                      | 600 | sq m |      |        |
| 16    | <b>Providing and Laying vitrified tiles</b> of approved make and quality of required size for flooring and skirting in required position laid on bed of C.M.1:4 including cement float, filling joint with white / colour cement slurry, cleaning, curing, complete. 600 mm x 600 mm. size (Basic rate = Rs. 70/- per Sqft) The item rate shall be inclusive of removing the existing flooring & skirting.                                                                                                                                                                                        | 10  | sq m |      |        |
| 17    | <b>Providing and fixing in position 12mm thick toughened glass door</b> including fixed side panel. The door to be fixed with heavy duty Dorma make floor spring, providing 300mm long 30mm dia SS pipe handle and door lock of Ozone/Dorma or equivalent make with necessary cutting chases in floor and restoring the same to its original position complete. Rate to include providing suitable wooden Top and bottom rail, frosted film as per detailed Engineering drawing complete. The item includes removal of existing door and buyback.                                                 | 14  | Sqm  |      |        |

| S.NO. | PARTICULARS                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | QTY   | UNIT   | RATE | AMOUNT |
|-------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|--------|------|--------|
| 18    | <b>Full height glazed/Partly glazed / partly panelled partition</b> : Providing and fixing in position partly glazed & partly panelled partition made of 50 mm x 50mm x 1.2mm medium duty aluminium hollow square pipes framed at 0.60 m. to 0.45 m c/c both ways covered with 6 mm MR grade ply and 1mm multi-colour laminate of approved shade and make with 6 mm thick glass panel with etching as per design and / or necessary beading patti including 3 coats of french polishing including door shutters as per architectural design with heavy duty hinges handles / handles / locks etc. of approved make. | 2     | Sqm    |      |        |
| 19    | <b>Providing &amp; fixing Panelling</b> out of 6 mm thick <b>ply</b> and finished in 4mm thick approved <b>veneer</b> finished with melamine polish existing to columns , tables , partitions, doors along with necessary accessories required if any etc. complete                                                                                                                                                                                                                                                                                                                                                 | 30    | sq m   |      |        |
| 20    | <b>Providing &amp; fixing Panelling in out of 12 mm thick ply and 1.0 mm thick laminate</b> with aluminium frame 50mmx25mmx1.2 mm in walls with screws and finished with approved shade and make to column with accessories and as per Bank engineer's instructions etc. complete                                                                                                                                                                                                                                                                                                                                   | 7.00  | Sq m   |      |        |
| 21    | Full height /Low height Aluminium Composite Panelled partition for server room: Providing and fixing in position fully panelled/partly glazed & partly panelled partition made of 50 mm x 50mm x 1.2mm medium duty aluminium hollow square pipes framed at 0.60 m. to 0.45 m c/c both ways covered with 6 mm MR grade ply and 3 mm aluminium composite panel of approved shade with necessary fittings, silicon sealant and pasting material etc. as per requirement and instructions of Bank's Engineer.                                                                                                           | 10.00 | Sq m   |      |        |
| 22    | Providing and fixing in position 3mm aluminium composite panel of approved shade on existing plywood partition covered with 6 mm MR grade ply with necessary fittings and pasting material of approved shade with necessary fittings, silicon sealant and pasting material etc. as per requirement and instructions of Bank's Engineer                                                                                                                                                                                                                                                                              | 5     | sq m   |      |        |
| 23    | Providing and fixing granite stone to treads and risers of staircase and entrance including all necessary material and labour.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | 2     | Sq MTR |      |        |
| 24    | Providing and fixing frosted film of 3 M/ LG make of approved design pattern, shade and colour to glass panels.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 7     | Sqm    |      |        |
| 25    | Providing and fixing MDF Jali (Mesh) work on walls/columns of approved design with high gloss paints                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | 10    | sq m   |      |        |

|  |                                    |            |  |  |
|--|------------------------------------|------------|--|--|
|  | <b>S U M M A R Y :</b>             |            |  |  |
|  | <b>Total of Interior Work</b>      | <b>Rs.</b> |  |  |
|  | <b>Less discount (if any)</b>      | <b>Rs.</b> |  |  |
|  | <b>Total cost of work Tendered</b> | <b>Rs.</b> |  |  |

SEAL AND SIGNATURE OF THE TENDERER

| S.NO. | PARTICULARS                | QTY | UNIT | RATE | AMOUNT |
|-------|----------------------------|-----|------|------|--------|
|       | Add SGST @ 9%              | Rs. |      |      |        |
|       | Add CGST @ 9%              | Rs. |      |      |        |
|       | FINAL AMOUNT INCLUDING GST | Rs. |      |      |        |

**Total Amount**

**Rupees in words:** \_\_\_\_\_

\_\_\_\_\_  
**Signature & Seal of Contractor**

**Date:** \_\_\_\_\_