



PRICE BID FOR INTERIOR WORK FOR STATE BANK OF INDIA AT BARIPADA MAIN BRANCH .

TENDER ID: BHU201906018

Date: 17.06.19

SL.No.	DESCRIPTION OF ITEMS	UNIT	QTY	RATE	AMOUNT
1	PARTITION WORK.				
A	FULL HEIGHT Partition (Solid/Semi Glazed) Providing and fixing in position partly glazed full Partition work as per drawing ,in frame work at 2'x2' grid (horizontally and vertically) comprising of 2"x1 ½"x1.30mm almunium section and/or as per frame work shown in the drawings with 9 mm BWR/BWP plywood on both sides finished with 1 mm thick laminates of approved shade and colour as shown in drawings. Item to include 8 mm thick glass as per design and fitted with 3-1/4" thick beach wood beading and 2"x2" T.W. member for door sides . All exposed T.W / beading surfaces to be finished in melamine polish as directed including all necessary Stainless Steel finish fittings/hardware and wood preservative paint etc. as per list of approved material and as approved by the Project Consultant/Bank complete in all respects. (Note : In case of false ceiling, the vertical members to be fixed with pucca ceiling but the area of partition payable will be below the false ceiling only)	Sqm.	90.00		
B	LOW HT. HEIGHT Partition (Solid/Semi Glazed) Providing and fixing in position partly glazed 4'-0" HT. Partition work as per drawing ,in frame work at 2'x2' grind (horizontally and vertically) comprising of 2"x1 ½" hevy gazed almunium section and/or as per frame work shown in the drawings with 9 mm BWR/BWP plywood on both sides finished with 1 mm thick laminates of approved shade and colour as shown in drawings. Item to include 12 mm thick glass as per design and fitted with 3-1/4" thick beach wood beading at glass sides All exposed wood. surfaces to be finished in melamine polish of as directed including all necessary Stainless Steel finish fittings/hardware and wood preservative paint etc. as per list of approved material and as approved by the Project Consultant/Bank complete in all respects. It also include Providing , fitting & fixing Pine wood beading (75mmx18 mm or as per design) in low height partition,cash counter front & low height cash counter front fascia with All pine wood beading surfaces to be finished in PU clear polish as directed . The work should be completed as per direction of architect including cost of all labour & material	Sqm.	90.00		
C	Providing, making and fixing in position 12mm thick toughened clear float glass in the front side/transcation side of half height partitions of Single Window Counters of appropriate size . All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets. The cost to include all materials, labour, fixing etching film and cut outs etc., for a neat finished job as per drawings and diretions etc., complete	Sqm.	20.00		
2	DOOR WORK.				
A	Doors – semi glazed standard size 3' x 7 ' Providing and fixing partly glazed doors of sizes as shown in the drawing. The door shutter shutter made out of 50mm x 75mm wood sections for frame work and claddded with 6mm ply (BWR/BWP)on both sides finished with 1mm laminate of approved brand and shade. The edges finished with teak wood lipping. The shutter will have partly glazed 8mm thk float glass incl. etching film of approved pattern and necessary TW wood beading etc mat polished with melamine polish of asian / ici , complete to match the aligned partition elevations designs, the rates are inclusive of cost of including all hardware fittings of S.S. finish, door stopper, door buffer, auto locking SS Knob , 2 Nos. SS 2 ball-bearing hinges, slide bolt, motise lock (7-lever- 8" lock of Godrej / Doorset make) , aldrops etc., all labour, materials, taxes, leads & lift to the place of work executed to the satisfaction of the Architect/EIC	Nos	10.00		
B	Wicket gate (up to 1.5M. ht) Flap doors: Proving and fixing flap door shutter made out of 50mm x 75mm wood sections for frame work 6mm ply fixed on both sides with 1mm laminate including all hardware fittings of S.S. finish, door stopper, door buffer, auto locking SS Knob , 2 Nos. SS 2 ball-bearing hinges, slide bolt all complete as per drawing, design, specification & direction of Engineer-in-charge. The rate shall include cost of all materials, labour, taxes, T&P, transportation, royalties etc.	Sqm.	3.00		
C	Door closer Providing and fixing Godrej / equivalent approved make over head door closers in door with necessary fixtures and fittings etc.	Nos	7.00		
3	FURNITURE WORK.				
A	SWO/Cash Counter				

	<p>Providing and fixing in position 750 mm high single widow counter with side credenza. The rate quoted for SWC shall consist of:</p> <p>a) Basic Structure: 19mm thick BWR/BWP ply for Top (1500 x 825 mm), Front (1500x750 mm), Two sides and one middle member (each 825x750 mm). Design and detail of the counters shall be as per Bank's new uniform colour, layout & elevation policy, with curvature on front made of flexi ply.</p> <p>b) One drawer unit (at every 1500-1800 mm length of counter) of 400mm wide (clear internal size). The chest of Drawer units shall have two smaller draw of equal size on top and one bigger vertical filling drawer at bottom with autolocking push type locks (Godrej/Link) and "C" type SS finish handles. The drawers to be made out of 12mm thick BWR/BWP ply at sides, bottom and rear, 19mm thick BWR /BWP plywood at front side.</p> <p>c) One Side Table (Credenza) of size 1000x450x750)mm with shutter unit of 600mm, with 2 drawers and two openable shutters made with 19mm BWP/BWR plyBoard with necessary hardware viz., 'W' hinges, handles, locks, tower bolts, etc. Ebco/Godrej make telescopic sliding key board tray and a mobile CPU stand.</p> <p>d) The table and credenza top- exposed surfaces shall be cladded with 1 mm thick laminate or equivalent make and shade as approved by EIC in the pattern as directed by the Engineer-in-charge with 6mm Flexi Plywood in curvature (which should be achieved with a frame work of 50mm x 50mm sal wood frame to be fixed from the front modesty panel / apron and the bottom of this niche to have provision of cove lighting with LED strips) and other exposed surface to be finished with 1 mm thk laminate of approved make and shade as directed by EIC.</p> <p>e) All un-exposed surfaces shall be cladded with 0.7 mm thick laminate of approved make and shade.</p> <p>f) Ebco/Godrej make telescopic sliding key board tray and a mobile CPU stand.</p>	Nos	10.00		
B	Branch Manager table with side credenza				
	<p>Providing executive type manager table of 2100x900x750 mm and side credenza 1050x700x400 mm with table top of 25mm th. ply and a front drawer unit consisting 3 Nos of drawer units slides on telescopic slider made up of 19mm thk ply with locking arrangement. The exposed edge surfaces are to be finished with 1.0mm thk laminates as per design of approved shade and the inner surface is finished with 0.7 mm thk laminate. The side credenza will have two drawer unit slides on telescopic slider and two cupboard unit. Quoted rates shall also include cost of polished teak wood moulding (finished 40x20 mm section) to edges of table. top: polished teak wood- lipping (6mm thick) to free edges of block board /plywood surfaces; approved drawer-slides, hinges and locks with keys in duplicate : other necessary hardware and accessories including satin finish S.S handles. knobs and wire - managers , foot rest etc. of approved quality. It also include readymade keyboard of engineering plastic .The keyboard is a pullout type, fixed to channels and screwed to below table top . The CPU stand is made up with 19 mm ply with laminate finish as per design. The work should be mpleted including all labour and material.</p>	Nos	1.00		
C	Manager's table/ Officer table with side credenza				
	<p>Providing executive type manager table of 1500x750x750 mm and side credenza 975x700x400 mm with table top of 19mm th. ply and a front drawer unit consisting 3 Nos of drawer units slides on telescopic slider made up of 19mm thk ply with locking arrangement. The exposed edge surfaces are to be finished with 1.0mm thk laminates as per design of approved shade and the inner surface is finished with 0.7 mm thk laminate. The side credenza will have two drawer unit slides on telescopic slider and two cupboard unit. Quoted rates shall also include cost of polished teak wood moulding (finished 40x20 mm section) to edges of table. top: polished teak wood- lipping (6mm thick) to free edges of block board /plywood surfaces; approved drawer-slides, hinges and locks with keys in duplicate : other necessary hardware and accessories including satin finish S.S handles. knobs and wire - managers , foot rest etc. of approved quality. It also include readymade keyboard of engineering plastic .The keyboard is a pullout type, fixed to channels and screwed to below table top . The CPU stand is made up with 19 mm ply with laminate finish as per design. The work should be mpleted including all labour and material.</p>	Nos	10.00		
D	Repair & Re fabrication of existing Work Stations				
	<p>Repair and re fabrication of existing tables/work stations including side cradenza and drawers by finishing table exposed surface with 4mm commercial ply and 1 mm laminate of approved brand and shade. The inner surface is finished with 0.7 mm th inner laminate wherever required . The table front edges to be provided and fixed with 75 mm x 75 mm thk boader lipping on sides and top finished with 1 mm laminate. Quoted rates shall also include cost of polished teak wood moulding and repair or fixing new hardware /channels /locks , hinges and locks with keys in dupli'cate : other necessary hardware and accessories including satin finish S.S handles. knobs and wire - managers as required to the furnitures The work should be completed including all labour and material.</p>				
	Approx. size of table 1500 x 750 X 750 mrn & credenza 750x900x450 mm	Nos	10.00		
E	Running table				

	Providing and fabricating of running table top of size 2'-0" wide and a front drawer unit consisting 3 Nos of drawer units slides on telescopic slider made up of 19mm th. ply (conforming IS 710) with locking arrangement. The exposed edge surfaces are to be finished with 1.0mm th. laminates as per design of approved shade and the inner surface is finished with 0.7 mm th inner laminate . Quoted rates shall also include cost of polished teak wood moulding (finished 40x20 mm section) to edges of table. top: polished teak wood- lipping (6mm thick) to free edges of block board /plywood surfaces; approved drawer-slides, hinges and locks with keys in duplicate : other necessary hardware and accessories including satin finish S.S handles. knobs and wire - managers, foot rest etc. of approved quality. It also include readymade keyboard of engineering plastic (KD 575 PMT/INNOFIT SYSTEMS OR Equivalent) .The keyboard is a pullout type, fixed to channels and screwed to below table top . The CPU stand is made up with 19 mm ply with laminate finish as per design. The work should be completed including all labour and material.	Rmt.	2.00		
F	Storage Cabinet. Providing and fixing 750mm high and depth of 450 storage cabinet having minimum 2 filing cabinets made out of 19 mm thk. BWP block board. All exposed surfaces shall be clad with 1 mm thick s laminates of approved make and shade except edges . Edges which shall be covered with 1mm thk PVC lipping as directed by the Engineer-in-charge and Cabinet Top is to be provided with 1mm thick laminate. All un-exposed surfaces shall be clad with 0.7 mm thick laminate of approved make and shade storage cabinet should be complete in all respect as per the drawing and direction of Engineer-in-charge including all hardware and locking arrangements. The rate shall include cost of all materials, labour, taxes, T&P, transportation, royalties etc.	Sqm.	12.00		
G	Grahak Mitra Table: Providing curved table of 1500x900x750 mm in curved pattern with table top made of 19mm th. ply and a front drawer unit consisting 3 Nos of drawer units slides on telescopic slider made up of 19mm thk ply with locking arrangement. The exposed edge surfaces are to be finished with 1.0mm thk laminates as per design of approved shade and the inner surface is finished with 0.7 mm thk laminate Quoted rates shall also include cost of polished teak wood moulding (finished 40x20 mm section) to edges of table. top: polished teak wood- lipping (6mm thick) to free edges of block board /plywood surfaces; approved drawer-slides, hinges and locks with keys in duplicate : other necessary hardware and accessories including satin finish S.S handles. knobs and wire - managers , foot rest etc. of approved quality. It also include readymade keyboard of engineering plastic .The keyboard is a pullout type, fixed to channels and screwed to below table top . The CPU stand is made up with 19 mm ply with laminate finish as per design. The work should be completed including all labour and material.	Nos	1.00		
4	PANELLING WORK				
	Providing and fixing wall and column paneling as described below				
	Providing and fixing wall / column paneling with 25mm x 25mmx1.5 mm hollow aluminum square tube frame work covered by 9 mm thick BWP/BWR ply and finished with 1mm thick laminate of approved shade and brand pasted as per design and 100x12mm teak wood skirting polish finished including provisions for providing electrical switch box etc complete as per the tender specification . The work should be executed as per Architect's recommendation & as directed by EIC. Cost includes all type of material, labour , necessary , staging , tools tackles, etc complete	Sqm.	170.00		
5	OTHER FURNISHING WORK				
A	Cheque drop box / Suggestion box Supplying and erecting cheque drop box (overall size 450 mm x 300 mm x 750 mm) made. of 19mm thick phenol formaldehyde bonded plyboard and the curved portion at top made out of 90 mm x 90 mm C.P.teak wood section. A slit opening of 10 mm x 150 mm is to be provided at the top of the box. An openable shutter of 259 mm x 262 mm size made of 19 mm thick phenol formaldehyde bonded block board is to be provided at 1.50 mm above finished floor level. All the exposed timber surfaces including. all free edges are to be finished with 1 mm thick laminate sheet of combination shade .Inner faces of block board surfaces are to be finished with minimum two coats of synthetic enamel. paint of approved shade and quality over a coat of approved primer.Rate .to include cost of necessary hardware fittings e.g. brass hinges, lock, knob etc. of approved design and quality.	Nos	1.00		
B	Writing platform for customers & application form set Providing , fitting , fixing writing platform at a height of 4' above floor level fixed to the wall made out of 19 mm BWP block board with lamination 1 mm tk on top & hard wood beading ducco painted . At least 10 nos vertical slip in chalan shelves attached to wall over writing platform made out of min 4 mm tk acrylic sheets with 6 mm tk ply back up. Each chalan shelf will be of size 6" height , 6" wide .The entire unit will be complete in all respect including materials ,labor etc to the satisfaction of consultant .	Rmt.	2.50		
C	Notice Board Providing soft board covered with approved fabric with wooden frame work and decorative beading for display drawings and documents,with locking arrangement of the sliding shutter made up of 8mm th. float glass. The work should be done including all labour and material.	Sqm.	2.00		

6.0	CORIAN MARBLE SURFACES ON FURNITURE / PARTITIONS : Supplying, Fabrication and Installation of Dupont/Corian/Merino solid surface of 6 mm thk of approved shade . Applied on table Top, Sides and any where wall, Logo etc in place of 1mm thick laminate. The edges to be joined should be straight, smooth and clean. Joints should only be made with joint Adhesive for Dupont Corian. All corners of a cutout must be rounded to 5mm radius and the edges smoothed, both on top & bottom, all around a cutout. "L" & "U" shaped corners need smooth 5mm radius inside corner. All works done to the satisfaction of the Architect/Project Manager. Note:- Work done including labour, material wastage, time limits, required hardware etc.	Sqm.	21.00		
	SUB -TOTAL				
7	(Charge made for existing counters, partitions, glass, tables etc/ The contractor have to quote for dismantling and clearing the salvage materials (except the Work Stations as mentioned in BOQ) from the site as per instruction. (The existing material can not be used in new furnishing work by the contractor)	LS	1	(-)	
			GROSS TOTAL		
Note:	1. GST shall be paid extra as per Govt. of India guidelines				
	2. The tender rates shall include cost towards cleaning of site and shifting of debris within the scope of work of contractor from Bank's premises to municipality				